

Sampling and Analysis Plan
for
Site 2 – Fire Training Area

**Naval Weapons
Industrial Reserve Plant
Calverton, New York**



**Engineering Field Activity Northeast
Naval Facilities Engineering Command**

Contract Number N62472-03-D-0057

Contract Task Order 0004

April 2005

SAMPLING AND ANALYSIS PLAN
SITE 2 – FIRE TRAINING AREA
NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
CALVERTON, NEW YORK
COMPREHENSIVE LONG-TERM
ENVIRONMENTAL ACTION NAVY (CLEAN) CONTRACT


Submitted to:
Engineering Field Activity Northeast
Environmental Branch (Code EV2)
Naval Facilities Engineering Command
10 Industrial Highway, Mail Stop #82
Lester, Pennsylvania 19113-2090

Submitted by:
Tetra Tech NUS, Inc.
600 Clark Avenue, Suite 3
King of Prussia, Pennsylvania 19406-1433

CONTRACT NUMBER N62472-03-D-0057
CONTRACT TASK ORDER 004


APRIL 2005

PREPARED UNDER THE DIRECTION OF:



DAVID D. BRAYACK
PROJECT MANAGER
TETRA TECH NUS, INC.
PITTSBURGH, PENNSYLVANIA

APPROVED FOR SUBMISSION BY:



JOHN J. TREPANOWSKI
PROGRAM MANAGER
TETRA TECH NUS, INC.
KING OF PRUSSIA, PENNSYLVANIA

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE NO.</u>
ACRONYMS.....	v
1.0 INTRODUCTION.....	1-1
1.1 PURPOSE.....	1-1
1.2 INVESTIGATION OBJECTIVE.....	1-2
1.3 FACILITY LOCATION AND DESCRIPTION.....	1-2
1.4 SITE LOCATION AND DESCRIPTION.....	1-4
1.5 WORK PLAN FORMAT.....	1-4
1.6 SCHEDULE.....	1-5
2.0 FIELD TASKS.....	2-1
2.1 SAMPLE AREA.....	2-1
2.2 SOIL SAMPLING AT THE PETROLEUM-CONTAMINATED SOIL AREA.....	2-2
2.3 SOIL SAMPLING AT THE CONCRETE PIT (FORMER BURN PIT).....	2-2
2.4 SOIL SAMPLING BEYOND THE PERIMETER OF THE PETROLEUM- CONTAMINATED SOIL AREA.....	2-3
2.5 FIELD PROCEDURES.....	2-4
2.5.1 Mobilization.....	2-4
2.5.2 Soil Boring, Sampling, and Decontamination.....	2-4
2.5.3 Soil Sample Designation, Handling, Analysis, and Field Documentation.....	2-5
2.5.4 Investigation Derived Wastes Handling.....	2-6
2.5.5 Quality Assurance/Quality Control.....	2-6
 <u>APPENDICES</u>	
A	TINUS STANDARD OPERATING PROCEDURES
B	FIELD FORMS

TABLES**SECTION****PAGE NO.****NUMBER**

2-1	Field Task Summary.....	2-7
2-2	Sample Identification and Analysis Summary.....	2-9
2-3	Summary of Analytical Program.....	2-12

FIGURES**NUMBER**

1-1	General Location Map	1-6
1-2	Site Location Map.....	1-7
1-3	Site 2 Layout Map.....	1-8
2-1	Proposed Soil Boring Sample Locations	2-13

ACRONYMS

bgs	below ground surface
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CLEAN	Comprehensive Long-Term Environmental Action Navy
CMS	Corrective Measures Study
CTO	Contract Task Order
DPT	Direct push technology
FFS	Focused Feasibility Study
FS	Feasibility Study
GOCO	Government-Owned Contractor operated
IAS	Initial Assessment Study
IDW	Investigation-derived waste
IR	Installation Restoration
Navy	United States Department of the Navy
NGC	Northrop Grumman Corporation
NWIRP	Naval Weapons Industrial Reserve Plant
NYCRR	New York Codes, Rules, and Regulations
NYSDEC	New York State Department of Environmental Conservation
PA	Preliminary Assessment
PAH	Polynuclear aromatic hydrocarbons
PCB	Polychlorinated biphenyl
PID	Photo ionization detector
PPE	Personal protection equipment
QA	Quality assurance
QAPP	Quality Assurance Project Plan
QC	Quality control
RCRA	Resource Conservation and Recovery Act
RFA	RCRA Facility Assessment
RFI	RCRA Facility Investigation
RI	Remedial Investigation
SI	Site Investigation
SOPs	Standard operating procedures
SWMUs	Solid waste management units
TAL	Target analyte list
TPH	Total petroleum hydrocarbons
TtNUS	Tetra Tech NUS, Inc.
VOC	Volatile organic compound

1.0 INTRODUCTION

1.1 PURPOSE

This Work Plan for supplemental sampling at Site 2 – Fire Training Area at the Naval Weapons Industrial Reserve Plant (NWIRP) in Calverton, New York was prepared by Tetra Tech NUS, Inc. (TtNUS) under the Comprehensive Long-Term Environmental Action Navy (CLEAN) Contract N63472-03-D-0057, Contract Task Order (CTO) 004.

This work is part of the Navy's Installation Restoration (IR) Program, which is designed to identify contamination of Navy and Marine Corps lands and facilities resulting from past operations and to institute remedial actions as necessary and consists of four distinct stages. Stage 1 is the Preliminary Assessment (PA), which was formerly known as the Initial Assessment Study (IAS). Stage 2 is a Resource Conservation and Recovery Act (RCRA) Facility Assessment-Sampling Visit (RFA), also referred to as a Site Investigation (SI) that augments information collected in the PA. Stage 3 is the RCRA Facility Investigation (RFI) and Corrective Measures Study (CMS), also referred to as a Remedial Investigation (RI) and Feasibility Study (FS) or Focused Feasibility Study (FFS) that characterizes the contamination at a facility and develops options for remediation of the site. Stage 4 is the Corrective Action, also referred to as the Remedial Action, which results in the control or cleanup of contamination at sites. This plan has been prepared under Stage 3.

This work is also being conducted in accordance with the requirements of the New York State Department of Environmental Conservation (NYSDEC) Division of Solid & Hazardous Materials Part 373 Permit issued to the Navy on April 18, 2000 under the NYSDEC implementing regulations [6 New York Codes, Rules, and Regulations (NYCRR) Part 621]. This permit supercedes and replaces the original Part 373 Permit to Operate a Hazardous Waste Storage Facility issued to what was then Grumman Aerospace Corporation on March 25, 1992. The new permit, issued only to the Department of the Navy, deals exclusively with those Solid Waste Management Units (SWMUs) that remain on the former NWIRP Calverton property and any Corrective Actions that may be required to adequately address each IR site. Although the Part 373 Permit is the enforceable document governing the Navy's remedial actions, the NYSDEC State Superfund Group, located in the Albany office, retains primary responsibility for regulatory oversight of the Navy's actions. The Navy has agreed to a request made by the NYSDEC State Superfund Group to utilize terminology associated with the NYSDEC State Superfund program, which is closely related to the Federal Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) Program. The CERCLA terminology parallels the RCRA terminology, and the implementation phases of each have been determined to meet the substantive requirements of both programs and will

also satisfy the Corrective Action requirements set forth in Module III of the Part 373 permit. Site 2 is listed as Classification 2 in the NYSDEC Registry of Inactive Waste Disposal Sites.

1.2 INVESTIGATION OBJECTIVE

The primary objective of this investigation is to define the horizontal and vertical extent of shallow petroleum-contaminated soils. The shallow petroleum-contaminated soils are located at a depth of approximately 1 to 7 feet below ground surface (bgs) and appear to act as a continuing source of groundwater contamination and contribute to a floating free product layer on the groundwater table. Petroleum-contaminated soil is not directly regulated as a contaminant in New York State, but the soil can be regulated through specific constituents of the fuel, including volatile organic compounds (VOCs) and polynuclear aromatic hydrocarbons (PAHs).

In addition to petroleum-based contaminants, other volatile organic compounds including chlorinated compounds, metals, and polychlorinated biphenyls (PCBs) are also present in site soil. Groundwater is located at a depth of approximately 14 to 20 feet bgs and has been observed to fluctuate by several feet over several years. Based on the water table elevation, residual free product at the groundwater table periodically exists as a smear zone below the water table. A floating free product layer is regulated by New York State. A layer of relatively clean soil is believed to exist between the shallow petroleum-contaminated subsurface soil and the free product at the groundwater table.

From the late 1980s and to the mid 1990s, Northrop Grumman operated a free product recovery system and removed approximately 325 gallons (2,400 pounds) of petroleum from the groundwater. From 1995 to 2001, an air sparging/soil vapor extraction (AS/SVE) system was operated. This system destroyed approximately 30,000 pounds of petroleum through biodegradation. In 2001, petroleum saturated soils were identified in shallow soils (up to 7 feet bgs). A floating free product layer remains at the site, but it is thin (less than 1 inch) and can not be effectively recovered.

The results of the investigation will be reported within the Engineering Evaluation/Cost Analysis to be prepared following the establishment of the horizontal and vertical extent of petroleum-contaminated soil.

1.3 FACILITY LOCATION AND DESCRIPTION

NWIRP Calverton is located in Suffolk County, Long Island, New York, approximately 70 miles east of New York City (Figure 1-1). The facility is located within the municipality of Riverhead. The Navy's property totaled approximately 6,000 acres and was formerly a Government-Owned Contractor Operated (GOCO) facility that was operated by the Northrop Grumman Corporation (NGC) until 1996. Of the 6,000 acres of the facility, 3,000 acres were entirely within a fenced boundary. The majority of the industrial

activity was confined to the south-central portion of the fenced area. Currently, NWIRP Calverton consists of four parcels of land totaling approximately 358 acres. Eight Navy IR sites are included within these parcels as follows (Figure 1-2).

Parcel A (32 acres)

Site 2 – Fire Training Area

Parcel B1 (40 acres)

Site 6A – Fuel Calibration Area

Site 10B – Engine Test House

Parcel B2 (131 acres)

Southern Area

Parcel C (10 acres)

Site 7 – Fuel Depot

Site 10A – Jet Fuel Systems Laboratory

Parcel D (145 acres)

Site 1 – Northeast Pond Disposal Area

Site 9 – ECM Area

NWIRP Calverton has been owned by the United States Department of the Navy (Navy) since the early 1950s, at which time the land was purchased from a number of private owners. The facility was expanded in 1958 through additional purchases of privately owned land. Northrop Grumman Corporation (previously Grumman Aerospace Corporation) leased the land and was the sole operator of the facility from its construction until February 1996. In 1996, the land was returned to the Navy.

In September 1998, the majority of the land within the developed section of the facility was transferred to the Town of Riverhead for redevelopment. Because of the need for additional environmental investigation and the potential need for remediation, the Navy retained four parcels of land within the developed section (Figure 1-2).

In September 1999, 2,935 acres of undeveloped land outside the fenced areas were transferred to NYSDEC who will continue to manage the property for resource conservation and recreational uses. An additional 140 acres of the northwest buffer zone were transferred to the Department of Veterans Affairs and will be used for expansion of the Calverton National Cemetery.

NWIRP Calverton was constructed in the early 1950s for use in the development, assembly, testing, refitting, and retrofitting of naval combat aircraft. The facility supported aircraft design and production at the Northrop Grumman's Bethpage facility, which is located in Nassau County, New York.

The majority of industrial activity at the facility was confined to the developed area in the central and south central portion of the facility between the two runways. Industrial activities at the facility were related to the manufacturing and assembly of aircraft and aircraft components. Operations that resulted in hazardous waste generation included but were not limited to metal finishing processes such as metal cleaning and electroplating, other maintenance operations, temporary storage of hazardous waste, fueling operations, and various training operations. The painting of aircraft and components resulted in additional waste generation.

1.4 SITE LOCATION AND DESCRIPTION

Site 2 – Fire Training Area (the focus of this Work Plan) is located on the eastern side of a 9-acre clearing in the south-central area of the NWIRP Calverton facility and is shown on Figure 1-3. A circular, concrete pit in the southeast corner of the clearing was used to contain liquids for fire training exercises. The pit is approximately 80 feet in diameter and is located approximately 500 feet north and 800 feet west of the facility south gate. A 1,000-gallon, steel, aboveground storage tank located approximately 75 feet north of the training pit was used to store fuel. This tank was removed in 1996. A 6,000-gallon storage tank was located north of the training area before 1982. Little information is available on the 6,000-gallon storage tank, other than it was likely an aboveground tank located north of the concrete pit and is no longer present at the site.


The eastern portion of the fire training area was partially excavated at an unknown time. A small embankment up to 4 feet high is located along the eastern edge of the area, and a dirt access road is located along the southern edge. The fire training area is surrounded by woodlands. The majority of the area within the clearing to the west of the concrete pit is covered by marsh-type vegetation, although there is no evidence of standing water. The water table is approximately 14 to 20 feet bgs.

1.5 WORK PLAN FORMAT

Section 1.0 of the Sampling and Analysis Work Plan is this brief introduction. Section 2.0 describes the field tasks and methodologies in detail. Lastly, Appendix A contains the appropriate Standard Operating Procedures (SOPs) needed to perform the identified work, and Appendix B contains the required field forms.

1.6 SCHEDULE

Field activities for the Sampling and Analysis Plan are scheduled to begin in early May 2005 and are anticipated to continue for 3 to 5 days.



DRAWN BY DATE
DLT 12/22/99

CHECKED BY DATE

COST/SCHED-AREA

SCALE
AS NOTED



Tetra Tech NUS, Inc.

GENERAL LOCATION MAP
NWRP CALVERTON, NEW YORK

CONTRACT NO.
7398


OWNER NO.
0270

APPROVED BY DATE

APPROVED BY DATE

DRAWING NO. FIGURE 1-1

REV.
0




P:\GIS\NWIRP_CALVERTON\SURFACE_WATER_HYDROLOGY\APR SITE LOCATION MAP 01/04/01 JAL

9603014



0
REV
DRAWING NO. FIGURE 1-3



SOURCE: THIS DRAWING, INCLUDING THE INFORMATION IT CONTAINS, IS THE PROPERTY OF C.F. BRAUN. IT IS SUBMITTED ONLY IN CONNECTION WITH THE TRANSACTION TO WHICH IT PERTAINS AND MUST NOT BE USED IN ANY MANNER DETRIMENTAL TO THE INTERESTS OF C.F. BRAUN. THE DRAWING IS NOT TO BE COPIED AND MUST BE RETURNED UPON REQUEST.

DRAWN BY	DM	DATE	4/6/05
CHECKED BY		DATE	
REVISED BY		DATE	
SCALE		AS NOTED	



SITE 2 LAYOUT MAP
SITE 2 - FIRE TRAINING AREA
NWIRP, CALVERTON, NEW YORK

LEGEND:	
FT-MW-04	MONITORING WELL
SB-102	SOIL BORING
FT-TP-01	TEST PIT
FT-SS-06	SURFACE SOIL SAMPLE
AI	AIR INJECTION WELL
E1	AIR EXTRACTION WELL
---	UNDERGROUND UTILITIES
---	TREE LINE
NOTE:	
1. TEST PIT LOCATIONS ARE APPROXIMATE.	
GRAPHIC SCALE IN FEET	
CONTRACT NO. 1G10	
OWNER NO. 004	
APPROVED BY	DATE
DRAWING NO. FIGURE 1-3	REV. 0

2.0 FIELD TASKS

2.1 SAMPLE AREA

To facilitate the field investigation, Site 2 is divided into three areas of investigation, as follows: 1) soil sampling at the shallow petroleum-contaminated soil area; 2) soil sampling at the concrete pit (former burn pit); and 3) soil sampling beyond the perimeter of the shallow petroleum-contaminated soil area. The field tasks for each of the sample areas are presented in Sections 2.2, 2.3 and 2.4. The detailed field procedures are presented in Section 2.5 and the SOPs are provided in Appendix A.

Table 2-1 provides a summary of the field tasks with rationale. Table 2-2 provides a summary of soil boring identification number, sample identification, sample depths, and analyses including quality assurance (QA) and quality control (QC) samples. Lastly, Table 2-3 summarizes the analytical methods for each analysis, bottleware, preservation requirements, holding times, and number of samples. Figure 2-1 presents the investigation area and proposed sample locations.

2.2 SOIL SAMPLING AT THE SHALLOW PETROLEUM-CONTAMINATED SOIL AREA

The objectives of the work within the shallow petroleum-contaminated soil area are to confirm the presence of petroleum and individual contaminants and to establish the horizontal and vertical extent of the petroleum-contaminated soil. Four soil borings will be installed into the water table in this area, (approximately 16 to 20 feet below ground surface (bgs)) (FT-SB-201 to FT-SB-204). Because of recent precipitation events, the free product normally at or above the water table may be present as a smear zone below the water table. One or more of the initial borings may be installed up to 24 feet below ground surface to determine the presence and depth of a smear zone.

Continuous soil samples will be taken using direct push technology (DPT). Table 2-2 summarizes the samples and sampling depths for the proposed borings in this area. Based on field observations [visual and photo ionization detector (PID) readings], three samples from each boring (12 total) will be submitted to an analytical laboratory for TPH analyses. The samples will be identified in the field to represent subsurface shallow petroleum-contaminated soils, free product at the water table, and from the soil interval in between these two units. Sample depths for chemical testing will not necessarily correspond to 4-foot intervals associated with the macro core samplers.

In addition, four soil samples that are representative of the shallow petroleum-contaminated soils will be analyzed for VOCs, PAHs, PCB/pesticides, and TAL metals. The proposed boring locations are identified on Figure 2-1.

Following laboratory analysis of the collected soil samples, the analytical data will be used to classify the petroleum-contaminated soil for reuse/disposal. In particular, petroleum-contaminated soils are commonly reused on Long Island at asphaltting plants. PCBs in the soil limit this potential reuse and would require the soils to be disposed elsewhere in a landfill.

Analytical data received from the laboratory will be subjected to a cursory validation process. A full data validation process is not required for this data since results will not be use to establish risk or clean up goals.

2.3 SOIL SAMPLING AT THE CONCRETE PIT (FORMER BURN PIT)

The objectives of the work within the concrete pit are similar to that for the shallow petroleum-contaminated soils described in Section 2.2 and include confirmation of petroleum and individual contaminants in this area and to establish the horizontal and vertical extent of the petroleum-contaminated soil.

Another objective of work in this area will be to estimate the thickness of the concrete. It is anticipated that the concrete pit will be demolished in the near future, and an accurate quantity estimate will be required to support this effort. As such, holes will be drilled through the concrete at the boring locations, and the thickness of concrete will be measured.

Four soil borings will be installed in this area into the water table (approximately 16 to 20 feet bgs)(FT-SB-205 to FT-SB-208). Continuous soil samples will be taken using DPT. Table 2-2 summarizes the samples and sampling depths for the proposed borings in this area. Based on field observations approximately 3 samples per boring (12 total) will be submitted an analytical laboratory for TPH analysis. In addition, one soil sample that is representative of the shallow petroleum-contaminated soils will be analyzed for VOCs, PAHs, PCB/pesticides, and TAL metals. The proposed boring locations are identified on Figure 2-1.

The data will be evaluated as indicated in Section 2.2.

2.4 SOIL SAMPLING BEYOND THE PERIMETER OF THE SHALLOW PETROLEUM-CONTAMINATED SOIL AREA

The primary objective of work in this area is to evaluate the potential for TPH, VOC, PAH, PCB/pesticide, and metal contamination to extend horizontally beyond the extent of the shallow petroleum-contaminated soils. In addition, surface soils samples will be tested for PAHs, PCB/pesticides, and metal contamination to evaluate potential risks to human health and the need for remedial activities of the surface soils. The boring locations were selected to be beyond the current estimate of the extent of the shallow petroleum-contaminated soil area.

Fourteen soil boring locations are currently shown to be investigated (FT-SB-209 to FT-SB-222). Based on findings from these 14 soil borings, as well as the findings from the other eight soil borings, additional soil borings may be installed.

The soil borings will normally be installed into the water table. In the event that free product is not observed at the water table, or in a smear zone, in an adjacent boring (FT-SB-201 to FT-SB-208), some of the borings may be terminated at approximately 8 feet bgs. As with the other soil borings at the site, continuous soil cores will be taken using DPT.

If, based on field screening, the proposed borings are beyond the field observed extent of shallow petroleum-contaminated soils, then a sample will be collected from 1 to 4 feet bgs and submitted for chemical testing. If soil in the upper 8 feet of these borings shows field evidence of significant contamination (staining and elevated PID reading), then soil samples will not be collected from that soil boring and an additional soil boring will be installed at a greater distance outward from the petroleum-contaminated soil. Samples for analytical testing in these borings should not exhibit field evidence of contamination. Soil samples will only be collected from nine of the 14 perimeter borings shown.

Surface soil samples will be collected at five soil boring locations (FT-SS-209, -211, -212, -214, and -215). The samples will be collected from the ground surface to a depth of one foot. A separate sample trowel will be used to collect these samples.

Based on historical data, it is not certain whether the extent of shallow petroleum-contaminated soil or the extent of the free product at the groundwater table is greater. Since defining the extent of the shallow petroleum-contaminated soil is a primary objective, soil borings will continue outward until clean shallow soils are encountered. If time permits, additional borings may be installed to better define the extent of

free product (or smear zone) at the groundwater table and/or may be installed within the existing soil boring sampling grid to potentially reduce the estimated area of contaminated soils.

Table 2-2 summarizes the samples and sampling depths for the proposed borings in this area. Samples will be submitted to an analytical laboratory for TPH, VOC, PAH, PCB/pesticide, and TAL metal analysis. The proposed borings locations are identified on Figure 2-1. Based on field observations, additional borings may be installed either closer to the area of known petroleum contamination or further out if contamination is observed in a specific boring.

The data will be evaluated as indicated in Section 2.2.

2.5 FIELD PROCEDURES

All field procedures shall be conducted in accordance with the site Health and Safety Plan and the site Quality Assurance Project Plan (QAPP) (both documents are provided under separate cover).

The field activities will include the following tasks:

- Mobilization
- Soil Boring, Sampling, and Decontamination
- Soil Sample Designation, Handling, Analysis, and Field Documentation
- Investigation Derived Wastes Handling
- Quality Assurance/Quality Control

The following sections describe these activities.

2.5.1 Mobilization

TtNUS will prepare specifications and obtain subcontractors for the drilling and analytical work associated with this Work Plan. All field team members will review this work plan and the Site Health and Safety Plan (provided under separate cover) prior to initiation of the soil sampling event. Lastly, a field team orientation meeting will be held to familiarize personnel with the scope of the field activities.

2.5.2 Soil Boring, Sampling, and Decontamination

The required soil samples will be collected using direct push methods. Direct push drilling will be performed in accordance with the methods identified in TtNUS SOP GH-1.3 "Soil and Rock Drilling Methods" and TtNUS SOP SA-2.5 "Direct Push Technology" provided in Appendix A. Soil samples will be

collected in accordance with the selected drilling technique. TtNUS sampling SOP SA-1.3 "Soil Sampling" is provided in Appendix A. Downhole sampling equipment such as rods and macro cores shall be decontaminated between each drilling location. Decontamination will be performed in accordance with the procedures presented in TtNUS SOP SA-7.1 "Decontamination of Field Equipment" provided in Appendix A.

2.5.3 Soil Sample Designation, Handling, Analysis, and Field Documentation

Soil Sample Designation

Table 2-2 presents the anticipated samples to be collected during this soil sampling event. The sampling nomenclature assumes that multiple samples will be collected from the same boring at varying depths and some of these samples will be shipped to an analytical laboratory for analysis. The sample designations identified in Table 2-2 assumes that samples will be collected using continuous core sampling.

Each sample designation identifies the site from which the sample was collected, the soil boring from which the sample was collected, and the depth from which the sample was collected. As an example, sample identification number FTSB201-0408 indicates that the soil sample was collected from Fire Training (FT), from soil boring 201 (SB201), and was collected from a depth of 4 to 8 feet (0408).

Soil Sample Handling

Handling soil samples includes the field-related consideration of the selection of sample containers, preservatives, allowable holding times, sample shipping and sample custody. Sample identification, packaging, shipping, and sample custody requirements are outlined in TtNUS SOP SA-6.1 "Non-Radiological Sample Handling" provided in Appendix A and within the approved QAPP. Summaries of sample containers, volume requirements, preservatives, allowable holding times, and analysis requested are provided in Table 2-3.

Sample Analysis

The proposed sample analyses are based on the past contaminant detections and anticipated future land use at each area. Samples submitted for laboratory for analysis will be analyzed for the compounds identified on Table 2-2. In addition to the soil samples collected, rinse blanks and field duplicate samples will also be analyzed for these parameters for quality control purposes. Each analytical sample will be analyzed with a 21-day turn-around time, however, the results will not be considered final until the data has been validated.

Field Documentation

Sample documentation consists of the completion of chain-of-custody reports and matrix-specific log sheets. The log sheets will be used as confirmation of the presence of petroleum-contaminated soil based on visual classification and PID readings. In addition, the Master Site Logbook, filled out in accordance with SOP SA-6.3 "Field Documentation," provided in Appendix A, serves as the overall record of field activities. Information to be recorded daily in the Master Site Logbook includes weather conditions, identity and arrival and departure times of personnel, management issues, etc. Anticipated field forms for this sampling event are provided in Appendix B.

2.5.4 Investigation Derived Wastes Handling

Personal Protective Equipment (PPE) and other miscellaneous trash visibly free of soil will be bagged and removed from the site by TtNUS for disposal as general refuse. Excess soil cuttings and decontamination fluids will be drummed. Drums will be staged for characterization and off-site disposal. The staging area will be determined by the Navy. No other investigation derived waste (IDW) will be generated during the course of the work.

2.5.5 Quality Assurance/Quality Control

Quality assurance/quality control includes assurances of correct field equipment calibration and adequate collection of QA/QC samples.

All field equipment (PID) will be calibrated according to the manufacturer recommendations and at a frequency recommended by the manufacturer.

QA/QC samples will be collected at the rate indicated in Table 2-2 and the QAPP established for field work at Calverton. Rinse or Equipment Blanks will be collected once every other day.

TABLE 2-1

**FIELD TASKS SUMMARY
SOIL INVESTIGATION
SITE 2 – FIRE TRAINING AREA
NWIRP CALVERTON, NEW YORK
PAGE 1 OF 2**

LOCATION	ACTIVITY	SAMPLE ANALYSES	RATIONAL
Soil Sampling at the Shallow ¹ Petroleum-Contaminated Soil Area	<ul style="list-style-type: none"> Install 4 soil borings into groundwater (approximately 16 to 20 feet bgs). Borings into the water table will evaluate possible presence of a smear zone located below the water table. Collect a continuous soil core from each boring. From the continuous soil core, form three samples from each boring to be submitted to the laboratory. Based on field screening², samples should correspond to: 1) shallow petroleum-contaminated soil; 2) soil underlying the shallow petroleum-contaminated soil; and 3) if floating free product is reached at the groundwater table or slightly below the groundwater table. 	<p>12 samples visually identified in the field for²:</p> <ul style="list-style-type: none"> TPH - DRO/GRO <p>4 shallow petroleum-contaminated samples² for:</p> <ul style="list-style-type: none"> PCB/pesticides VOCs PAHs TAL metals 	<ul style="list-style-type: none"> TPH data will be used to define the quantity of petroleum contamination present. The AS/SVE system did not fully address contamination in this area⁴. Sampling at the three layers will confirm the suggested contamination in the area. Other analytes will be used to characterize petroleum-contaminated soil for reuse/disposal.
Soil Sampling at the Concrete Pit (Former Burn Pit)	<ul style="list-style-type: none"> Install 4 soil borings into groundwater (approximately 16 to 20 feet bgs). Borings into the water table will evaluate possible presence of a smear zone located below the water table. Collect a continuous soil core from each boring. From the continuous soil core, form three samples from each boring to be submitted to the laboratory. Based on field screening², samples should correspond to: 1) shallow petroleum-contaminated soil; 2) soil underlying the shallow petroleum-contaminated soil; and 3) if floating free product is reached at the groundwater table or slightly below the groundwater table. 	<p>12 samples visually identified in the field for²:</p> <ul style="list-style-type: none"> TPH - DRO/GRO <p>1 shallow petroleum-contaminated samples² for:</p> <ul style="list-style-type: none"> PCB/pesticides VOCs PAHs TAL Metals 	<ul style="list-style-type: none"> The presence of petroleum contaminated soil beneath the concrete pit is unknown. The AS/SVE system may not have fully addressed contamination in this area⁴. The thickness of the concrete is unknown. Sampling at the three layers will confirm the suggested contamination in the area.

TABLE 2-1

**FIELD TASKS SUMMARY
SOIL INVESTIGATION
SITE 2 – FIRE TRAINING AREA
NWIRP CALVERTON, NEW YORK
PAGE 2 OF 2**

LOCATION	ACTIVITY	SAMPLE ANALYSES	RATIONAL
Soil Sampling Beyond the Perimeter of the Petroleum-Contaminated Soil Area	<ul style="list-style-type: none"> Install 14 soil borings beyond the extent of the currently estimated petroleum-contaminated soil area. Boring will normally be installed into the water table. Based on the absence of free product at the groundwater table in nearby soil borings, some boring may be installed to a depth of 8 feet bgs. Samples for laboratory testing are to be limited to borings that do not show field screening evidence of significant petroleum contamination. Install additional borings as needed to define the horizontal extent of petroleum-contaminated soils. Collect surface soil samples at 5 locations. 	9 subsurface soil samples and 5 surface soil samples: <ul style="list-style-type: none"> TPH - DRO/GRO PAH PCB/pesticides TAL metals VOCs³ 	<ul style="list-style-type: none"> The horizontal extent of shallow petroleum-contaminated soil is unknown. Borings will be installed to delineate the horizontal extent of this contamination. The AS/SVE system actively treated soil contamination in this area⁴. The presence and horizontal extent of PAH, PCB/pesticide, VOC, and metal contamination is unknown. Sample data will be used to define the maximum extent of remediation. Residual contamination in surface soil is unknown.

1. The shallow petroleum-contaminated soil was observed in test pits in 2001. The layer was observed to start at 0.5 to 2 feet bgs and extend to a depth of 2 to 7 feet bgs.
2. The shallow petroleum-contaminated is characterized in the field by a black organic-rich appearance and/or PID readings greater than 25 ppm.
3. Subsurface soil samples only.
4. An Air Sparging/Soil Vapor Extraction (AS/SVE) system operated at the site from 1995 to 2000. This system removed volatile organic compounds and promoted biological degradation of organics at the site.

TPH: Total petroleum hydrocarbons
 DRO: Diesel range organics
 GRO: Gasoline range organics
 PAH: Polynuclear aromatic hydrocarbons
 PCB: Polychlorinated biphenyl
 TAL: Target Analyte List

TABLE 2-2

SAMPLE IDENTIFICATION AND ANALYSIS SUMMARY
SOIL INVESTIGATION
SITE 2 - FIRE TRAINING AREA
MWIRP CALVERTON, NEW YORK
PAGE 1 OF 3

BORING NUMBER	SAMPLE IDENTIFICATION ⁽¹⁾	SAMPLE ANALYSIS				
		Metals	PAHs	PCB/ Pesticide	TPH - DRO/GRO	VOC

Soil Sampling at the Shallow Petroleum-Contaminated Soil Area						
FT-SB-201 ²	FTSB201-XXXX	X	X	X	X	X
	FTSB201-XXXX	--	--	--	X	--
	FTSB201-XXXX	--	--	--	X ²	--
FT-SB-202 ²	FTSB202-XXXX	X	X	X	X	X
	FTSB202-XXXX	--	--	--	X	--
	FTSB202-XXXX	--	--	--	X ²	--
FT-SB-203 ²	FTSB203-XXXX	X	X	X	X	X
	FTSB203-XXXX	--	--	--	X	--
	FTSB203-XXXX	--	--	--	X ²	--
FT-SB-204 ²	FTSB204-XXXX	X	X	X	X	X
	FTSB204-XXXX	--	--	--	X	--
	FTSB204-XXXX	--	--	--	X ²	--

Soil Sampling at the Concete Pit (Former Burn Pit)						
FT-SB-205 ²	FTSB205-XXXX	--	--	--	X	--
	FTSB205-XXXX	--	--	--	X	--
	FTSB205-XXXX	--	--	--	X ²	--
FT-SB-206 ²	FTSB206-XXXX	--	--	--	X	--
	FTSB206-XXXX	--	--	--	X	--
	FTSB206-XXXX	--	--	--	X ²	--
FT-SB-207 ²	FTSB207-XXXX	--	--	--	X	--
	FTSB207-XXXX	--	--	--	X	--
	FTSB207-XXXX	--	--	--	X ²	--
FT-SB-208 ²	FTSB208-XXXX	X	X	X	X	X
	FTSB208-XXXX	--	--	--	X	--
	FTSB208-XXXX	--	--	--	X ²	--

TABLE 2-2

SAMPLE IDENTIFICATION AND ANALYSIS SUMMARY
SOIL INVESTIGATION
SITE 2 - FIRE TRAINING AREA
MWIRP CALVERTON, NEW YORK
PAGE 2 OF 3

BORING NUMBER	SAMPLE IDENTIFICATION ⁽¹⁾	SAMPLE ANALYSIS				
		Metals	PAHs	PCB/ Pesticide	TPH - DRO/GRO	VOC
Soil Sampling Beyond the Perimeter of the Petroleum-Contaminated Soil Area						
FT-SB-209	FTSS209-0001	X	X	X	X	--
	FTSB209-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-210	FTSB210-XXXX	X	X	X	X	--
FT-SB-211	FTSS211-0001	X	X	X	X	--
	FTSB211-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-212	FTSS212-0001	X	X	X	X	--
	FTSB212-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-213	FTSB213-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-214	FTSS214-0001	X	X	X	X	--
	FTSB214-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-215	FTSS215-0001	X	X	X	X	--
	FTSB215-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-216	FTSB216-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-217	FTSB217-XXXX	X ³	X ³	X ³	X ³	X ³
FT-SB-218	FTSB218-XXXX	X ⁶	X ⁶	X ⁶	X ⁶	X ⁶
FT-SB-219	FTSB219-XXXX	X ⁶	X ⁶	X ⁶	X ⁶	X ⁶
FT-SB-220	FTSB220-XXXX	X ⁶	X ⁶	X ⁶	X ⁶	X ⁶
FT-SB-221	FTSB221-XXXX	X ⁶	X ⁶	X ⁶	X ⁶	X ⁶
FT-SB-222	FTSB222-XXXX	X ⁶	X ⁶	X ⁶	X ⁶	X ⁶
QA/QC Samples						
Rinse Blank	RB-042905 ⁴	X	X	X	X	X
Duplicate	DUP-042905-01 ⁵	X	X	X	X	X

-- Analysis not performed

- 1 Sample depths are to be entered in feet, e.g., 0406 indicates a sample collected from 4 to 6 feet below the ground surface.
- 2 The first sample in each boring should consist of shallow petroleum-contaminated soil and be collected between 1 and 7 feet bgs. The second sample in each boring should be collected approximately 2 to 4 feet below the bottom of the petroleum-contaminated soil. If petroleum contaminated soils are not observed in the field, then the second sample in each boring should not be submitted for chemical testing. The third sample in each boring should consist of petroleum-contaminated soil near the water table. If petroleum contaminated soil is not observed at the water table, then a sample should not be submitted for chemical testing.
- 3 Sample for laboratory analysis should only be collected if boring does not exhibit field evidence of petroleum contamination. Sample should be collected at a depth interval similar to shallow petroleum contaminated soils observed at the nearest boring.

TABLE 2-2

SAMPLE IDENTIFICATION AND ANALYSIS SUMMARY
SOIL INVESTIGATION
SITE 2 - FIRE TRAINING AREA
MWIRP CALVERTON, NEW YORK
PAGE 3 OF 3

- 4 Rinse blanks are labeled using RB to indicate rinse blank and the date to indicate the day on which the rinse blank was collected (e.g. 090105 represents September 1, 2005).
- 5 Duplicate samples are labeled using DUP to indicate duplicate, the date to indicate the day on which the duplicate was collected (e.g. 090105 represents September 1, 2005), and a number to represent the sequential number collected that day (e.g. 01 indicates the first duplicate sample collected on the indicated date).
- 6 Samples from these borings may be submitted if needed to define extent of contamination in this area.


TABLE 2-3

**SUMMARY OF ANALYTICAL PROGRAM
SOIL INVESTIGATION
SITE 2 - FIRE TRAINING AREA
NWIRP CALVERTON, NEW YORK**

ANALYSIS	MATRIX	METHOD	PRESERVATION	HOLDING TIME	NUMBER OF SAMPLES	FIELD BLANKS ⁽²⁾	RINSE BLANKS ⁽³⁾	DUPLICATE SAMPLES ⁽⁴⁾	MS/MSDs ⁽⁵⁾	TOTAL NUMBER OF SAMPLES ⁽⁶⁾
FIXED-BASED LABORATORY ANALYSIS										
TAL Metals	SOIL	SW-846 6010B/7000A series	Cool to 4° C	Analysis: 180 days except mercury which is 28 days	19	1	2	2	1	24
PAHs	SOIL	SW-846 8310 or 270CSIM	Cool to 4° C	Extraction: 14 days Analysis: 40 days	19	1	2	2	1	24
PCBs/ Pesticide	SOIL	SW-845 8082/ 8081A	Cool to 4° C	Extraction: 14 days Analysis: 40 days	19	1	2	2	2	24
TPH-DRO/GRO	SOIL	SW-846 8015B/ SW-846 8015B	Cool to 4° C	Analysis: 28 days	38	1	2	4	2	45
VOC	SOIL	SW-846 5035/8260B	Cool to 4° C	Extraction: 48 hours Analysis: 14 days	14	1	2	2	1	19

1. Bottleware requirements may differ in number and size, depending on the requirements of the contracted laboratory.
2. Field blanks are quality assurance (QA) samples collected at a rate of one field blank per week of sampling.
3. Rinse blanks are QA samples collected by running laboratory provided water over decontaminated sampling equipment. Samples are collected at a rate of one rinse blank every two days. Number presented on table based on the number of days scheduled for the soil investigation (numbers are subject to change).
4. Duplicate samples are single samples split into equal portions during the single act of sampling. Duplicate samples will be collected at a rate of 1 duplicate for every 10 environmental samples.
5. MS/MSDs (matrix spike/matrix spike duplicate) samples are QA/Quality Control (QC) checks. These samples require 3 times the normal sample volume and are performed by the analytical laboratory at a rate of one for every 20 environmental samples.
6. Total number of samples excludes MS/MSD samples.

APRIL 2005



- LEGEND:**
- FT-MW-01-S MONITORING WELL (1994,1995)
 - FT-SB-217 PROPOSED SOIL BORING LOCATION
 - SB-102 SOIL BORING
 - FT-TP-01 TEST PIT
 - FT-SS-06 SURFACE SOIL SAMPLE
 - △ I1 AIR INJECTION WELL
 - E1 AIR EXTRACTION WELL
 - UNDERGROUND UTILITIES
 - ~~~~~ TREE LINE
 - LIMIT OF PETROLEUM CONTAMINATED SOIL (DASHED WHERE ESTIMATED)
- NOTES:**
1. TEST PIT LOCATIONS ARE APPROXIMATE.
 2. IF OBSTRUCTIONS PROHIBIT INSTALLATION OF FT-SB-207, LOCATION WILL BE MOVED APPROXIMATELY 25 FEET WEST.

SOURCE: THIS DRAWING, INCLUDING THE INFORMATION IT CONTAINS, IS THE PROPERTY OF C.F. BRAUN. IT IS SUBMITTED ONLY IN CONNECTION WITH THE TRANSACTION TO WHICH IT PERTAINS AND MUST NOT BE USED IN ANY MANNER DETRIMENTAL TO THE INTERESTS OF C.F. BRAUN. THE DRAWING IS NOT TO BE COPIED AND MUST BE RETURNED UPON REQUEST.

DRAWN BY	DM	DATE	4/5/05
CHECKED BY		DATE	
REVISED BY		DATE	
SCALE AS NOTED			



PROPOSED SOIL BORING SAMPLE LOCATIONS
SITE 2 - FIRE TRAINING AREA
NWRP, CALVERTON, NEW YORK

CONTRACT NO.	IGIO
OWNER NO.	004
APPROVED BY	DATE
DRAWING NO.	FIGURE 2-1
REV.	0

APPENDIX A

TtNUS STANDARD OPERATING PROCEDURES

TtNUS SOP GH-1.3 – Soil and Rock Drilling Methods

TtNUS SOP SA-2.5 – Direct Push Technology

TtNUS SOP SA-1.3 – Soil Sampling

TtNUS SOP SA-7.1 – Decontamination of Field Equipment

TtNUS SOP SA-6.1 – Non-Radiological Sample Handling

TtNUS SOP SA-6.3 – Field Documentation

TtNUS SOP GH-1.3 – Soil and Rock Drilling Methods



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number	GH-1.3	Page	1 of 26
Effective Date	06/99	Revision	1
Applicability	Tetra Tech NUS, Inc.		
Prepared	Earth Sciences Department		
Approved	D. Senovich <i>ds</i>		

Subject
SOIL AND ROCK DRILLING METHODS

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 PURPOSE	3
2.0 SCOPE	3
3.0 GLOSSARY.....	3
4.0 RESPONSIBILITIES	3
5.0 PROCEDURES	4
5.1 GENERAL.....	4
5.2 DRILLING METHODS	4
5.2.1 Continuous-Flight Hollow-Stem Auger Drilling	5
5.2.2 Continuous-Flight Solid-Stem Auger Drilling	6
5.2.3 Rotary Drilling	7
5.2.4 Rotosonic Drilling	9
5.2.5 Reverse Circulation Rotary Drilling	9
5.2.6 Drill-through Casing Driver	10
5.2.7 Cable Tool Drilling	11
5.2.8 Jet Drilling (Washing)	12
5.2.9 Drilling with a Hand Auger	13
5.2.10 Rock Drilling and Coring	13
5.2.11 Drilling & Support Vehicles	14
5.2.12 Equipment Sizes.....	15
5.2.13 Estimated Drilling Progress	16
5.3 PREVENTION OF CROSS-CONTAMINATION	16
5.4 CLEANOUT OF CASING PRIOR TO SAMPLING	17
5.5 MATERIALS OF CONSTRUCTION	18
5.6 SUBSURFACE SOIL SAMPLES	19
5.7 ROCK SAMPLING (CORING) (ASTM D2113-83)	19
5.7.1 Diamond Core Drilling.....	23
5.7.2 Rock Sample Preparation and Documentation	23
6.0 REFERENCES	24

ATTACHMENT

A	DRILLING EQUIPMENT SIZES	25
---	--------------------------------	----

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 2 of 26
	Revision 1	Effective Date 06/99

FIGURE

NUMBER

PAGE

1 STANDARD SIZES OF CORE BARRELS AND CASING 20

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 3 of 26
	Revision 1	Effective Date 06/99

1.0 PURPOSE

The purpose of this procedure is to describe the methods and equipment necessary to perform soil and rock borings and identify the equipment, sequence of events, and appropriate methods necessary to obtain soil, both surface and subsurface, and rock samples during field sampling activities.

2.0 SCOPE

This guideline addresses most of the accepted and standard drilling techniques, their benefits, and drawbacks. It should be used generally to determine what type of drilling techniques would be most successful depending on site-specific geologic conditions and the type of sampling required.

The sampling methods described within this procedure are applicable to collecting surface and subsurface soil samples, and obtaining rock core samples for lithologic and hydrogeologic evaluation, excavation/foundation design, remedial alternative design and related civil engineering purposes.

3.0 GLOSSARY

Rock Coring - A method in which a continuous solid cylindrical sample of rock or compact rock-like soil is obtained by the use of a double tube core barrel that is equipped with an appropriate diamond-studded drill bit which is advanced with a hydraulic rotary drilling machine.

Wire-Line Coring - As an alternative to conventional coring, this technique is valuable in deep hole drilling, since this method eliminates trips in and out of the hole with the coring equipment. With this technique, the core barrel becomes an integral part of the drill rod string. The drill rod serves as both a coring device and casing.

4.0 RESPONSIBILITIES

Project Manager - In consultation with the project geologist, the Project Manager is responsible for evaluating the drilling requirements for the site and specifying drilling techniques that will be successful given the study objectives and the known or suspected geologic conditions at the site. The Project Manager also determines the disposal methods for products generated by drilling, such as drill cuttings and well development water, as well as any specialized supplies or logistical support required for the drilling operations.

Field Operations Leader (FOL) - The FOL is responsible for the overall supervision and scheduling of drilling activities, and is strongly supported by the project geologist.

Project Geologist - The project geologist is responsible for ensuring that standard and approved drilling procedures are followed. The geologist will generate a detailed boring log for each test hole. This log shall include a description of materials, samples, method of sampling, blow counts, and other pertinent drilling and testing information that may be obtained during drilling (see SOPs SA-6.3 and GH-1.5). Often this position for inspecting the drilling operations may be filled by other geotechnical personnel, such as soils and foundation engineers, civil engineers, etc.

Determination of the exact location for borings is the responsibility of the site geologist. The final location for drilling must be properly documented on the boring log. The general area in which the borings are to be located will be shown on a site map included in the Work Plan and/or Sampling and Analysis Plan.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 4 of 26
	Revision 1	Effective Date 06/99

Drilling Subcontractor - Operates under the supervision of the FOL. Responsible for obtaining all drilling permits and clearances, and supplying all services (including labor), equipment and material required to perform the drilling, testing, and well installation program, as well as maintenance and quality control of such required equipment except as stated in signed and approved subcontracts.

The driller must report any major technical or analytical problems encountered in the field to the FOL within 24 hours of determination, and must provide advance written notification of any changes in field procedures, describing and justifying such changes. No such changes shall be made unless requested and authorized in writing by the FOL (with the concurrence of the Project Manager). Depending on the subcontract, the Project Manager may need to obtain written authorization from appropriate administrative personnel before approving any changes.

The drilling subcontractor is responsible for following decontamination procedures specified in the project plan documents. Upon completion of the work, the driller is responsible for demobilizing all equipment, cleaning up any materials deposited on site during drilling operations, and properly backfilling any open borings.

5.0 PROCEDURES

5.1 General

The purpose of drilling boreholes is:

- To determine the type, thickness, and certain physical and chemical properties of the soil, water and rock strata which underlie the site.
- To install monitoring wells or piezometers.

All drilling and sampling equipment will be cleaned between samples and borings using appropriate decontamination procedures as outlined in SOP SA-7.1. Unless otherwise specified, it is generally advisable to drill borings at "clean" locations first, and at the most contaminated locations last, to reduce the risk of spreading contamination between locations. All borings must be logged by the site geologist as they proceed (see SOPs SA-6.3 and GH-1.5). Situations where logging would not be required would include installation of multiple well points within a small area, or a "second attempt" boring adjacent to a boring that could not be continued through resistant material. In the latter case, the boring log can be resumed 5 feet above the depth at which the initial boring was abandoned, although the site geologist should still confirm that the stratigraphy at the redrilled location conforms essentially with that encountered at the original location. If significant differences are seen, each hole should be logged separately.

5.2 Drilling Methods

The selected drilling methods described below apply to drilling in subsurface materials, including, but not limited to, sand, gravel, clay, silt, cobbles, boulders, rock and man-made fill. Drilling methods should be selected after studying the site geology and terrain, the waste conditions at the site, and reviewing the purpose of drilling and the overall subsurface investigation program proposed for the site. The full range of different drilling methods applicable to the proposed program should be identified with final selection based on relative cost, availability, time constraints, and how well each method meets the sampling and testing requirements of the individual drilling program.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 5 of 26
	Revision 1	Effective Date 06/99

5.2.1 Continuous-Flight Hollow-Stem Auger Drilling

This method of drilling consists of rotating augers with a hollow stem into the ground. Cuttings are brought to the surface by the rotating action of the auger. This method is relatively quick and inexpensive. Advantages of this type of drilling include:

- Samples can be obtained without pulling the augers out of the hole. However, this is a poor method for obtaining grab samples from thin, discrete formations because of mixing of soils which occurs as the material is brought to the surface. Sampling of such formations requires the use of split-barrel or thin-wall tube samplers advanced through the hollow core of the auger.
- No drilling fluids are required.
- A well can be installed inside the auger stem and backfilled as the augers are withdrawn.

Disadvantages and limitations of this method of drilling include:

- Augering can only be done in unconsolidated materials.
- The inside diameter of hollow stem augers used for well installation should be at least 4 inches greater than the well casing. Use of such large-diameter hollow-stem augers is more expensive than the use of small-diameter augers in boreholes not used for well installation. Furthermore, the density of unconsolidated materials and depths become more of a limiting factor. More friction is produced with the larger diameter auger and subsequently greater torque is needed to advance the boring.
- The maximum effective depth for drilling is 150 feet or less, depending on site conditions and the size of augers used.
- In augering through clean sand formations below the water table, the sand will tend to flow into the hollow stem when the plug is removed for soil sampling or well installation. If the condition of "running" or "flowing" sands is persistent at a site, an alternative method of drilling is recommended, in particular for wells or boreholes deeper than 25 feet.

Hollow-stem auger drilling is the preferred method of drilling. Most alternative methods require the introduction of water or mud downhole (air rotary is the exception) to maintain the open borehole. With these other methods, great care must be taken to ensure that the method does not interfere with the collection of a representative sample (which may be the prime objective of the borehole construction). With this in mind, the preferred order of choice of drilling method after hollow-stem augering (HSA) is:

- Cable tool
- Casing drive (air)
- Air rotary
- Mud rotary
- Rotosonic
- Drive and wash
- Jetting

However, the use of any method will also depend on efficiency and cost-effectiveness. In many cases, mud rotary is the only feasible alternative to hollow-stem augering. Thus, mud rotary drilling is generally acceptable as a first substitute for HSA.

The procedures for sampling soils through holes drilled by hollow-stem auger shall conform with the applicable ASTM Standards: D1587-83 and D1586-84. The guidelines established in SOP SA-1.3 shall

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 6 of 26
	Revision 1	Effective Date 06/99

also be followed. The hollow-stem auger may be advanced by any power-operated drilling machine having sufficient torque and ram range to rotate and force the auger to the desired depth. The machine must, however, be equipped with the accessory equipment needed to perform required sampling, or rock coring.

The hollow-stem auger may be used without the plug when boring for geotechnical examination or for well installation. However, when drilling below the water table, specially designed plugs which allow passage of formation water but not solid material shall be used (see Reference 1 of this guideline). This drilling configuration method also prevents blow back and plugging of the auger when the plug is removed for sampling.

Alternately, it may be necessary to keep the hollow stem full of water, at least to the level of the water table, to prevent blowback and plugging of the auger. If water is added to the hole, it must be sampled and analyzed to determine if it is free from contaminants prior to use. In addition, the amount of water introduced, the amount recovered upon attainment of depth, and the amount of water extracted during well development must be carefully logged in order to ensure that a representative sample of the formation water can be obtained. Well development should occur as soon after well completion as practicable (see SOP GH-2.8 for well development procedures). If gravelly or hard material is encountered which prevents advancing the auger to the desired depth, augering should be halted and either driven casing or hydraulic rotary methods should be attempted. If the depth to the bedrock/soil interface and bedrock lithology must be determined, then a 5-foot confirmatory core run should be conducted (see Section 5.2.9).

At the option of the Field Operations Leader (in communication with the Project Manager), when resistant materials prevent the advancement of the auger, a new boring can be attempted. The original boring must be properly backfilled and the new boring started a short distance away at a location determined by the site geologist. If multiple water bearing strata were encountered, the original boring must be grouted. In some formations, it may be prudent to also grout borings which penetrate only the water table aquifer, since loose soil backfill in the boring may still provide a preferred pathway for surface liquids to reach the water table. Backfilling requirements may also be driven by state or local regulations.

5.2.2 Continuous-Flight Solid-Stem Auger Drilling

This drilling method is similar to hollow-stem augering. Practical application of this method is severely restricted compared to use of hollow-stem augers. Split-barrel (split-spoon) sampling cannot be performed without pulling the augers out, which may allow the hole to collapse. The continuous-flight solid-stem auger drilling method is therefore very time consuming and is not cost effective. Also, augers would have to be withdrawn before installing a monitoring well, which again, may allow the hole to collapse. Furthermore, geologic logging by examining the soils brought to the surface is unreliable, and depth to water may be difficult to determine while drilling.

There would be very few situations where use of a solid-stem auger would be preferable to other drilling methods. The only practical applications of this method would be to drill boreholes for well installation where no lithologic information is desired and the soils are such that the borehole can be expected to remain open after the augers are withdrawn. Alternatively, this technique can be used to find depth to bedrock in an area when no other information is required from drilling.

5.2.3 Rotary Drilling

Direct rotary drilling includes air-rotary and fluid-rotary drilling. For air or fluid-rotary drilling, the rotary drill may be advanced to the desired depth by any power-operated drilling machine having sufficient torque

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 7 of 26
	Revision 1	Effective Date 06/99

and ram range to rotate and force the bit to the desired depth. The drilling machine must, however, be equipped with any accessory equipment needed to perform required sampling, or coring. Prior to sampling, any settled drill cuttings in the borehole must be removed.

Air-rotary drilling is a method of drilling where the drill rig simultaneously turns and exerts a downward pressure on the drilling rods and bit while circulating compressed air down the inside of the drill rods, around the bit, and out the annulus of the borehole. Air circulation serves to both cool the bit and remove the cuttings from the borehole. Advantages of this method include:

- The drilling rate is high (even in rock).
- The cost per foot of drilling is relatively low.
- Air-rotary rigs are common in most areas.
- No drilling fluid is required (except when water is injected to keep down dust).
- The borehole diameter is large, to allow room for proper well installation procedures.

Disadvantages to using this method include:

- Formations must be logged from the cuttings that are blown to the surface and thus the depths of materials logged are approximate.
- Air blown into the formation during drilling may "bind" the formation and impede well development and natural groundwater flow.
- In-situ samples cannot be taken, unless the hole is cased.
- Casing must generally be used in unconsolidated materials.
- Air-rotary drill rigs are large and heavy.
- Large amounts of Investigation Derived Waste (IDW) may be generated which may require containerization, sampling, and off-site disposal.

A variation of the typical air-rotary drill bit is a down hole hammer which hammers the drill bit down as it drills. This makes drilling in hard rock faster. Air-rotary drills can also be adapted to use for rock coring although they are generally slower than other types of core drills. A major application of the air-rotary drilling method would be to drill holes in rock for well installation.

Fluid-Rotary drilling operates in a similar manner to air-rotary drilling except that a drilling fluid ("mud") or clean water is used in place of air to cool the drill bit and remove cuttings. There are a variety of fluids that can be used with this drilling method, including bentonite slurry and synthetic slurries. If a drilling fluid other than water/cuttings is used, it must be a natural clay (i.e., bentonite) and a "background" sample of the fluid should be taken for analysis of possible organic or inorganic contaminants.

Advantages to the fluid-rotary drilling method include:

- The ability to drill in many types of formations.
- Relatively quick and inexpensive.
- Split-barrel (split-spoon) or thin-wall (Shelby) tube samples can be obtained without removing drill rods if the appropriate size drill rods and bits (i.e., fish-tail or drag bit) are used.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 8 of 26
	Revision 1	Effective Date 06/99

- In some borings temporary casing may not be needed as the drilling fluids may keep the borehole open.
- Drill rigs are readily available in most areas.

Disadvantages to this method include:

- Formation logging is not as accurate as with hollow-stem auger method if split-barrel (split-spoon) samples are not taken (i.e., the depths of materials logged from cuttings delivered to the surface are approximate).
- Drilling fluids reduce permeability of the formation adjacent to the boring to some degree, and require more extensive well development than "dry" techniques (augering, air-rotary).
- No information on depth to water is obtainable while drilling.
- Fluids are needed for drilling, and there is some question about the effects of the drilling fluids on subsequent water samples obtained. For this reason as well, extensive well development may be required.
- In very porous materials (i.e., rubble fill, boulders, coarse gravel) drilling fluids may be continuously lost into the formation. This requires either constant replenishment of the drilling fluid, or the use of casing through this formation.
- Drill rigs are large and heavy, and must be supported with supplied water.
- Groundwater samples can be potentially diluted with drilling fluid.

The procedures for performing direct rotary soil investigations and sampling shall conform with the applicable ASTM standards: D2113-83, D1587-83, and D1586-84.

Soil samples shall be taken as specified by project plan documents, or more frequently, if requested by the project geologist. Any required sampling shall be performed by rotation, pressing, or driving in accordance with the standard or approved method governing use of the particular sampling tool.

When field conditions prevent the advancement of the hole to the desired depth, a new boring may be drilled at the request of the Field Operations Leader. The original boring shall be backfilled using methods and materials appropriate for the given site and a new boring started a short distance away at a location determined by the project geologist.

5.2.4 Rotosonic Drilling

The Rotosonic drilling method employs a high frequency vibrational and low speed rotational motion coupled with down pressure to advance the cutting edge of a drill string. This produces a uniform borehole while providing a continuous, undisturbed core sample of both unconsolidated and most bedrock formations. Rotosonic drilling advances a 4-inch diameter to 12-inch diameter core barrel for sampling and can advance up to a 12-inch diameter outer casing for the construction of standard and telescoped monitoring wells. During drilling, the core barrel is advanced ahead of the outer barrel in increments as determined by the site geologist and depending upon type of material, degree of subsurface contamination and sampling objectives.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 9 of 26
	Revision 1	Effective Date 06/99

The outer casing can be advanced at the same time as the inner drill string and core barrel, or advanced down over the inner drill rods and core barrel, or after the core barrel has moved ahead to collect the undisturbed sample and has been pulled out of the borehole. The outer casing can be advanced dry in most cases, or can be advanced with water or air depending upon the formations being drilled, the depth and diameter of the hole, or requirements of the project.

Advantages of this method include:

- Sampling and well installation are faster as compared to other drilling methods.
- Continuous sampling, with larger sample volume as compared to split-spoon sampling.
- The ability to drill through difficult formations such as cobbles or boulders, hard till and bedrock.
- Reduction of IDW by an average of 70 to 80 percent.
- Well installations are quick and controlled by elimination of potential bridging of annular materials during well installation, due to the ability to vibrate the outer casing during removal.

Disadvantages include:

- The cost for Rotosonic drilling as compared to other methods are generally higher. However, the net result can be a significant savings considering reduced IDW and shortened project duration.
- Rotosonic drill rigs are large and need ample room to drill, however, Rotosonic units can be placed on the ground or placed on an ATV.
- There are a limited number of Rotosonic drilling contractors at the present time.

5.2.5 Reverse Circulation Rotary Drilling

The common reverse-circulation rig is a water or mud-rotary rig with a large-diameter drill pipe which circulates the drilling water down the annulus and up the inside of the drill pipe (reverse flow direction from direct mud-rotary). This type of rig is used for the construction of large-capacity production water wells and is not suited for small, water quality sampling wells because of the use of drilling muds and the large-diameter hole which is created. A few special reverse-circulation rotary rigs are made with double-wall drill pipe. The drilling water or air is circulated down the annulus between the drill pipes and up inside the inner pipe.

Advantages of the latter method include:

- The formation water is not contaminated by the drilling water.
- Formation samples can be obtained, from known depths.
- When drilling with air, immediate information is available regarding the water-bearing properties of formations penetrated.
- Collapsing of the hole in unconsolidated formations is not as great a problem as when drilling with the normal air-rotary rig.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 10 of 26
	Revision 1	Effective Date 06/99

Disadvantages include:

- Double-wall, reverse-circulation drill rigs are rare and expensive to operate.
- Placing cement grout around the outside of the well casing above a well screen often is difficult, especially when the screen and casing are placed down through the inner drill pipe before the drill pipe is pulled out.

5.2.6 Drill-through Casing Driver

The driven-casing method consists of alternately driving casing (fitted with a sharp, hardened casing shoe) into the ground using a hammer lifted and dropped by the drill rig (or an air-hammer) and cleaning out the casing using a rotary chopping bit and air or water to flush out the materials. The casing is driven down in stages (usually 5 feet per stage); a continuous record is kept of the blows per foot in driving the casing (see SOP GH-1.5). The casing is normally advanced by a 300-pound hammer falling freely through a height of 30 inches. Simultaneous washing and driving of the casing is not recommended. If this procedure is used, the elevations within which wash water is used and in which the casing is driven must be clearly recorded.

The driven casing method is used in unconsolidated formations only. When the boring is to be used for later well installation, the driven casing used should be at least 4 inches larger in diameter than the well casing to be installed. Advantages to this method of drilling include:

- Split-barrel (split-spoon) sampling can be conducted while drilling.
- Well installation is easily accomplished.
- Drill rigs used are relatively small and mobile.
- The use of casing minimizes flow into the hole from upper water-bearing layers; therefore, multiple aquifers can be penetrated and sampled for rough field determinations of some water quality parameters.

Some of the disadvantages include:

- This method can only be used in unconsolidated formations.
- The method is slower than other methods (average drilling progress is 30 to 50 feet per day).
- Maximum depth of the borehole varies with the size of the drill rig and casing diameter used, and the nature of the formations drilled.
- The cost per hour or per foot of drilling may be substantially higher than other drilling methods.
- It is difficult and time consuming to pull back the casing if it has been driven very deep (deeper than 50 feet in many formations).

5.2.7 Cable Tool Drilling

A cable tool rig uses a heavy, solid-steel, chisel-type drill bit ("tool") suspended on a steel cable, which when raised and dropped, chisels or pounds a hole through the soils and rock. Drilling progress may be

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 11 of 26
	Revision 1	Effective Date 06/99

expedited by the use of "slip-jars" which serve as a cable-activated down hole percussion device to hammer the bit ahead.

When drilling through the unsaturated zone, some water must be added to the hole. The cuttings are suspended in the water and then bailed out periodically. Below the water table, after sufficient ground water enters the borehole to replace the water removed by bailing, no further water needs to be added. When soft caving formations are encountered, it is usually necessary to drive casing as the hole is advanced to prevent collapse of the hole. Often the drilling can be only a few feet below the bottom of the casing. Because the drill bit is lowered through the casing, the hole created by the bit is smaller than the casing. Therefore, the casing (with a sharp, hardened casing shoe on the bottom) must be driven into the hole (see Section 5.2.5 of this guideline).

Advantages of the cable-tool method include the following:

- Information regarding water-bearing zones is readily available during the drilling. Even relative permeabilities and rough water quality data from different zones penetrated can be obtained by skilled operators.
- The cable-tool rig can operate satisfactorily in all formations, but is best suited for caving, boulder, cobble or coarse gravel type formations (e.g., glacial till) or formations with large cavities above the water table (such as limestones).
- When casing is used, the casing seals formation water out of the hole, preventing down hole contamination and allowing sampling of deeper aquifers for field-measurable water quality parameters.
- Split-barrel (split-spoon) or thin-wall (Shelby) tube samples can be collected through the casing.

Disadvantages include:

- Drilling is slow compared with rotary rigs.
- The necessity of driving the casing in unconsolidated formations requires that the casing be pulled back if exposure of selected water-bearing zones is desired. This process complicates the well completion process and often increases costs. There is also a chance that the casing may become stuck in the hole.
- The relatively large diameters required (minimum of 4-inch casing) plus the cost of steel casing result in higher costs compared to rotary drilling methods where casing is not required (e.g., such use of a hollow-stem auger).
- Cable-tool rigs have largely been replaced by rotary rigs. In some parts of the U.S., availability may be difficult.

5.2.8 Jet Drilling (Washing)

Jet drilling, which should be used only for piezometer or vadose zone sampler installation, consists of pumping water or drilling mud down through a small diameter (1/2- to 2-inch) standard pipe (steel or PVC). The pipe may be fitted with a chisel bit or a special jetting screen. Formation materials dislodged by the bit and jetting action of the water are brought to the surface through the annulus around the pipe. As the pipe is jetted deeper, additional lengths of pipe may be added at the surface.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 12 of 26
	Revision 1	Effective Date 06/99

Jet percussion is a variation of the jetting method, in which the casing is driven with a drive weight. Normally, this method is used to place 2-inch-diameter casing in shallow, unconsolidated sand formations, but this method has also been used to install 3- to 4-inch-diameter casings to a depth of 200 feet.

Jetting is acceptable in very soft formations, usually for shallow sampling, and when introduction of drilling water to the formation is acceptable. Such conditions would occur during rough stratigraphic investigation or installation of piezometers for water level measurement. Advantages of this method include:

- Jetting is fast and inexpensive.
- Because of the small amount of equipment required, jetting can be accomplished in locations where access by a normal drilling rig would be very difficult. For example, it would be possible to jet down a well point in the center of a lagoon at a fraction of the cost of using a drill rig.
- Jetting numerous well points just into a shallow water table is an inexpensive method for determining the water table contours, hence flow direction.

Disadvantages include the following:

- A large amount of foreign water or drilling mud is introduced above and into the formation to be sampled.
- Jetting is usually done in very soft formations which are subject to caving. Because of this caving, it is often not possible to place a grout seal above the screen to assure that water in the well is only from the screened interval.
- The diameter of the casing is usually limited to 2 inches.
- Jetting is only possible in very soft formations that do not contain boulders or coarse gravel, and the depth limitation is shallow (about 30 feet without jet percussion equipment).
- Large quantities of water are often needed.

5.2.9 Drilling with a Hand Auger

This method is applicable wherever the formation, total depth of sampling, and the site and groundwater conditions are such as to allow hand auger drilling. Hand augering can also be considered at locations where drill rig access is not possible. All hand auger borings will be performed according to ASTM D1452-80.

Samples should be taken continuously unless otherwise specified by the project plan documents. Any required sampling is performed by rotation, pressing, or driving in accordance with the standard or approved method governing use of the particular sampling tool. Typical equipment used for sampling and advancing shallow "hand auger" holes are Iwan samplers (which are rotated) or post hole diggers (which are operated like tongs). These techniques are slow but effective where larger pieces of equipment do not have access, and where very shallow holes are desired (less than 15 feet). Surficial soils must be composed of relatively soft and non-cemented formations to allow penetration by the auger.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 13 of 26
	Revision 1	Effective Date 06/99

5.2.10 Rock Drilling and Coring

When soil borings cannot be continued using augers or rotary methods due to the hardness of the soil or when rock or large boulders are encountered, drilling and sampling can be performed using a diamond bit corer in accordance with ASTM D2113.

Drilling is done by rotating and applying downward pressure to the drill rods and drill bit. The drill bit is a circular, hollow, diamond-studded bit attached to the outer core barrel in a double-tube core barrel. The use of single-tube core barrels is not recommended, as the rotation of the barrel erodes the sample and limits its use for detailed geological evaluation. Water or air is circulated down through the drill rods and annular space between the core barrel tubes to cool the bit and remove the cuttings. The bit cuts a core out of the rock which rises into an inner barrel mounted inside the outer barrel. The inner core barrel and rock core are removed by lowering a wire line with a coupling into the drill rods, latching onto the inner barrel and withdrawing the inner barrel. A less efficient variation of this method utilizes a core barrel that cannot be removed without pulling all of the drill rods. This variation is practical only if less than 50 feet of core is required.

Core borings are made through the casing used for the soil borings. The casing must be driven and sealed into the rock formation to prevent seepage from the overburden into the hole to be cored (see Section 5.3 of this guideline). A double-tube core barrel with a diamond bit and reaming shell or equivalent should be used to recover rock cores of a size specified in the project plans. The most common core barrel diameters are listed in Attachment A.

Soft or decomposed rock should be sampled with a driven split-barrel whenever possible or cored with a Denison or Pitcher sampler.

When coring rock, including shale and claystone, the speed of the drill and the drilling pressure, amount and pressure of water, and length of run can be varied to give the maximum recovery from the rock being drilled. Should any rock formation be so soft or broken that the pieces continually fall into the hole causing unsatisfactory coring, the hole should be reamed and a flush-joint casing installed to a point below the broken formation. The size of the flush-joint casing must permit securing the core size specified. When soft or broken rock is anticipated, the length of core runs should be reduced to less than 5 feet to avoid core loss and minimize core disturbance.

Advantages of core drilling include:

- Undisturbed rock cores can be recovered for examination and/or testing.
- In formations in which the cored hole will remain open without casing, water from the rock fractures may be recovered from the well without the installation of a well screen and gravel pack.
- Formation logging is extremely accurate.
- Drill rigs are relatively small and mobile.

Disadvantages include:

- Water or air is needed for drilling.
- Coring is slower than rotary drilling (and more expensive).
- Depth to water cannot accurately be determined if water is used for drilling.
- The size of the borehole is limited.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 14 of 26
	Revision 1	Effective Date 06/99

This drilling method is useful if accurate determinations of rock lithology are desired or if open wells are to be installed into bedrock. To install larger diameter wells in coreholes, the hole must be reamed out to the proper size after boring, using air or mud rotary drilling methods.

5.2.11 Drilling & Support Vehicles

In addition to the drilling method required to accomplish the objectives of the field program, the type of vehicle carrying the drill rig and/or support equipment and its suitability for the site terrain, will often be an additional deciding factor in planning the drilling program. The types of vehicles available are extensive, and depend upon the particular drilling subcontractor's fleet. Most large drilling subcontractors will have a wide variety of vehicle and drill types suited for most drilling assignments in their particular region, while smaller drilling subcontractors will usually have a fleet of much more limited diversity. The weight, size, and means of locomotion (tires, tracks, etc.) of the drill rig must be selected to be compatible with the site terrain to assure adequate mobility between borehole locations. Such considerations also apply to necessary support vehicles used to transport water and/or drilling materials to the drill rigs at the borehole locations. When the drill rigs or support vehicles do not have adequate mobility to easily traverse the site, provisions must be made for assisting equipment, such as bulldozers, winches, timber planking, etc., to maintain adequate progress during the drilling program.

Some of the typical vehicles which are usually available for drill rigs and support equipment are:

- Totally portable drilling/sampling equipment, where all necessary components (tripods, samplers, hammers, catheads, etc.) may be hand carried to the borehole site. Drilling/sampling methods used with such equipment include:
 - Hand augers and lightweight motorized augers.
 - Retractable plug samplers--driven by hand (hammer).
 - Motorized cathead - a lightweight aluminum tripod with a small gas-engine cathead mounted on one leg, used to install small-diameter cased borings. This rig is sometimes called a "monkey on a stick."
- Skid-mounted drilling equipment containing a rotary drill or engine-driven cathead (to lift hammers and drill string), a pump, and a dismounted tripod. The skid is pushed, dragged, or winched (using the cathead drum) between boring locations.
- Small truck-mounted drilling equipment using a Jeep, stake body or other light truck (4 to 6 wheels), upon which are mounted the drill and/or a cathead, a pump, and a tripod or small drilling derrick. On some rigs, the drill and/or a cathead are driven by a power take-off from the truck, instead of by a separate engine.
- Track-mounted drilling equipment is similar to truck-mounted rigs, except that the vehicle used has wide bulldozer tracks for traversing soft ground. Sometimes a continuous-track "all terrain vehicle" is also modified for this purpose. Some types of tracked drill rigs are called "bombardier" or "weasel" rigs.
- Heavy truck-mounted drilling equipment is mounted on tandem or dual tandem trucks to transport the drill, derrick, winches, and pumps or compressors. The drill may be provided with a separate engine or may use a power take-off from the truck engine. Large augers, hydraulic rotary and reverse circulation rotary drilling equipment are usually mounted on such heavy duty trucks. For soft-ground sites, the drilling equipment is sometimes mounted on vehicles having low pressure, very wide diameter tires and capable of floating; these vehicles are called "swamp buggy" rigs.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 15 of 26
	Revision 1	Effective Date 06/99

- Marine drilling equipment is mounted on various floating equipment for drilling borings in lakes, estuaries and other bodies of water. The floating equipment varies, and is often manufactured or customized by the drilling subcontractor to suit specific drilling requirements. Typically, the range of flotation vehicles include:

- Barrel-float rigs - a drill rig mounted on a timber platform buoyed by empty 55-gallon drums or similar flotation units.
- Barge-mounted drill rigs.
- Jack-up platforms - drilling equipment mounted on a floating platform having retractable legs to support the unit on the sea or lake bed when the platform is jacked up out of the water.
- Drill ships - for deep ocean drilling.

In addition to the mobility for the drilling equipment, similar consideration must be given for equipment to support the drilling operations. Such vehicles or floating equipment are needed to transport drill water, drilling supplies and equipment, samples, drilling personnel, etc. to and/or from various boring locations.

5.2.12 Equipment Sizes

In planning subsurface exploration programs, care must be taken in specifying the various drilling components, so that they will fit properly in the boring or well.

For drilling open boreholes using rotary drilling equipment, tri-cone drill bits are employed with air, water or drilling mud to remove cuttings and cool the bit. Tri-cone bits are slightly smaller than the holes they drill (i.e., 5-7/8-inch or 7-7/8-inch bits will nominally drill 6-inch and 8-inch holes, respectively).

For obtaining split-barrel samples of a formation, samplers are commonly manufactured in sizes ranging from 2 inches to 3-1/2 inches in outside diameter. However, the most commonly used size is the 2-inch O.D., 1-3/8-inch I.D. split-barrel sampler. When this sampler is used and driven by a 140-pound (\pm 2-pound) hammer dropping 30 inches (\pm 1 inch), the procedure is called a Standard Penetration Test, and the blows per foot required to advance the sampler into the formation can be correlated to the formation's density or strength.

In planning the drilling of boreholes using hollow-stem augers or casing, in which thin-wall tube samples or diamond core drilling will be performed, refer to the various sizes and clearances provided in Attachment A of this guideline. Sizes selected must be stated in the project plan documents.

5.2.13 Estimated Drilling Progress

To estimate the anticipated rates of drilling progress for a site, the following must be considered:

- The speed of the drilling method employed.
- Applicable site conditions (e.g., terrain, mobility between borings, difficult drilling conditions in bouldery soils, rubble fill or broken rock, etc.).
- Project-imposed restrictions (e.g., drilling while wearing personal protective equipment, decontamination of drilling equipment, etc.).

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 16 of 26
	Revision 1	Effective Date 06/99

Based on recent experience in drilling average soil conditions (no boulders) and taking samples at 5-foot intervals, for moderate depth (30 feet to 50 feet) boreholes (not including installation or development of wells), the following daily rates of total drilling progress may be anticipated for the following drilling methods:

Drilling Method	Average Daily Progress (linear feet)
Hollow-stem augers	75'
Solid-stem augers	50'
Mud-Rotary Drilling	100' (cuttings samples)
Rotosonic Drilling	100'-160' (continuous core)
Reverse-Circulation Rotary	100' (cuttings samples)
Skid-Rig with driven casing	30'
Rotary with driven casing	50'
Cable Tool	30'
Hand Auger	Varies
Continuous Rock Coring	50'

5.3 Prevention of Cross-Contamination

A telescoping or multiple casing technique minimizes the potential for the migration of contaminated groundwater to lower strata below a confining layer. The telescoping technique consists of drilling to a confining layer utilizing a spun casing method with a diamond cutting or augering shoe (a method similar to the rock coring method described in Section 5.2.10, except that larger casing is used) or by using a driven-casing method (see Section 5.2.6 of this guideline) and installing a specified diameter steel well casing. The operation consists of three separate steps. Initially, a drilling casing (usually of 8-inch diameter) is installed followed by installation of the well casing (6-inch-diameter is common for 2-inch wells). This well casing is driven into the confining layer to ensure a tight seal at the bottom of the hole. The well casing is sealed at the bottom with a bentonite-cement slurry. The remaining depth of the boring is drilled utilizing a narrower diameter spun or driven casing technique within the outer well casing. A smaller diameter well casing with an appropriate length of slotted screen on the lower end, is installed to the surface.

Clean sand is placed in the annulus around and to a point of about 2 feet above the screen prior to withdrawal of the drilling casing. The annular space above the screen and to a point 2 feet above the bottom of the outer well casing is sealed with a tremied cement-bentonite slurry which is pressure-grouted or displacement-grouted into the hole. The remaining casing annulus is backfilled with clean material and grouted at the surface, or it is grouted all the way to the surface.

5.4 Cleanout of Casing Prior to Sampling

The boring hole must be completely cleaned of disturbed soil, segregated coarse material and clay adhering to the inside walls of the casing. The cleaning must extend to the bottom edge of the casing and, if possible, a short distance further (1 or 2 inches) to bypass disturbed soil resulting from the advancement of the casing. Loss of wash water during cleaning should be recorded.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 17 of 26
	Revision 1	Effective Date 06/99

For disturbed samples both above and below the water table and where introduction of relatively large volumes of wash water is permissible, the cleaning operation is usually performed by washing the material out of the casing with water; however, the cleaning should never be accomplished with a strong, downward-directed jet which will disturb the underlying soil. When clean out has reached the bottom of the casing or slightly below (as specified above), the string of tools should be lifted one foot off the bottom with the water still flowing, until the wash water coming out of the casing is clear of granular soil particles. In formations where the cuttings contain gravel and other larger particles, it is often useful to repeatedly raise and lower the drill rods and wash bit while washing out the hole, to surge these large particles upward out of the hole. As a time saver, the drilling contractor may be permitted to use a split-barrel (split-spoon) sampler with the ball check valve removed as the clean-out tool, provided the material below the spoon is not disturbed and the shoe of the spoon is not damaged. However, because the ball check valve has been removed, in some formations it may be necessary to install a flap valve or spring sample retainer in the split-spoon bit, to prevent the sample from falling out as the sampler is withdrawn from the hole. The use of jet-type chopping bits is discouraged except where large boulders and cobbles or hard-cemented soils are encountered. If water markedly softens the soils above the water table, clean out should be performed dry with an auger.

For undisturbed samples below the water table, or where wash water must be minimized, clean out is usually accomplished with an appropriate diameter clean out auger. This auger has cutting blades at the bottom to carry loose material up into the auger, and up-turned water jets just above the cutting blades to carry the removed soil to the surface. In this manner, there is a minimum of disturbance at the top of the material to be sampled. If any gravel material washes down into the casing and cannot be removed by the clean out auger, a split-barrel sample can be taken to remove it; bailers and sandpumps should not be used. For undisturbed samples above the groundwater table, all operations must be performed in a dry manner.

If all of the cuttings created by drilling through the overlying formations are not cleaned from the borehole prior to sampling, some of the problems which may be encountered during sampling include:

- When sampling is attempted through the cuttings remaining in the borehole, all or part of the sampler may become filled with the cuttings. This limits the amount of sample from the underlying formation which can enter and be retained in the sampler, and also raises questions as to the validity of the sample.
- If the cuttings remaining in the borehole contain coarse gravel and/or other large particles, these may block the bit of the sampler and prevent any materials from the underlying formation from entering the sampler when the sampler is advanced.
- In cased borings, should sampling be attempted through cuttings which remain in the lower portion of the casing, these cuttings could cause the sampler to become bound into the casing, such that it becomes very difficult to either advance or retract the sampler.
- When sampler blow counts are used to estimate the density or strength of the formation being sampled, the presence of cuttings in the borehole will usually give erroneously high sample blow counts.

To confirm that all cuttings have been removed from the borehole prior to attempting sampling, it is important that the site geologist measure the "stickup" of the drill string. This is accomplished by measuring the assembled length of all drill rods and bits or samplers (the drill string) as they are lowered to the bottom of the hole, below some convenient reference point of the drill string, then measuring the height of this reference point above the ground surface. The difference of these measurements is the

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 18 of 26
	Revision 1	Effective Date 06/99

depth of the drill string (lower end of the bit or sampler) below the ground surface, which must then be compared with the depth of sampling required (installed depth of casing or depth of borehole drilled). If the length of drill string below grade is more than the drilled or casing depth, the borehole has been cleaned too deeply, and this deeper depth of sampling must be recorded on the log. If the length of drill string below grade is less than the drilled or casing depth, the difference represents the thickness of cuttings which remain in the borehole. In most cases, an inch or two of cuttings may be left in the borehole with little or no problem. However, if more than a few inches of cuttings are encountered, the borehole must be recleaned prior to attempting sampling.

5.5 Materials of Construction

The effects of monitoring well construction materials on specific chemical analytical parameters are described and/or referenced in SOP GH-2.8. However, there are several materials used during drilling, particularly drilling fluids and lubricants, which must be used with care to avoid compromising the representativeness of soil and ground water samples.

The use of synthetic or organic polymer slurries is not permitted at any location where soil samples for chemical analysis are to be collected. These slurry materials could be used for installation of long-term monitoring wells, but the early time data in time series collection of ground water data may then be suspect. If synthetic or organic polymer muds are proposed for use at a given site, a complete written justification including methods and procedures for their use must be provided by the site geologist and approved by the Project Manager. The specific slurry composition and the concentration of suspected contaminants for each site must be known.

For many drilling operations, potable water is an adequate lubricant for drill stem and drilling tool connections. However, there are instances, such as drilling in tight clayey formations or in loose gravels, when threaded couplings must be lubricated to avoid binding. In these instances, to be determined in the field by the judgment of the site geologist and noted in the site logbook, and only after approval by the Project Manager, a vegetable oil or silicone-based lubricant should be used. Petroleum based greases, etc. will not be permitted. Samples of lubricants used must be provided and analyzed for chemical parameters appropriate to the given site.

5.6 Subsurface Soil Samples

Subsurface soil samples are used to characterize subsurface stratigraphy. This characterization can indicate the potential for migration of chemical contaminants in the subsurface. In addition, definition of the actual migration of contaminants can be obtained through chemical analysis of the soil samples. Where the remedial activities may include in-situ treatment or excavation and removal of the contaminated soil, the depth and areal extent of contamination must be known as accurately as possible.

Engineering and physical properties of soil may also be of interest should site construction activities be planned. Soil types, grain size distribution, shear strength, compressibility, permeability, plasticity, unit weight, and moisture content are some of the physical characteristics that may be determined for soil samples.

Penetration tests are also described in this procedure. The tests can be used to estimate various physical and engineering parameters such as relative density, unconfined compressive strength, and consolidation characteristics of soils.

Surface protocols for various soil sampling techniques are discussed in SOP SA-1.3. Continuous-core soil sampling and rock coring are discussed below. The procedures described here are representative of

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 19 of 26
	Revision 1	Effective Date 06/99

a larger number of possible drilling and sampling techniques. The choice of techniques is based on a large number of variables such as cost, local geology, etc. The final choice of methods must be made with the assistance of drilling subcontractors familiar with the local geologic conditions. Alternative techniques must be based upon the underlying principles of quality assurance implicit in the following procedures.

The CME continuous sample tube system provides a method of sampling soil continuously during hollow-stem augering. The 5-foot sample barrel fits within the lead auger of a hollow-auger column. The sampling system can be used with a wide range of I.D. hollow-stem augers (from 3-1/4-inch to 8-1/4-inch I.D.). This method has been used to sample many different materials such as glacial drift, hard clays and shales, mine tailings, etc. This method is particularly used when SPT samples are not required and a large volume of material is needed. Also, this method is useful when a visual description of the subsurface lithology is required. Rotasonic drilling methods also provide a continuous soil sample.

5.7 Rock Sampling (Coring) (ASTM D2113-83)

Rock coring enables a detailed assessment of borehole conditions to be made, showing precisely all lithologic changes and characteristics. Because coring is an expensive drilling method, it is commonly used for shallow studies of 500 feet or less, or for specific intervals in the drill hole that require detailed logging and/or analyzing. Rock coring can, however, proceed for thousands of feet continuously, depending on the size of the drill rig, and yields better quality data than air-rotary drilling, although at a substantially reduced drilling rate. Rate of drilling varies widely, depending on the characteristics of lithologies encountered, drilling methods, depth of drilling, and condition of drilling equipment. Average output in a 10-hour day ranges from 40 to over 200 feet. Down hole geophysical logging or television camera monitoring is sometimes used to complement the data generated by coring.

Borehole diameter can be drilled to various sizes, depending on the information needed. Standard sizes of core barrels (showing core diameter) and casing are shown in Figure 1.

Core drilling is used when formations are too hard to be sampled by soil sampling methods and a continuous solid sample is desired. Usually, soil samples are used for overburden, and coring begins in sound bedrock. Casing is set into bedrock before coring begins to prevent loose material from entering the borehole, to prevent loss of drilling fluid, and to prevent cross-contamination of aquifers.

Drilling through bedrock is initiated by using a diamond-tipped core bit threaded to a drill rod (outer core barrel) with a rate of drilling determined by the downward pressure, rotation speed of drill rods, drilling fluid pressure in the borehole, and the characteristics of the rock (mineralogy, cementation, weathering).

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 20 of 26
	Revision 1	Effective Date 05/99

FIGURE 1

STANDARD SIZES OF CORE BARRELS AND CASING

Coring Bit Size	Nominal*		Set Size*	
	O.D.	I.D.	O.D.	I.D.
RWT	1 5/32	3/4	1.160	0.735
EWT	1 1/2	29/32	1.470	0.905
EX, EXL, EWG, EWM	1 1/2	13/16	1.470	0.845
AWT	1 7/8	1 9/32	1.875	1.281
AX, AXL, AWG, AWM	1 7/8	1 3/16	1.875	1.185
BWT	2 3/8	1 3/4	2.345	1.750
BX, BXL, BWG, BWM	2 3/8	1 5/8	2.345	1.655
NWT	3	2 5/16	2.965	2.313
NX, NXL, NWG, NWM	3	2 1/8	2.965	2.155
HWT	3 29/32	3 3/16	3.889	3.187
HWG	3 29/32	3	3.889	3.000
2 3/4 x 3 7/8	3 7/8	2 3/4	3.840	2.690
4 x 5 1/2	5 1/2	4	5.435	3.970
6 x 7 3/4	7 3/4	6	7.655	5.970
AX Wire line ____/____	1 7/8	1	1.875	1.000
BX Wire line ____/____	2 3/8	1 7/16	2.345	1.437
NX Wire line ____/____	3	1 15/16	2.965	1.937

* All dimensions are in inches; to convert to millimeters, multiply by 25.4.
____/____ Wire line dimensions and designations may vary according to manufacturer.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 21 of 26
	Revision 1	Effective Date 06/99

FIGURE 1
STANDARD SIZES OF CORE BARRELS AND CASING
PAGE TWO

Size Designations		Casing O.D., Inches	Casing Coupling		Casing bit O.D., Inches	Core barrel bit O.D., Inches*	Drill rod O.D., Inches	Approximate Core Diameter	
Casing; Casing coupling; Casing bits; Core barrel bits	Rod; rod couplings		O.D., Inches	I.D., Inches				Normal, Inches	Thinwall, Inches
RX	RW	1.437	1.437	1.188	1.485	1.160	1.094	—	0.735
EX	E	1.812	1.812	1.500	1.875	1.470	1.313	0.845	0.905
AX	A	2.250	2.250	1.906	2.345	1.875	1.625	1.185	1.281
BX	B	2.875	2.875	2.375	2.965	2.345	1.906	1.655	1.750
NX	N	3.500	3.500	3.000	3.615	2.965	2.375	2.155	2.313
HX	HW	4.500	4.500	3.938	4.625	3.890	3.500	3.000	3.187
RW	RW	1.437	Flush Joint	No Coupling	1.485	1.160	1.094	—	0.735
EW	EW	1.812			1.875	1.470	1.375	0.845	0.905
AW	AW	2.250			2.345	1.875	1.750	1.185	1.281
BW	BW	2.875			2.965	2.345	2.125	1.655	1.750
NW	NW	3.500			3.615	2.965	2.625	2.155	2.313
HW	HW	4.500			4.625	3.890	3.500	3.000	3.187
PW	—	5.500			5.650	—	—	—	—
SW	—	6.625			6.790	—	—	—	—
UW	—	7.625			7.800	—	—	—	—
ZW	—	8.625			8.810	—	—	—	—
—	AX <u> </u> <u> </u> \	—	—	—	—	1.875	1.750	1.000	—
—	BX <u> </u> <u> </u> \	—	—	—	—	2.345	2.250	1.437	—
—	NX <u> </u> <u> </u> \	—	—	—	—	2.965	2.813	1.937	—

* All dimensions are in inches; to convert to millimeters, multiply by 25.4.
 / Wire line dimensions and designations may vary according to manufacturer.

NOMINAL DIMENSIONS FOR DRILL CASINGS AND ACCESSORIES.
(DIAMOND CORE DRILL MANUFACTURERS ASSOCIATION). 288-
D-2889

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 22 of 26
	Revision 1	Effective Date 06/99

5.7.1 Diamond Core Drilling

A penetration of typically less than 6 inches per 50 blows using a 140-lb. hammer dropping 30 inches with a 2-inch split-barrel sampler shall be considered an indication that soil sampling methods may not be applicable and that coring may be necessary to obtain samples.

When formations are encountered that are too hard to be sampled by soil sampling methods, the following diamond core drilling procedure may be used:

- Firmly seat a casing into the bedrock or the hard material to prevent loose materials from entering the hole and to prevent the loss of drilling fluid return. Level the surface of the rock or hard material when necessary by the use of a fishtail or other bits. If the drill hole can be retained open without the casing and if cross-contamination of aquifers in the unconsolidated materials is unlikely, leveling may be omitted.
- Begin the core drilling using a double-tube swivel-core barrel of the desired size. After drilling no more than 10 feet (3 m), remove the core barrel from the hole and take out the core. If the core blocks the flow of the drilling fluid during drilling, remove the core barrel immediately. In soft materials, a large starting size may be specified for the coring tools; where local experience indicates satisfactory core recovery or where hard, sound materials are anticipated, a smaller size or the single-tube type may be specified and longer runs may be drilled. NX/NW size coring equipment is the most commonly used size.
- When soft materials are encountered that produce less than 50 percent recovery, stop the core drilling. If soil samples are desired, secure such samples in accordance with the procedures described in ASTM Method D 1586 (Split-barrel Sampling) or in Method D 1587 (Thin-Walled Tube Sampling); sample soils per SOP SA-1.3. Resume diamond core drilling when refusal materials are again encountered.
- Since rock structures and the occurrence of seams, fissures, cavities, and broken areas are among the most important items to be detected and described, take special care to obtain and record these features. If such broken zones or cavities prevent further advance of the boring, one of the following three steps shall be taken: (1) cement the hole; (2) ream and case; or (3) case and advance with the next smaller size core barrel, as conditions warrant.
- In soft, seamy, or otherwise unsound rock, where core recovery may be difficult, M-design core barrels may be used. In hard, sound rock where a high percentage of core recovery is anticipated, the single-tube core barrel may be employed.

5.7.2 Rock Sample Preparation and Documentation

Once the rock coring has been completed and the core recovered, the rock core shall be carefully removed from the barrel, placed in a core tray (previously labeled "top" and "bottom" to avoid confusion), classified, and measured for percentage of recovery as well as the rock quality designation (RQD). Each core shall be described, classified, and logged using a uniform system as presented in SOP GH-1.5. If moisture content will be determined or if it is desirable to prevent drying (e.g., to prevent shrinkage of clay formations) or oxidation of the core, the core shall be wrapped in plastic sleeves immediately after logging. Each plastic sleeve shall be labeled with indelible ink. The boring number, run number, and the footage represented in each sleeve shall be included, as well as designating the top and bottom of the core run.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 23 of 26
	Revision 1	Effective Date 06/99

After sampling, rock cores shall be placed in the sequence of recovery in well-constructed wooden boxes provided by the drilling contractor. Rock cores from two different borings shall not be placed in the same core box unless accepted by the Project Geologist. The core boxes shall be constructed to accommodate at least 20 linear feet of core in rows of approximately 5 feet each and shall be constructed with hinged tops secured with screws, and a latch (usually a hook and eye) to keep the top securely fastened down. Wood partitions shall be placed at the end of each core run and between rows.

The depth from the surface of the boring to the top and bottom of the drill run and run number shall be marked on the wooden partitions with indelible ink. A wooden partition (wooden block) shall be placed at the end of each run with the depth of the bottom of the run written on the block. These blocks will serve to separate successive core runs and indicate depth intervals for each run. The order of placing cores shall be the same in all core boxes. Rock core shall be placed in the box so that, when the box is open, with the inside of the lid facing the observer, the top of the cored interval contained within the box is in the upper left corner of the box, and the bottom of the cored interval is in the lower right corner of the box. The top and bottom of each core obtained and its true depth shall be clearly and permanently marked on each box. The width of each row must be compatible with the core diameter to prevent lateral movement of the core in the box. Similarly, an empty space in a row shall be filled with an appropriate filler material or spacers to prevent longitudinal movement of the core in the box.

The inside and outside of the core-box lid shall be marked by indelible ink to show all pertinent data on the box's contents. At a minimum, the following information shall be included:

- Project name.
- Project number.
- Boring number.
- Run numbers.
- Footage (depths).
- Recovery.
- RQD (%).
- Box number and total number of boxes for that boring (Example: Box 5 of 7).

For easy retrieval when core boxes are stacked, the sides and ends of the box shall also be labeled and include project number, boring number, top and bottom depths of core and box number.

Prior to final closing of the core box, a photograph of the recovered core and the labeling on the inside cover shall be taken. If moisture content is not critical, the core shall be wetted and wiped clean for the photograph. (This will help to show true colors and bedding features in the cores).

6.0 REFERENCES

Acker Drill Co., 1958. Basic Procedures of Soil Sampling. Acker Drill Co., Scranton, Pennsylvania.

American Institute of Steel Construction, 1978. Manual of Steel Construction, 7th Edition. American Institute of Steel Construction, New York, New York.

American Society for Testing and Materials, 1987. ASTM Standards D1587-83, D1586-84, and D1452-80. ASTM Annual Book of Standards, ASTM, Philadelphia, Pennsylvania, Vol. 4.08.

American Society for Testing and Materials, 1989. Standard Practice for Diamond Core Drilling for Site Investigation. ASTM Method D2113-83 (reapproved 1987), Annual Book of Standards, ASTM, Philadelphia, Pennsylvania.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 24 of 26
	Revision 1	Effective Date 06/99

Barcelona, M. J., J. P. Gibb and R. A. Miller, 1983. A Guide to the Selection of Material for Monitoring Well Construction and Ground Water Sampling. ISWS Contract Report 327, Illinois State Water Survey, Champaign, Illinois.

BOART Longyear Co., Sonic Drilling. Environmental Drilling Division, Andova, Minnesota.

Central Mine Equipment Company, Drilling Equipment, St. Louis, Missouri.

Dept. of the Navy, Naval Facilities Engineering Command, 1982. Soil Mechanics Design Manual 7.1.

Driscoll, Fletcher G., 1986. Groundwater and Wells, 2nd Edition. Johnson Division, St. Paul, Minnesota.

Procedure GH-1.5 - Borehole and Sample Logging.

Scalf, M. R., J. F. McNabb, W. J. Dunlap, R. L. Crosby and J. Fryberger, 1981. Manual of Ground-Water Sampling Procedures. NWWA/EPA Series. Kerr Environmental Research Laboratory, Office of Research and Development, U.S. EPA, Ada, Oklahoma.

U.S. Department of the Interior, 1974, Earth Manual, A Water Resources Technical Publication, 810 pages.

U.S. EPA, 1980. Procedure Manual for Ground Water Monitoring at Solid Waste Disposal Facilities. SW-611. Office of Solid Waste, U.S. EPA, Cincinnati, Ohio.

W. L. Acker III, 1974. Basic Procedures for Soil Sampling and Core Drilling. Acker Drill Co., Inc., Scranton, Pennsylvania.

Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 25 of 26
	Revision 1	Effective Date 06/99

ATTACHMENT A

DRILLING EQUIPMENT SIZES

Drilling Component	Designation or Hole Size (Inches)	O.D. (Inches)	I.D. (Inches)	Coupling I.D. (Inches)
Hollow-stem augers (Ref. 7)	6 1/4	5	2 1/4	
	6 3/4	5 3/4	2 3/4	---
	7 1/4	6 1/4	3 1/4	---
	13 1/4	12	6	---
Thin Wall Tube Samplers (Ref. 7)	---	2	1 7/8	---
	---	2 1/2	2 3/8	---
	---	3	2 7/8	---
	---	3 1/2	3 3/8	---
	---	4 1/2	4 3/8	---
	---	5	4 3/4	---
Drill Rods (Ref. 7)	RW	1 3/32	23/32	13/32
	EW	1 3/8	15/16	7/16
	AW	1 3/4	1 1/4	5/8
	BW	2 1/8	1 3/4	3/4
	NW	2 5/8	2 1/4	1 3/8
	HW	3 1/2	3 1/16	2 3/8
	E	1 5/16	7/8	7/16
	A	1 5/8	1 1/8	9/16
	B	1 7/8	1 1/4	5/8
	N	2 3/8	2	1
				Wall Thickness (Inches)
Driven External Coupled Extra Strong Steel* Casing (Ref. 8)	2 1/2	2.875	2.323	0.276
	3	3.5	2.9	0.300
	3 1/2	4.0	3.364	0.318
	4	4.5	3.826	0.337
	5	5.63	4.813	0.375
	6	6.625	5.761	0.432
	8	8.625	7.625	0.500
	10	10.750	9.750	0.500
	12	12.750	11.750	0.500

* Add twice the casing wall thickness to casing O.D. to obtain the approximate O.D. of the external pipe couplings.


Subject SOIL AND ROCK DRILLING METHODS	Number GH-1.3	Page 26 of 26
	Revision 1	Effective Date 06/99

**ATTACHMENT A
DRILLING EQUIPMENT SIZES
PAGE TWO**

Drilling Component	Designation or Hole Size (Inches)	O.D. (Inches)	I.D. (Inches)	Coupling I.D. (Inches)
Flush Coupled Casing (Ref. 7)	RX	1 7/16	1 3/16	1 3/16
	EX	1 13/16	1 5/8	1 1/2
	AX	2 1/4	2	1 29/32
	BX	2 7/8	2 9/16	2 3/8
	NX	3 1/2	3 3/16	3
	HX	4 1/2	4 1/8	3 15/16
Flush Joint Casing (Ref. 7)	RW	1 7/16	1 3/16	
	EW	1 13/16	1 1/2	
	AW	2 1/4	1 29/32	
	BW	2 7/8	2 3/8	
	NW	3 1/2	3	
	HW	4 1/2	4	
	PW	5 1/2	5	
	SW	6 5/8	6	
	UW	7 5/8	7	
	ZW	8 5/8	8	
Diamond Core Barrels (Ref. 7)	EWM	1 1/2	7/8**	
	AWM	1 7/8	1 1/8**	
	BWM	2 3/8	1 5/8**	
	NWM	3	2 1/8	
	HWG	3 7/8	3	
	2 3/4 x 3 7/8	3 7/8	2 11/16	
	4 x 5 1/2	5 1/2	3 15/16	
	6 x 7 3/4	7 3/4	5 15/16	
	AQ (wireline)	1 57/64	1 1/16**	
	BQ (wireline)	2 23/64	1 7/16**	
	NQ (wireline)	2 63/64	1 7/8	
	HQ (wireline)	3 25/32	2 1/2	

** Because of the fragile nature of the core and the difficulty to identify rock details, use of small-diameter core (1 3/8") is not recommended.

TtNUS SOP SA-2.5 – Direct Push Technology



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number	SA-2.5	Page	1 of 6
Effective Date	09/03	Revision	3
Applicability	Tetra Tech NUS, Inc.		
Prepared	Earth Sciences Department		
Approved	D. Senovich <i>DS</i>		

Subject DIRECT PUSH TECHNOLOGY
(GEOPROBE®/HYDROPUNCH™)

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 PURPOSE	2
2.0 SCOPE	2
3.0 GLOSSARY	2
4.0 RESPONSIBILITIES	2
5.0 SOIL SAMPLING PROCEDURES	3
5.1 GENERAL	3
5.2 SAMPLING EQUIPMENT	3
5.3 DPT SAMPLING METHODOLOGY	3
6.0 GROUNDWATER SAMPLING PROCEDURES	4
6.1 GENERAL	4
6.2 SAMPLING EQUIPMENT	4
6.3 DPT TEMPORARY WELL POINT INSTALLATION AND SAMPLING METHODOLOGY	5
7.0 RECORDS	5
 <u>ATTACHMENTS</u>	
1 SAFE WORK PERMIT	6

Subject DIRECT PUSH TECHNOLOGY (GEOPROBE®/HYDROPUNCH™)	Number SA-2.5	Page 2 of 6
	Revision 3	Effective Date 09/03

1.0 PURPOSE

The purpose of this procedure is to provide general reference information on Direct Push Technology (DPT). DPT is designed to collect soil, groundwater, and soil gas samples without using conventional drilling techniques. The advantage of using DPT over conventional drilling includes the generation of little or no drill cuttings, sampling in locations with difficult accessibility, reduced overhead clearance requirements, no fluid introduction during probing, and typical lower costs per sample than with conventional techniques. Disadvantages include a maximum penetration depth of approximately 15 to 40 feet in dense soils (although it may be as much as 60 to 80 feet in certain types of geological environments), reduced capability of obtaining accurate water-level measurements, and the inability to install permanent groundwater monitoring wells. The methods and equipment described herein are for collection of surface and subsurface soil samples and groundwater samples. Soil gas sampling is discussed in SOP SA-2.4.

2.0 SCOPE

This procedure provides information on proper sampling equipment and techniques for DPT. Review of the information contained herein will facilitate planning of the field sampling effort by describing standard sampling techniques. The techniques described shall be followed whenever applicable, noting that site-specific conditions or project-specific plans may require adjustments in methodology.

3.0 GLOSSARY

Direct Push Technology (DPT) - DPT refers to sampling tools and sensors that are driven directly into the ground without the use of conventional drilling equipment. DPT typically utilizes hydraulic pressure and/or percussion hammers to advance the sampling tools. A primary advantage of DPT over conventional drilling techniques is that DPT results in the generation of little or no investigation derived waste.

Geoprobe® - Geoprobe® is a manufacturer of a hydraulically-powered, percussion/probing machines utilizing DPT to collect subsurface environmental samples. Geoprobe® relies on a relatively small amount of static weight (vehicle) combined with percussion as the energy for advancement of a tool string. The Geoprobe® equipment can be mounted in a multitude of vehicles for access to all types of environmental sites.

HydroPunch™ - HydroPunch™ is a manufacturer of stainless steel and Teflon® sampling tools that are capable of collecting representative groundwater and/or soil samples without requiring the installation of a groundwater monitoring well or conventional soil boring. HydroPunch™ is an example of DPT sampling equipment.

Flame Ionization Detector (FID) - A portable instrument for the measurement of many combustible organic compounds and a few inorganic compounds in air at parts-per million levels. The basis for the detection is the ionization of gaseous species utilizing a flame as the energizing source.

Photo Ionization Detector (PID) - A portable instrument for the measurement of many combustible organic compounds and a few inorganic compounds in air at parts-per million levels. The basis for the detection is the ionization of gaseous species utilizing ultraviolet radiation as the energizing source.

4.0 RESPONSIBILITIES

Project Manager - The Project Manager is responsible for selecting and/or reviewing the appropriate DPT drilling procedure required to support the project objectives.

Subject DIRECT PUSH TECHNOLOGY (GEOPROBE®/HYDROPUNCH™)	Number SA-2.5	Page 3 of 6
	Revision 3	Effective Date 09/03

Field Operations Leader (FOL)- The FOL is primarily responsible for performing the DPT in accordance with the project-specific plan.

5.0 SOIL SAMPLING PROCEDURES

5.1 General

The common methodology for the investigation of the vadose zone is soil boring drilling and soil sampling. However, drilling soil borings can be very expensive. Generally the advantage of DPT for subsurface soil sampling is the reduced cost of disposal of drilling cuttings and shorter sampling times.

5.2 Sampling Equipment

Equipment needed for conducting DPT drilling for subsurface soil sampling includes, but is not limited to, the following:

- Geoprobe® Sampling Kit
- Cut-resistant gloves
- 4-foot x 1.5-inch diameter macrocore sampler
- Probe sampling adapters
- Roto-hammer with 1.5-inch bit
- Disposable acetate liners for soil macrocore sampler
- Cast aluminum or steel drive points
- Geoprobe® AT-660 Series Large Bore Soil Sampler, or equivalent
- Standard decontamination equipment and solutions

For health and safety equipment and procedures, follow the direction provided in the Safe Work Permit in Attachment 1, or the more detailed directions provided in the project's Health and Safety Plan.

5.3 DPT Sampling Methodology

There are several methods for the collection of soil samples using DPT drilling. The most common method is discussed in the following section. Variations of the following method may be conducted upon approval of the Project Manager in accordance with the project-specific plan.

- Macrocore samplers fitted with detachable aluminum or steel drive points are driven into the ground using hydraulic pressure. If there is concrete or pavement over a sampling location, a Roto-hammer is used to drill a minimum 1.5-inch diameter hole through the surface material. A Roto-hammer may also be used if very dense soils are encountered.
- The sampler is advanced continuously in 4-foot intervals or less if desired. No soil cuttings are generated because the soil which is not collected in the sampler is displaced within the formation.
- The sampler is retracted from the hole, and the 4-foot continuous sample is removed from the outer coring tube. The sample is contained within an inner acetate liner.
- Attach the metal trough from the Geoprobe® Sampling Kit firmly to the tail gate of a vehicle. If a vehicle with a tail gate is not available, secure the trough on another suitable surface.
- Place the acetate liner containing the soils in the trough.

Subject DIRECT PUSH TECHNOLOGY (GEOPROBE®/HYDROPUNCH™)	Number SA-2.5	Page 4 of 6
	Revision 3	Effective Date 09/03

- While wearing cut-resistant gloves (constructed of leather or other suitable material), cut the acetate liner through its entire length using the double-bladed knife that accompanies the Geoprobe® Sampling Kit. Then remove the strip of acetate from the trough to gain access to the collected soils. Do not attempt to cut the acetate liner while holding it in your hand.
- Field screen the sample with an FID or PID, and observe/examine the sample (according to SOP GH-1.3). If appropriate, transfer the sample to sample bottles for laboratory analysis. If additional volume is required, push an additional boring adjacent to the first and composite/mix the same interval. Field compositing is usually not acceptable for sample requiring volatile organics analysis.
- Once sampling has been completed, the hole is backfilled with bentonite chips or bentonite cement grout, depending upon project requirements. Asphalt or concrete patch is used to cap holes through paved or concrete areas. All holes should be finished smooth to existing grade.
- In the event the direct push van/truck cannot be driven to a remote location or a sampling location with difficult accessibility, sampling probes may be advanced and sampled manually or with air/electric operated equipment (e.g., jack hammer).
- Sampling equipment is decontaminated prior to collecting the next sample.

6.0 GROUNDWATER SAMPLING PROCEDURES

6.1 General

The most common methodology for the investigation of groundwater is the installation and sampling of permanent monitoring wells. If only groundwater screening is required, the installation and sampling of temporary well points may be performed. The advantage of temporary well point installation using DPT is reduced cost due to no or minimal disposal of drilling cuttings and well construction materials, and shorter installation/times sampling.

Two disadvantages of DPT drilling for well point installation are:

- In aquifers with low yields, well points may have to be sampled without purging or development.
- If volume requirements are high, this method can be time consuming for low yield aquifers.

6.2 Sampling Equipment

Equipment needed for temporary well installation and sampling using DPT includes, but is not limited, to the following:

- 2-foot x 1-inch diameter mill-slotted (0.005 to 0.02-inch) well point
- Connecting rods
- Roto-hammer with 1.5-inch bit
- Mechanical jack
- 1/4-inch OD polyethylene tubing
- 3/8-inch OD polyethylene tubing
- Peristaltic pump
- Standard decontamination equipment and solutions

Subject DIRECT PUSH TECHNOLOGY (GEOPROBE®/HYDROPUNCH™)	Number SA-2.5	Page 5 of 6
	Revision 3	Effective Date 09/03

6.3 DPT Temporary Well Point Installation and Sampling Methodology

There are several methods for the installation and sampling of temporary well points using DPT. The most common methodology is discussed below. Variations of the following method may be conducted upon approval of the Project Manager in accordance with the project specific plan.

- A 2-foot x 1-inch diameter mill-slotted (0.005 to 0.02-inch) well point attached to connecting rods is driven into the ground to the desired depth using a rotary electric hammer or other direct push drill rig. If there is concrete or pavement over a sampling location, a Roto-hammer or electric coring machine is used to drill a hole through the surface material.
- The well point will be allowed to equilibrate for at least 15 minutes, after which a measurement of the static water level will be taken. The initial measurement of the water level will be used to assess the amount of water which is present in the well point and to determine the amount of silt and sand infiltration that may have occurred.
- The well point will be developed using a peristaltic pump and polyethylene tubing to remove silt and sand which may have entered the well point. The well point is developed by inserting polyethylene tubing to the bottom of the well point and lifting and lowering the tubing slightly while the pump is operating. The pump will be operated at a maximum rate of approximately 2 liters per minute. After removal of sediment from the bottom of the well point, the well point will be vigorously pumped at maximum capacity until discharge water is visibly clear and no further sediments are being generated. Measurements of pH, specific conductance, temperature, and turbidity shall be recorded every 5 to 10 minutes during the purging process. After two consistent readings of pH, specific conductance, temperature and turbidity (± 10 percent), the well may be sampled.
- A sample will be collected using the peristaltic pump set at the same or reduced speed as during well development. Samples (with the exception of the samples to be analyzed for volatile organic compounds, VOCs) will be collected directly from the pump discharge. Sample containers for VOCs will be filled by (first shutting off the pump) crimping the discharge end of the sample tubing when filled, removing the inlet end of the sample tubing from the well, suspending the inlet tubing above the vial, and allowing water to fill each vial by gravity flow.
- Once the groundwater sample has been collected, the connecting rods and well point will be removed from the hole with the direct push rig hydraulics. The hole will be backfilled with bentonite chips or bentonite cement grout, depending upon project requirements. Asphalt or concrete patch will be used to cap holes through paved or concrete areas. All holes will be finished smooth to existing grade.
- In the event the direct push van/truck cannot be driven to a remote location or sampling location with difficult accessibility, sampling probes may be advanced and sampled manually or with air/electric-operated equipment (e.g., jack hammer).
- Decontaminate the equipment before moving to the next location.

7.0 RECORDS

A record of all field procedures, tests, and observations must be recorded in the field logbook, boring logs, and sample log sheets, as needed. Entries should include all pertinent data regarding the investigation. The use of sketches and field landmarks will help to supplement the investigation and evaluation.

Subject DIRECT PUSH TECHNOLOGY (GEOPROBE®/HYDROPUNCH™)	Number SA-2.5	Page 6 of 6
	Revision 3	Effective Date 09/03

**ATTACHMENT 1
SAFE WORK PERMIT FOR DPT OPERATIONS**

Permit No. _____ Date: _____ Time: From _____ to _____

SECTION I: General Job Scope

- I. Work limited to the following (description, area, equipment used): **Monitoring well drilling and installation through direct push technology**
- II. Required Monitoring Instruments: _____
- III. Field Crew: _____
- IV. On-site Inspection conducted ☐ Yes ☐ No Initials of Inspector **TINUS**

SECTION II: General Safety Requirements (To be filled in by permit issuer)

- V. Protective equipment required
- | | | |
|--|--|--|
| Level D <input checked="" type="checkbox"/> Level B <input type="checkbox"/> | Respiratory equipment required | Escape Pack <input type="checkbox"/> |
| Level C <input type="checkbox"/> Level A <input type="checkbox"/> | Full face APR <input type="checkbox"/> | SCBA <input type="checkbox"/> |
| Detailed on Reverse | Half face APR <input type="checkbox"/> | Bottle Trailer <input type="checkbox"/> |
| | SKA-PAC SAR <input type="checkbox"/> | None <input checked="" type="checkbox"/> |
| | Skid Rig <input type="checkbox"/> | |

Level D Minimum Requirements: Sleeved shirt and long pants, safety footwear, and work gloves. Safety glasses, hard hats, and hearing protection will be worn when working near or sampling in the vicinity of the DPT rig.

Modifications/Exceptions.

VI. Chemicals of Concern	Action Level(s)	Response Measures
_____	_____	_____

VII. Additional Safety Equipment/Procedures

- | | |
|---|--|
| Hard-hat <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Hearing Protection (Plugs/Muffs) <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Safety Glasses <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Safety belt/harness <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| Chemical/splash goggles <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Radio <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| Splash Shield <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Barricades <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Splash suits/coveralls <input type="checkbox"/> Yes <input type="checkbox"/> No | Gloves (Type - _____) <input type="checkbox"/> Yes <input type="checkbox"/> No |
| Steel toe Work shoes or boots <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Work/warning regimen <input type="checkbox"/> Yes <input type="checkbox"/> No |

Modifications/Exceptions: Reflective vests for high traffic areas.

- | | | | | |
|--|-------------------------------------|-------------------------------------|--------------------------|--------------------------|
| VIII. Procedure review with permit acceptors | Yes | NA | Yes | NA |
| Safety shower/eyewash (Location & Use) | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Daily tail gate meetings | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Contractor tools/equipment/PPE inspected | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Emergency alarms | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Evacuation routes | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Assembly points | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

IX. Site Preparation

- | | |
|---|--|
| Utility Clearances obtained for areas of subsurface investigation | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| Physical hazards removed or blockaded | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| Site control boundaries demarcated/signage | <input type="checkbox"/> Yes <input type="checkbox"/> No |

X. Equipment Preparation

- | | | |
|---|--------------------------|-------------------------------------|
| Equipment drained/depressurized | Yes | NA |
| Equipment purged/cleaned | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| Isolation checklist completed | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| Electrical lockout required/field switch tested | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| Blinds/misalignments/blocks & bleeds in place | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| Hazardous materials on walls/behind liners considered | <input type="checkbox"/> | <input checked="" type="checkbox"/> |


- XI. Additional Permits required (Hot work, confined space entry) ☐ Yes ☐ No

If yes, complete permit required or contact Health Sciences, Pittsburgh Office

XII. Special instructions, precautions:

Permit Issued by: _____ Permit Accepted by: _____

TtNUS SOP SA-1.3 – Soil Sampling



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number	SA-1.3	Page	1 of 20
Effective Date	09/03	Revision	7
Applicability	Tetra Tech NUS, Inc.		
Prepared	Earth Sciences Department		
Approved	D. Senovich <i>DS</i>		

Subject
SOIL SAMPLING

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 PURPOSE.....	2
2.0 SCOPE.....	2
3.0 GLOSSARY.....	2
4.0 RESPONSIBILITIES.....	3
5.0 PROCEDURES.....	3
5.1 OVERVIEW.....	3
5.2 SOIL SAMPLE COLLECTION.....	4
5.2.1 Procedure for Collecting Soil Samples for Volatile Organic Compounds.....	4
5.2.2 Procedure for Collecting Non-Volatile Soil Samples.....	6
5.2.3 Procedure for Collecting Undisturbed Soil Samples (ASTM D1587-83).....	6
5.3 SURFACE SOIL SAMPLING.....	7
5.4 NEAR-SURFACE SOIL SAMPLING.....	7
5.5 SUBSURFACE SOIL SAMPLING WITH A HAND AUGER.....	8
5.6 SUBSURFACE SOIL SAMPLING WITH A SPLIT-BARREL SAMPLER (ASTM D1586-84).....	9
5.7 SUBSURFACE SOL SAMPLING USING DIRECT PUSH TECHNOLOGY.....	10
5.8 EXCAVATION AND SAMPLING OF TEST PITS AND TRENCHES.....	10
5.8.1 Applicability.....	10
5.8.2 Test Pit and Trench Excavation.....	10
5.8.3 Sampling in Test Pits and Trenches.....	12
5.8.4 Backfilling of Trenches and Test Pits.....	15
5.9 RECORDS.....	15
6.0 REFERENCES.....	16
 <u>ATTACHMENTS</u>	
A SOIL & SEDIMENT SAMPLE LOG SHEET.....	17
B SPLIT-SPOON SAMPLER.....	18
C TEST PIT LOG.....	19
D REMOTE SAMPLE HOLDER FOR TEST PIT/TRENCH SAMPLING.....	20

Subject SOIL SAMPLING	Number SA-1.3	Page 2 of 20
	Revision 7	Effective Date 09/03

1.0 PURPOSE

This procedure discusses the methods used to collect surface, near surface, and subsurface soil samples. Additionally, it describes the method for sampling of test pits and trenches to determine subsurface soil and rock conditions, and recover small-volume or bulk samples.

2.0 SCOPE

This procedure is applicable to the collection of surface, near surface and subsurface soils for laboratory testing, which are exposed through hand digging, hand augering, drilling, or machine excavating at hazardous substance sites.

3.0 GLOSSARY

Composite Sample - A composite sample exists as a combination of more than one sample at various locations and/or depths and times, which is homogenized and treated as one sample. This type of sample is usually collected when determination of an average waste concentration for a specific area is required. Composite samples are not to be collected for volatile organics analysis.

Grab Sample - One sample collected at one location and at one specific time.

Non-Volatile Sample - A non-volatile sample includes all other chemical parameters (e.g., semivolatiles, pesticides/PCBs, metals, etc.) and those engineering parameters that do not require undisturbed soil for their analysis.

Hand Auger - A sampling device used to extract soil from the ground in a relatively undisturbed form.

Thin-Walled Tube Sampler - A thin-walled metal tube (also called a Shelby tube) used to recover relatively undisturbed soil samples. These tubes are available in various sizes, ranging from 2 to 5 inches outside diameter (OD) and from 18 to 54 inches in length.

Split-Barrel Sampler - A steel tube, split in half lengthwise, with the halves held together by threaded collars at either end of the tube. Also called a split-spoon sampler, this device can be driven into resistant materials using a drive weight mounted in the drilling string. A standard split-barrel sampler is typically available in two common lengths, providing either 20-inch or 26-inch longitudinal clearance for obtaining 18-inch or 24-inch-long samples, respectively. These split-barrel samplers commonly range in size from 2-inch OD to 3-1/2 inch OD. The larger sizes are commonly used when a larger volume of sample material is required.

Test Pit and Trench - Open, shallow excavations, typically rectangular (if a test pit) or longitudinal (if a trench), excavated to determine the shallow subsurface conditions for engineering, geological, and soil chemistry exploration and/or sampling purposes. These pits are excavated manually or by machine (e.g., backhoe, clamshell, trencher excavator, or bulldozer).

Confined Space - As stipulated in 29 CFR 1910.146, a confined space means a space that: 1) is large enough and so configured that an employee can bodily enter and perform assigned work; 2) has limited or restricted means for entry or exit (for example tanks, vessels, silos, storage bins, hoppers, vaults, pits, and excavations); and 3) is not designed for continuous employee occupancy. TtNUS considers all confined space as permit-required confined spaces.

Subject SOIL SAMPLING	Number SA-1.3	Page 3 of 20
	Revision 7	Effective Date 09/03

4.0 RESPONSIBILITIES

Project Manager - The Project Manager is responsible for determining sampling objectives, as well as, the field procedures used in the collection of soil samples. Additionally, in consultation with other project personnel (geologist, hydrogeologist, etc.), the Project Manager establishes the need for test pits or trenches, and determines their approximate locations and dimensions.

Site Safety Officer (SSO) - The SSO (or a qualified designee) is responsible for providing the technical support necessary to implement the project Health and Safety Plan. This will include (but not be limited to) performing air quality monitoring during sampling, boring and excavation activities, and to ensure that workers and offsite (downwind) individuals are not exposed to hazardous levels of airborne contaminants. The SSO/designee may also be required to advise the FOL on other safety-related matters regarding boring, excavation and sampling, such as mitigative measures to address potential hazards from unstable trench walls, puncturing of drums or other hazardous objects, etc.

Field Operations Leader (FOL) - The FOL is responsible for finalizing the location of surface, near surface, and subsurface (hand and machine borings, test pits/trenches) soil samples. He/she is ultimately responsible for the sampling and backfilling of boreholes, test pits and trenches, and for adherence to OSHA regulations during these operations.

Project Geologist/Sampler - The project geologist/sampler is responsible for the proper acquisition of soil samples and the completion of all required paperwork (i.e., sample log sheets, field notebook, boring logs, test pit logs, container labels, custody seals, and chain-of-custody forms).

Competent Person - A Competent Person, as defined in 29 CFR 1929.650 of Subpart P - Excavations, means one who is capable of identifying existing and predictable hazards in the surroundings, or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them.

5.0 PROCEDURES

5.1 Overview

Soil sampling is an important adjunct to groundwater monitoring. Sampling of the soil horizons above the groundwater table can detect contaminants before they have migrated into the water table, and can establish the amount of contamination sorbed on aquifer solids that have the potential of contributing to groundwater contamination.

Soil types can vary considerably on a hazardous waste site. These variations, along with vegetation, can affect the rate of contaminant migration through the soil. It is important, therefore, that a detailed record be maintained during the sampling operations, particularly noting the location, depth, and such characteristics as grain size, color, and odor. Subsurface conditions are often stable on a daily basis and may demonstrate only slight seasonal variation especially with respect to temperature, available oxygen and light penetration. Changes in any of these conditions can radically alter the rate of chemical reactions or the associated microbiological community, thus further altering specific site conditions. As a result, samples must be kept at their at-depth temperature or lower, protected from direct light, sealed tightly in approved glass containers, and be analyzed as soon as possible.

The physical properties of the soil, its grain size, cohesiveness, associated moisture, and such factors as depth to bedrock and water table, will limit the depth from which samples can be collected and the method required to collect them. Often this information on soil properties can be obtained from published soil surveys available through the U.S. Geological Surveys and other government or farm agencies. It is the

Subject SOIL SAMPLING	Number SA-1.3	Page 4 of 20
	Revision 7	Effective Date 09/03

intent of this procedure to present the most commonly employed soil sampling methods used at hazardous waste sites.

5.2 Soil Sample Collection

5.2.1 Procedure for Collecting Soil Samples for Volatile Organic Compounds

The above described traditional sampling techniques, used for the collection of soil samples for volatile organic analysis, have recently been evaluated by the scientific community and determined to be ineffective in producing accurate results (biased low) due to the loss of volatile organics in the sampling stages and microbial degradation of aromatic volatiles. One of the newly adopted sampling procedures for collecting soil samples includes the field preservation of samples with methanol or sodium bisulfate to minimize volatilization and biodegradation. These preservation methods may be performed either in the field or laboratory, depending on the sampling methodology employed.

Soil samples to be preserved by the laboratory are currently being performed using method SW-846, 5035. Laboratories are currently performing low level analyses (sodium bisulfate preservation) and high level analyses (methanol preservation) depending on the end users needs.

It should be noted that a major disadvantage of the methanol preservation method is that the laboratory reporting limits will be higher than conventional testing. The reporting levels using the new method for most analytes are 0.5 µg/g for GC/MS and 0.05 µg/g for GC methods.

The alternative preservation method for collecting soil samples is with sodium bisulfate. This method is more complex to perform in the field and therefore is not preferred for field crews. It should also be noted that currently, not all laboratories have the capabilities to perform this analysis. The advantage to this method is that the reporting limits (0.001 µg/g for GC/PID or GC/ELCD, or 0.010 for GC/MS) are lower than those described above.

The following procedures outline the necessary steps for collecting soil samples to be preserved at the laboratory, and for collecting soil samples to be preserved in the field with methanol or sodium bisulfate.

5.2.1.1 Soil Samples to be Preserved at the Laboratory

Soil samples collected for volatile organics that are to be preserved at the laboratory will be obtained using a hermetically sealed sample vial such as an EnCore™ sampler. Each sample will be obtained using a reusable sampling handle provided with the EnCore™ sampler. The sample is collected by pushing the EnCore™ sampler directly into the soil, ensuring that the sampler is packed tight with soil, leaving zero headspace. Using this type of sampling device eliminates the need for field preservation and the shipping restrictions associated with preservatives. A complete set of instructions is included with each EnCore™ sampler shipment by the manufacturer.

Once the sample is collected, it should be placed on ice immediately and shipped to the laboratory within 48 hours (following the chain-of-custody and documentation procedures outlined in SOP SA-6.1). Samples must be preserved by the laboratory within 48 hours of sample collection.

If the lower detection limits are necessary, an option would be to collect several EnCore™ samplers at a given sample location. Send all samplers to the laboratory and the laboratory can perform the required preservation and analyses.

Subject SOIL SAMPLING	Number SA-1.3	Page 5 of 20
	Revision 7	Effective Date 09/03

5.2.1.2 Soil Samples to be Preserved in the Field

Soil samples preserved in the field may be prepared for analyses using both the low-level (sodium bisulfate preservation) method and medium-level (methanol preservation) method.

Methanol Preservation (Medium Level):

Soil samples to be preserved in the field with methanol will utilize 40-60 mL glass vials with septum lids. Each sample bottle will be filled with 25 mL of demonstrated analyte-free purge and trap grade methanol. Bottles may be prespiked with methanol in the laboratory or prepared in the field.

Soil will be collected with the use of a decontaminated (or disposable), small-diameter coring device such as a disposable tube/plunger-type syringe with the tip cut off. The outside diameter of the coring device must be smaller than the inside diameter of the sample bottle neck.

A small electronic balance or manual scale will be necessary for measuring the volume of soil to be added to the methanol preserved sample bottle. Calibration of the scale should be performed prior to use and intermittently throughout the day according to the manufacturers requirements.

The sample should be collected by pulling the plunger back and inserting the syringe into the soil to be sampled. The top several inches of soil should be removed before collecting the sample. Approximately 10 grams \pm 2g (8-12 grams) of soil should be collected. The sample should be weighed and adjusted until obtaining the required amount of sample. The sample weight should be recorded to the nearest 0.01 gram in the field logbook and/or sample log sheet. The soil should then be extruded into the methanol preserved sample bottle taking care not to contact the sample container with the syringe. The threads of the bottle and cap must be free of soil particles.

After capping the bottle, swirl the sample (do not shake) in the methanol and break up the soil such that all of the soil is covered with methanol. Place the sample on ice immediately and prepare for shipment to the laboratory as described in SOP SA-6.1.

Sodium Bisulfate Preservation (Low Level):

Samples to be preserved using the sodium bisulfate method are to be prepared as follows:

Add 1 gram of sodium bisulfate to 5 mL of laboratory grade deionized water in a 40-60 mL glass vial with septum lid. Bottles may be prespiked in the laboratory or prepared in the field. The soil sample should be collected in a manner as described above and added to the sample container. The sample should be weighed to the nearest 0.01 gram as described above and recorded in the field logbook or sample log sheet.

Care should be taken when adding the soil to the sodium bisulfate solution. A chemical reaction of soils containing carbonates (limestone) may cause the sample to effervesce or the vial to possibly explode.

When preparing samples using the sodium bisulfate preservation method, duplicate samples must be collected using the methanol preservation method on a one for one sample basis. The reason for this is because it is necessary for the laboratory to perform both the low level and medium level analyses. Place the sample on ice immediately and prepare for shipment to the laboratory as described in SOP SA-6.1.

If the lower detection limits are necessary, an option to field preserving with sodium bisulfate would be to collect 3 EnCore™ samplers at a given sample location. Send all samplers to the laboratory and the laboratory can perform the required preservation and analyses.

Subject SOIL SAMPLING	Number SA-1.3	Page 6 of 20
	Revision 7	Effective Date 09/03

5.2.2 Procedure for Collecting Non-Volatile Soil Samples

Non-volatile soil samples may be collected as either grab or composite samples. The non-volatile soil sample is thoroughly mixed in a stainless steel or disposable, inert plastic tray, using a stainless steel trowel or other approved tool, then transferred into the appropriate sample container(s). Head space is permitted in a non-volatile soil sample container to allow for sample expansion.

5.2.3 Procedure for Collecting Undisturbed Soil Samples (ASTM D1587-83)

When it is necessary to acquire undisturbed samples of soil for purposes of engineering parameter analysis (e.g., permeability), a thin-walled, seamless tube sampler (Shelby tube) will be employed. The following method will be used:

1. Remove all surface debris (e.g., vegetation, roots, twigs, etc.) from the specific sampling location and drill and clean out the borehole to the sampling depth, being careful to minimize the chance for disturbance of the material to be sampled. In saturated material, withdraw the drill bit slowly to prevent loosening of the soil around the borehole and to maintain the water level in the hole at or above groundwater level.
2. The use of bottom discharge bits or jetting through an open-tube sampler to clean out the borehole shall not be allowed. Use of any side-discharge bits is permitted.
3. A stationary piston-type sampler may be required to limit sample disturbance and aid in retaining the sample. Either the hydraulically operated or control rod activated-type of stationary piston sampler may be used. Prior to inserting the tube sampler into the borehole, check to ensure that the sampler head contains a check valve. The check valve is necessary to keep water in the rods from pushing the sample out the tube sampler during sample withdrawal and to maintain a suction within the tube to help retain the sample.
4. To minimize chemical reaction between the sample and the sampling tube, brass tubes may be required, especially if the tube is stored for an extended time prior to testing. While steel tubes coated with shellac are less expensive than brass, they're more reactive, and shall only be used when the sample will be tested within a few days after sampling or if chemical reaction is not anticipated. With the sampling tube resting on the bottom of the hole and the water level in the boring at groundwater level or above, push the tube into the soil by a continuous and rapid motion, without impacting or twisting. In no case shall the tube be pushed farther than the length provided for the soil sample. Allow about 3 inches in the tube for cuttings and sludge.
5. Upon removal of the sampling tube from the hole, measure the length of sample in the tube and also the length penetrated. Remove disturbed material in the upper end of the tube and measure the length of sample again. After removing at least an inch of soil from the lower end and after inserting an impervious disk, seal both ends of the tube with at least a 1/2-inch thickness of wax applied in a way that will prevent the wax from entering the sample. Clean filler must be placed in voids at either end of the tube prior to sealing with wax. Place plastic caps on the ends of the sample tube, tape the caps in place, and dip the ends in wax.
6. Affix label(s) to the tube as required and record sample number, depth, penetration, and recovery length on the label. Mark the "up" direction on the side of the tube with indelible ink, and mark the end of the sample. Complete Chain-of-Custody (see SOP SA-6.3) and other required forms (including Attachment A of this SOP). Do not allow tubes to freeze, and store the samples vertically with the same orientation they had in the ground, (i.e., top of sample is up) in a cool place out of the sun at all times. Ship samples protected with suitable resilient packing material to reduce shock, vibration, and disturbance.

Subject SOIL SAMPLING	Number SA-1.3	Page 6 of 20
	Revision 7	Effective Date 09/03

5.2.2 Procedure for Collecting Non-Volatile Soil Samples

Non-volatile soil samples may be collected as either grab or composite samples. The non-volatile soil sample is thoroughly mixed in a stainless steel or disposable, inert plastic tray, using a stainless steel trowel or other approved tool, then transferred into the appropriate sample container(s). Head space is permitted in a non-volatile soil sample container to allow for sample expansion.

5.2.3 Procedure for Collecting Undisturbed Soil Samples (ASTM D1587-83)

When it is necessary to acquire undisturbed samples of soil for purposes of engineering parameter analysis (e.g., permeability), a thin-walled, seamless tube sampler (Shelby tube) will be employed. The following method will be used:

1. Remove all surface debris (e.g., vegetation, roots, twigs, etc.) from the specific sampling location and drill and clean out the borehole to the sampling depth, being careful to minimize the chance for disturbance of the material to be sampled. In saturated material, withdraw the drill bit slowly to prevent loosening of the soil around the borehole and to maintain the water level in the hole at or above groundwater level.
2. The use of bottom discharge bits or jetting through an open-tube sampler to clean out the borehole shall not be allowed. Use of any side-discharge bits is permitted.
3. A stationary piston-type sampler may be required to limit sample disturbance and aid in retaining the sample. Either the hydraulically operated or control rod activated-type of stationary piston sampler may be used. Prior to inserting the tube sampler into the borehole, check to ensure that the sampler head contains a check valve. The check valve is necessary to keep water in the rods from pushing the sample out the tube sampler during sample withdrawal and to maintain a suction within the tube to help retain the sample.
4. To minimize chemical reaction between the sample and the sampling tube, brass tubes may be required, especially if the tube is stored for an extended time prior to testing. While steel tubes coated with shellac are less expensive than brass, they're more reactive, and shall only be used when the sample will be tested within a few days after sampling or if chemical reaction is not anticipated. With the sampling tube resting on the bottom of the hole and the water level in the boring at groundwater level or above, push the tube into the soil by a continuous and rapid motion, without impacting or twisting. In no case shall the tube be pushed farther than the length provided for the soil sample. Allow about 3 inches in the tube for cuttings and sludge.
5. Upon removal of the sampling tube from the hole, measure the length of sample in the tube and also the length penetrated. Remove disturbed material in the upper end of the tube and measure the length of sample again. After removing at least an inch of soil from the lower end and after inserting an impervious disk, seal both ends of the tube with at least a 1/2-inch thickness of wax applied in a way that will prevent the wax from entering the sample. Clean filler must be placed in voids at either end of the tube prior to sealing with wax. Place plastic caps on the ends of the sample tube, tape the caps in place, and dip the ends in wax.
6. Affix label(s) to the tube as required and record sample number, depth, penetration, and recovery length on the label. Mark the "up" direction on the side of the tube with indelible ink, and mark the end of the sample. Complete Chain-of-Custody (see SOP SA-6.3) and other required forms (including Attachment A of this SOP). Do not allow tubes to freeze, and store the samples vertically with the same orientation they had in the ground, (i.e., top of sample is up) in a cool place out of the sun at all times. Ship samples protected with suitable resilient packing material to reduce shock, vibration, and disturbance.

Subject SOIL SAMPLING	Number SA-1.3	Page 7 of 20
	Revision 7	Effective Date 09/03

Thin-walled undisturbed tube samplers are restricted in their usage by the consistency of the soil to be sampled. Often, very loose and/or wet samples cannot be retrieved by the samplers, and soils with a consistency in excess of very stiff cannot be penetrated by the sampler. Devices such as Dennison or Pitcher core samplers can be used to obtain undisturbed samples of stiff soils. Using these devices normally increases sampling costs, and therefore their use shall be weighed against the need for acquiring an undisturbed sample.

5.3 Surface Soil Sampling

The simplest, most direct method of collecting surface soil samples (most commonly collected to a depth of 6 inches) for subsequent analysis is by use of a stainless steel trowel. Surface soils are considered 0-12 inches bgs.

In general, the following equipment is necessary for obtaining surface soil samples:

- Stainless steel or pre-cleaned disposable trowel.
- Real-time air monitoring instrument (e.g., PID, FID, etc.).
- Latex gloves.
- Required Personal Protective Equipment (PPE).
- Required paperwork (see SOP SA-6.3 and Attachment A of this SOP).
- Required decontamination equipment.
- Required sample container(s).
- Wooden stakes or pin flags.
- Sealable polyethylene bags (i.e., Ziploc® baggies).
- Heavy duty cooler.
- Ice.
- Chain-of-custody records and custody seals.

When acquiring surface soil samples, the following procedure shall be used:

1. Carefully remove vegetation, roots, twigs, litter, etc., to expose an adequate soil surface area to accommodate sample volume requirements.
2. Using a decontaminated stainless steel trowel, follow the procedure cited in Section 5.2.1 for collecting a volatile soil sample. Surface soil samples for volatile organic analysis should be collected from 6-12 inches bgs only.
3. Thoroughly mix (in-situ) a sufficient amount of soil to fill the remaining sample containers and transfer the sample into those containers utilizing the same stainless steel trowel employed above. Cap and securely tighten all sample containers.
4. Affix a sample label to each container. Be sure to fill out each label carefully and clearly, addressing all the categories described in SOP SA-6.3.
5. Proceed with the handling and processing of each sample container as described in SOP SA-6.2.

5.4 Near-Surface Soil Sampling

Collection of samples from near the surface (depth of 6-18 inches) can be accomplished with tools such as shovels and stainless steel or pre-cleaned disposable trowels.

Subject SOIL SAMPLING	Number SA-1.3	Page 8 of 20
	Revision 7	Effective Date 09/03

The following equipment is necessary to collect near surface soil samples:

- Clean shovel.
- The equipment listed under Section 5.3 of this procedure.
- Hand auger.

To obtain near-surface soil samples, the following protocol shall be observed:

1. With a clean shovel, make a series of vertical cuts to the depth required in the soil to form a square approximately 1 foot by 1 foot.
2. Lever out the formed plug and scrape the bottom of the freshly dug hole with a decontaminated stainless steel or pre-cleaned disposable trowel to remove any loose soil.
3. Follow steps 2 through 5 listed under Section 5.3 of this procedure.

5.5 Subsurface Soil Sampling With a Hand Auger

A hand augering system generally consists of a variety of all stainless steel bucket bits (i.e., cylinders 6-1/2" long, and 2-3/4", 3-1/4", and 4" in diameter), a series of extension rods (available in 2', 3', 4' and 5' lengths), and a cross handle. A larger diameter bucket bit is commonly used to bore a hole to the desired sampling depth and then withdrawn. In turn, the larger diameter bit is replaced with a smaller diameter bit, lowered down the hole, and slowly turned into the soil at the completion depth (approximately 6 inches). The apparatus is then withdrawn and the soil sample collected.

The hand auger can be used in a wide variety of soil conditions. It can be used to sample soil both from the surface, or to depths in excess of 12 feet. However, the presence of rock layers and the collapse of the borehole normally contribute to its limiting factors.

To accomplish soil sampling using a hand augering system, the following equipment is required:

- Complete hand auger assembly (variety of bucket bit sizes).
- Stainless steel mixing bowls.
- The equipment listed under Section 5.3 of this procedure.

To obtain soil samples using a hand auger, the following procedure shall be followed:

1. Attach a properly decontaminated bucket bit to a clean extension rod and further attach the cross handle to the extension rod.
2. Clear the area to be sampled of any surface debris (vegetation, twigs, rocks, litter, etc.).
3. Begin augering (periodically removing accumulated soils from the bucket bit) and add additional rod extensions as necessary. Also, note (in a field notebook, boring log, and/or on standardized data sheets) any changes in the color, texture or odor of the soil.
4. After reaching the desired depth, slowly and carefully withdraw the apparatus from the borehole.
5. Remove the soiled bucket bit from the rod extension and replace it with another properly decontaminated bucket bit. The bucket bit used for sampling is commonly smaller in diameter than the bucket bit employed to initiate the borehole.

Subject SOIL SAMPLING	Number SA-1.3	Page 9 of 20
	Revision 7	Effective Date 09/03

6. Carefully lower the apparatus down the borehole. Care must be taken to avoid scraping the borehole sides.
7. Slowly turn the apparatus until the bucket bit is advanced approximately 6 inches.
8. Discard the top of the core (approximately 1"), which represents any loose material collected by the bucket bit before penetrating the sample material.
9. Fill volatile sample container(s), using a properly decontaminated stainless steel trowel, with sample material directly from the bucket bit. Refer to Section 5.2.1 of this procedure.
10. Utilizing the above trowel, remove the remaining sample material from the bucket bit and place into a properly decontaminated stainless steel mixing bowl and thoroughly homogenize the sample material prior to filling the remaining sample containers. Refer to Section 5.2.2 of this procedure.
11. Follow steps 4 and 5 listed under Section 5.3 of this procedure.

5.6 Subsurface Soil Sampling With a Split-Barrel Sampler (ASTM D1586-84)

Split-barrel (split-spoon) samplers consist of a heavy carbon steel or stainless steel sampling tube that can be split into two equal halves to reveal the soil sample (see Attachment B). A drive head is attached to the upper end of the tube and serves as a point of attachment for the drill rod. A removable tapered nosepiece/drive shoe attaches to the lower end of the tube and facilitates cutting. A basket-like sample retainer can be fitted to the lower end of the split tube to hold loose, dry soil samples in the tube when the sampler is removed from the drill hole. This split-barrel sampler is made to be attached to a drill rod and forced into the ground by means of a 140-lb. or larger casing driver.

Split-barrel samplers are used to collect soil samples from a wide variety of soil types and from depths greater than those attainable with other soil sampling equipment.

The following equipment is used for obtaining split-barrel samples:

- Drilling equipment (provided by subcontractor).
- Split-barrel samplers (O.D. 2 inches, I.D. 1-3/8 inches, either 20 inches or 26 inches long); Larger O.D. samplers are available if a larger volume of sample is needed.
- Drive weight assembly, 140-lb. weight, driving head and guide permitting free fall of 30 inches.
- Stainless steel mixing bowls.
- Equipment listed under Section 5.3 of this procedure.

The following steps shall be followed to obtain split-barrel samples:

1. Remove the drive head and nosepiece, and open the sampler to reveal the soil sample. Immediately scan the sample core with a real-time air monitoring instrument (e.g., FID, PID, etc.). Carefully separate the soil core, with a decontaminated stainless steel knife or trowel, at about 6-inch intervals while scanning the center of the core for elevated readings. Also scan stained soil, soil lenses, and anomalies (if present), and record readings.
2. Collect the volatile sample from the center of the core where elevated readings occurred. If no elevated readings were encountered the sample material should still be collected from the core's

Subject SOIL SAMPLING	Number SA-1.3	Page 10 of 20
	Revision 7	Effective Date 09/03

center (this area represents the least disturbed area with minimal atmospheric contact). Refer to Section 5.2.1 of this procedure.

- Using the same trowel, remove remaining sample material from the split-barrel sampler (except for the small portion of disturbed soil usually found at the top of the core sample) and place the soil into a decontaminated stainless steel mixing bowl. Thoroughly homogenize the sample material prior to filling the remaining sample containers. Refer to Section 5.2.2 of this procedure.
- Follow steps 4 and 5 listed under Section 5.3 of this procedure.

5.7 Subsurface Sol Sampling Using Direct Push Technology

Subsurface soil samples can be collected to depths of 40+ feet using direct push technology (DPT). DPT equipment, responsibilities, and procedures are described in SOP SA-2.5.

5.8 Excavation and Sampling of Test Pits and Trenches

5.8.1 Applicability

This subsection presents routine test pit or trench excavation techniques and specialized techniques that are applicable under certain conditions.

During the excavation of trenches or pits at hazardous waste sites, several health and safety concerns arise which control the method of excavation. No personnel shall enter any test pit or excavation over 4 feet deep except as a last resort, and then only under direct supervision of a Competent Person (as defined in 29 CFR 1929.650 of Subpart P - Excavations). Whenever possible, all required chemical and lithological samples should be collected using the excavator bucket or other remote sampling apparatus. If entrance is still required, all test pits or excavations must be stabilized by bracing the pit sides using specifically designed wooden or steel support structures. Personnel entering the excavation may be exposed to toxic or explosive gases and oxygen-deficient environments. Any entry may constitute a Confined Space and must be done in conformance with all applicable regulations. In these cases, substantial air monitoring is required before entry, and appropriate respiratory gear and protective clothing is mandatory. There must be at least two persons present at the immediate site before entry by one of the investigators. The reader shall refer to OSHA regulations 29 CFR 1926, 29 CFR 1910.120, 29 CFR 1910.134, and 29 CFR 1910.146.

Excavations are generally not practical where a depth of more than about 15 feet is desired, and they are usually limited to a few feet below the water table. In some cases, a pumping system may be required to control water levels within the pit, providing that pumped water can be adequately stored or disposed. If data on soils at depths greater than 15 feet are required, the data are usually obtained through test borings instead of test pits.

In addition, hazardous wastes may be brought to the surface by excavation equipment. This material, whether removed from the site or returned to the subsurface, must be properly handled according to any and all applicable federal, state, and local regulations.

5.8.2 Test Pit and Trench Excavation

These procedures describe the methods for excavating and logging test pits and trenches excavated to determine subsurface soil and rock conditions. Test pit operations shall be logged and documented (see Attachment C).

Subject SOIL SAMPLING	Number SA-1.3	Page 11 of 20
	Revision 7	Effective Date 09/03

Test pits and trenches may be excavated by hand or by power equipment to permit detailed description of the nature and contamination of the in-situ materials. The size of the excavation will depend primarily on the following:

- The purpose and extent of the exploration.
- The space required for efficient excavation.
- The chemicals of concern.
- The economics and efficiency of available equipment.

Test pits normally have a cross section that is 4 to 10 feet square; test trenches are usually 3 to 6 feet wide and may be extended for any length required to reveal conditions along a specific line. The following table, which is based on equipment efficiencies, gives a rough guide for design consideration:

Equipment	Typical Widths, in Feet
Trenching machine	2
Backhoe	2-6
Track dozer	10
Track loader	10
Excavator	10
Scraper	20

The lateral limits of excavation of trenches and the position of test pits shall be carefully marked on area base maps. If precise positioning is required to indicate the location of highly hazardous waste materials, nearby utilities, or dangerous conditions, the limits of the excavation shall be surveyed. Also, if precise determination of the depth of buried materials is needed for design or environmental assessment purposes, the elevation of the ground surface at the test pit or trench location shall also be determined by survey. If the test pit/trench will not be surveyed immediately, it shall be backfilled and its position identified with stakes placed in the ground at the margin of the excavation for later surveying.

The construction of test pits and trenches shall be planned and designed in advance as much as possible. However, field conditions may necessitate revisions to the initial plans. The final depth and construction method shall be determined by the field geologist. The actual layout of each test pit, temporary staging area, and spoils pile will be predicated based on site conditions and wind direction at the time the test pit is made. Prior to excavation, the area can be surveyed by magnetometer or metal detector to identify the presence of underground utilities or drums.

As mentioned previously, no personnel shall enter any test pit or excavation except as a last resort, and then only under direct supervision of a Competent Person. If entrance is still required, Occupational Safety and Health Administration (OSHA) requirements must be met (e.g., walls must be braced with wooden or steel braces, ladders must be in the hole at all times, and a temporary guardrail must be placed along the surface of the hole before entry). It is emphasized that the project data needs should be structured such that required samples can be collected without requiring entrance into the excavation. For example, samples of leachate, groundwater, or sidewall soils can be taken with telescoping poles, etc.

Dewatering may be required to assure the stability of the side walls, to prevent the bottom of the pit from heaving, and to keep the excavation dry. This is an important consideration for excavations in cohesionless material below the groundwater table. Liquids removed as a result of dewatering operations must be handled as potentially contaminated materials. Procedures for the collection and disposal of such materials should be discussed in the site-specific project plans.

Subject SOIL SAMPLING	Number SA-1.3	Page 12 of 20
	Revision 7	Effective Date 09/03

5.8.3 Sampling in Test Pits and Trenches

5.8.3.1 General

Test pits and trenches are usually logged as they are excavated. Records of each test pit/trench will be made as presented in Attachment C. These records include plan and profile sketches of the test pit/trench showing materials encountered, their depth and distribution in the pit/trench, and sample locations. These records also include safety and sample screening information.

Entry of test pits by personnel is extremely dangerous, shall be avoided unless absolutely necessary, and can occur only after all applicable Health and Safety and OSHA requirements have been met.

The final depth and type of samples obtained from each test pit will be determined at the time the test pit is excavated. Sufficient samples are usually obtained and analyzed to quantify contaminant distribution as a function of depth for each test pit. Additional samples of each waste phase and any fluids encountered in each test pit may also be collected.

In some cases, samples of soil may be extracted from the test pit for reasons other than waste sampling and chemical analysis, for instance, to obtain geotechnical information. Such information would include soil types, stratigraphy, strength, etc., and could therefore entail the collection of disturbed (grab or bulk) or relatively undisturbed (hand-carved or pushed/driven) samples, which can be tested for geotechnical properties. The purposes of such explorations are very similar to those of shallow exploratory or test borings, but often test pits offer a faster, more cost-effective method of sampling than installing borings.

5.8.3.2 Sampling Equipment

The following equipment is needed for obtaining samples for chemical or geotechnical analysis from test pits and trenches:

- Backhoe or other excavating machinery.
- Shovels, picks, hand augers, and stainless steel trowels/disposable trowels.
- Sample container - bucket with locking lid for large samples; appropriate bottleware for chemical or geotechnical analysis samples.
- Polyethylene bags for enclosing sample containers; buckets.
- Remote sampler consisting of 10-foot sections of steel conduit (1-inch-diameter), hose clamps and right angle adapter for conduit (see Attachment D).

5.8.3.3 Sampling Methods

The methods discussed in this section refer to test pit sampling from grade level. If test pit entry is required, see Section 5.8.3.4.

- Excavate trench or pit in several depth increments. After each increment, the operator will wait while the sampler inspects the test pit from grade level to decide if conditions are appropriate for sampling. (Monitoring of volatiles by the SSO will also be used to evaluate the need for sampling.) Practical depth increments range from 2 to 4 feet.

Subject SOIL SAMPLING	Number SA-1.3	Page 13 of 20
	Revision 7	Effective Date 09/03

- The backhoe operator, who will have the best view of the test pit, will immediately cease digging if:
 - Any fluid phase or groundwater seepage is encountered in the test pit.
 - Any drums, other potential waste containers, obstructions or utility lines are encountered.
 - Distinct changes of material are encountered.

This action is necessary to permit proper sampling of the test pit and to prevent a breach of safety protocol. Depending upon the conditions encountered, it may be required to excavate more slowly and carefully with the backhoe.

For obtaining test pit samples from grade level, the following procedure shall be followed:

- Remove loose material to the greatest extent possible with backhoe.
- Secure walls of pit if necessary. (There is seldom any need to enter a pit or trench which would justify the expense of shoring the walls. All observations and samples should be taken from the ground surface.)
- Samples of the test pit material are to be obtained either directly from the backhoe bucket or from the material once it has been deposited on the ground. The sampler or Field Operations Leader directs the backhoe operator to remove material from the selected depth or location within the test pit/trench. The bucket is brought to the surface and moved away from the pit. The sampler and/or SSO then approaches the bucket and monitors its contents with a photoionization or flame ionization detector. The sample is collected from the center of the bucket or pile and placed in sample containers using a decontaminated stainless steel trowel or disposable spatula.
- If a composite sample is desired, several depths or locations within the pit/trench are selected and a bucket is filled from each area. It is preferable to send individual sample bottles filled from each bucket to the laboratory for compositing under the more controlled laboratory conditions. However, if compositing in the field is required, each sample container shall be filled from materials that have been transferred into a mixing bucket and homogenized. Note that homogenization/compositing is not applicable for samples to be subjected to volatile organic analysis.
- Using the remote sampler shown in Attachment D, samples can be taken at the desired depth from the side wall or bottom of the pit. The face of the pit/trench shall first be scraped (using a long-handled shovel or hoe) to remove the smeared zone that has contacted the backhoe bucket. The sample shall then be collected directly into the sample jar, by scraping with the jar edge, eliminating the need to utilize samplers and minimizing the likelihood of cross-contamination. The sample jar is then capped, removed from the assembly, and packaged for shipment.
- Complete documentation as described in SOP SA-6.3 and Attachment C of this SOP.

5.8.3.4 In-Pit Sampling

Under rare conditions, personnel may be required to enter the test pit/trench. This is necessary only when soil conditions preclude obtaining suitable samples from the backhoe bucket (e.g., excessive mixing of soils or wastes within the test pit/trench) or when samples from relatively small discrete zones within the test pit are required. This approach may also be necessary to sample any seepage occurring at discrete levels or zones in the test pit that are not accessible with remote samplers.

In general, personnel shall sample and log pits and trenches from the ground surface, except as provided for by the following criteria:

Subject SOIL SAMPLING	Number SA-1.3	Page 14 of 20
	Revision 7	Effective Date 09/03

- There is no practical alternative means of obtaining such data.
- The Site Safety Officer and Competent Person determines that such action can be accomplished without breaching site safety protocol. This determination will be based on actual monitoring of the pit/trench after it is dug (including, at a minimum, measurements of volatile organics, explosive gases and available oxygen).
- A Company-designated Competent Person determines that the pit/trench is stable or is made stable (by grading the sidewalls or using shoring) prior to entrance of any personnel. OSHA requirements must be strictly observed.

If these conditions are satisfied, one person will enter the pit/trench. On potentially hazardous waste sites, this individual will be dressed in safety gear as required by the conditions in the pit. He/she will be affixed to a safety rope and continuously monitored while in the pit.

A second individual will be fully dressed in protective clothing including a self-contained breathing device and on standby during all pit entry operations. The individual entering the pit will remain therein for as brief a period as practical, commensurate with performance of his/her work. After removing the smeared zone, samples shall be obtained with a decontaminated trowel or spoon. As an added precaution, it is advisable to keep the backhoe bucket in the test pit when personnel are working below grade. Such personnel can either stand in or near the bucket while performing sample operations. In the event of a cave-in they can either be lifted clear in the bucket, or at least climb up on the backhoe arm to reach safety.

5.8.3.5 Geotechnical Sampling

In addition to the equipment described in Section 5.8.3.2, the following equipment is needed for geotechnical sampling:

- Soil sampling equipment, similar to that used in shallow drilled boring (i.e., open tube samplers), which can be pushed or driven into the floor of the test pit.
- Suitable driving (i.e., a sledge hammer) or pushing (i.e., the backhoe bucket) equipment which is used to advance the sampler into the soil.
- Knives, spatulas, and other suitable devices for trimming hand-carved samples.
- Suitable containers (bags, jars, tubes, boxes, etc.), labels, wax, etc. for holding and safely transporting collected soil samples.
- Geotechnical equipment (pocket penetrometer, torvane, etc.) for field testing collected soil samples for classification and strength properties.

Disturbed grab or bulk geotechnical soil samples may be collected for most soils in the same manner as comparable soil samples for chemical analysis. These collected samples may be stored in jars or plastic-lined sacks (larger samples), which will preserve their moisture content. Smaller samples of this type are usually tested for their index properties to aid in soil identification and classification, while larger bulk samples are usually required to perform compaction tests.

Relatively undisturbed samples are usually extracted in cohesive soils using open tube samplers, and such samples are then tested in a geotechnical laboratory for their strength, permeability and/or compressibility. The techniques for extracting and preserving such samples are similar to those used in performing Shelby tube sampling in borings, except that the sampler is advanced by hand or backhoe,

Subject SOIL SAMPLING	Number SA-1.3	Page 15 of 20
	Revision 7	Effective Date 09/03

rather than by a drill rig. Also, the sampler may be extracted from the test pit by excavation around the sampler when it is difficult to pull it out of the ground. If this excavation requires entry of the test pit, the requirements described in Section 5.8.3.4 of this procedure must be followed. The open tube sampler shall be pushed or driven vertically into the floor or steps excavated in the test pit at the desired sampling elevations. Extracting tube samples horizontally from the walls of the test pit is not appropriate, because the sample will not have the correct orientation.

A sledge hammer or the backhoe may be used to drive or push the sampler or tube into the ground. Place a piece of wood over the top of the sampler or sampling tube to prevent damage during driving/pushing of the sample. Pushing the sampler with a constant thrust is always preferable to driving it with repeated blows, thus minimizing disturbance to the sample. If the sample cannot be extracted by rotating it at least two revolutions (to shear off the sample at the bottom), hand-excavate to remove the soil from around the sides of the sampler. If hand-excavation requires entry of the test pit, the requirements in Section 5.8.3.4 of this procedure must be followed. Prepare, label, pack and transport the sample in the required manner, as described in SOP SA-6.3 and SA-6.1.

5.8.4 Backfilling of Trenches and Test Pits

All test pits and excavations must be either backfilled, covered, or otherwise protected at the end of each day. No excavations shall remain open during non-working hours unless adequately covered or otherwise protected.

Before backfilling, the onsite crew shall photograph all significant features exposed by the test pit and trench and shall include in the photograph a scale to show dimensions. Photographs of test pits shall be marked to include site number, test pit number, depth, description of feature, and date of photograph. In addition, a geologic description of each photograph shall be entered in the site logbook. All photographs shall be indexed and maintained as part of the project file for future reference.

After inspection, backfill material shall be returned to the pit under the direction of the FOL.

If a low permeability layer is penetrated (resulting in groundwater flow from an upper contaminated flow zone into a lower uncontaminated flow zone), backfill material must represent original conditions or be impermeable. Backfill could consist of a soil-bentonite mix prepared in a proportion specified by the FOL (representing a permeability equal to or less than original conditions). Backfill can be covered by "clean" soil and graded to the original land contour. Revegetation of the disturbed area may also be required.

5.9 Records

The appropriate sample log sheet (see Attachment A of this SOP) must be completed by the site geologist/sampler. All soil sampling locations should be documented by tying in the location of two or more nearby permanent landmarks (building, telephone pole, fence, etc.) or obtaining GPS coordinates; and shall be noted on the appropriate sample log sheet, site map, or field notebook. Surveying may also be necessary, depending on the project requirements.

Test pit logs (see Attachment C of this SOP) shall contain a sketch of pit conditions. In addition, at least one photograph with a scale for comparison shall be taken of each pit. Included in the photograph shall be a card showing the test pit number. Boreholes, test pits and trenches shall be logged by the field geologist in accordance with SOP GH-1.5.

Other data to be recorded in the field logbook include the following:

- Name and location of job.
- Date of boring and excavation.

Subject SOIL SAMPLING	Number SA-1.3	Page 16 of 20
	Revision 7	Effective Date 09/03

- Approximate surface elevation.
- Total depth of boring and excavation.
- Dimensions of pit.
- Method of sample acquisition.
- Type and size of samples.
- Soil and rock descriptions.
- Photographs.
- Groundwater levels.
- Organic gas or methane levels.
- Other pertinent information, such as waste material encountered.

6.0 REFERENCES

American Society for Testing and Materials, 1987. ASTM Standards D1587-83 and D1586-84. ASTM Annual Book of Standards. ASTM. Philadelphia, Pennsylvania. Volume 4.08.


NUS Corporation, 1986. Hazardous Material Handling Training Manual.

NUS Corporation and CH2M Hill, August, 1987. Compendium of Field Operation Methods. Prepared for the U.S. EPA.

OSHA, Excavation, Trenching and Shoring 29 CFR 1926.650-653.

OSHA, Confined Space Entry 29 CFR 1910.146.

ATTACHMENT B SPLIT-SPOON SAMPLER



Subject

SOIL SAMPLING

Number

SA-1.3

Page

20 of 20


Revision

7

Effective Date

09/03

ATTACHMENT D
REMOTE SAMPLE HOLDER FOR TEST PIT/TRENCH SAMPLING



TtNUS SOP SA-7.1 – Decontamination of Field Equipment



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number

SA-7.1

Page

1 of 8

Effective Date

09/03

Revision

3

Applicability

Tetra Tech NUS, Inc.

Prepared

Earth Sciences Department

Subject DECONTAMINATION OF FIELD EQUIPMENT

Approved

D. Senovich

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 PURPOSE.....	2
2.0 SCOPE.....	2
3.0 GLOSSARY.....	2
4.0 RESPONSIBILITIES.....	3
5.0 PROCEDURES.....	3
5.1 DECONTAMINATION DESIGN/CONSTRUCTIONS CONSIDERATIONS.....	3
5.1.1 Temporary Decontamination Pads.....	3
5.1.2 Decontamination Activities at Drill Rigs/DPT Units.....	4
5.1.3 Decontamination Activities at Remote Sample Locations.....	5
5.2 EQUIPMENT DECONTAMINATION PROCEDURES.....	5
5.2.1 Monitoring Well Sampling Equipment.....	5
5.2.2 Down-Hole Drilling Equipment.....	6
5.2.3 Soil/Sediment Sampling Equipment.....	6
5.3 CONTACT WASTE/MATERIALS.....	7
5.3.1 Decontamination Solutions.....	7
5.4 DECONTAMINATION EVALUATION.....	7

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	2 of 8
		Revision	3	Effective Date	09/03

1.0 PURPOSE

Decontamination is the process of removing and/or neutralizing site contaminants that have contacted and/or accumulated on equipment. The objective/purpose of this SOP is intended to protect site personnel, general public, and the sample integrity through the prevention of cross contamination onto unaffected persons or areas. It is further intended through this procedure to provide guidelines regarding the appropriate procedures to be followed when decontaminating drilling equipment, monitoring well materials, chemical sampling equipment and field analytical equipment.

2.0 SCOPE

This procedure applies to all equipment including drilling equipment, heavy equipment, monitoring well materials, as well as chemical sampling and field analytical equipment decontamination that may be used to provide access/acquire environmental samples. Where technologically and economically feasible, single use sealed disposable equipment will be employed to minimize the potential for cross contamination. This procedure also provides general reference information on the control of contaminated materials.

3.0 GLOSSARY

Acid - For decontamination of equipment when sampling for trace levels of inorganics, a 10% solution of nitric acid in deionized water should be used. Due to the leaching ability of nitric acid, it should not be used on stainless steel.

Alconox/Liquinox - A brand of phosphate-free laboratory-grade detergent.

Decontamination Solution - Is a solution selected/identified within the Health and Safety Plan or Project-Specific Quality Assurance Plan. The solution is selected and employed as directed by the project chemist/health and safety professional.

Deionized Water (DI) - Deionized water is tap water that has been treated by passing through a standard deionizing resin column. This water may also pass through additional filtering media to attain various levels of analyte-free status. The DI water should meet CAP and NCCLS specifications for reagent grade, Type I water.

Potable Water - Tap water used from any municipal water treatment system. Use of an untreated potable water supply is not an acceptable substitute for tap water.

Pressure Washing - Employs high pressure pumps and nozzle configuration to create a high pressure spray of potable water. High pressure spray is employed to remove solids.

Solvent - The solvent of choice is pesticide-grade Isopropanol. Use of other solvents (methanol, acetone, pesticide-grade hexane, or petroleum ether) may be required for particular projects or for a particular purpose (e.g. for the removal of concentrated waste) and must be justified in the project planning documents. As an example, it may be necessary to use hexane when analyzing for trace levels of pesticides, PCBs, or fuels. In addition, because many of these solvents are not miscible in water, the equipment should be air dried prior to use. Solvents should not be used on PVC equipment or well construction materials.

Steam Pressure Washing - This method employs a high pressure spray of heated potable water. This method through the application of heat provides for the removal of various organic/inorganic compounds.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	3 of 8
		Revision	3	Effective Date	09/03

4.0 RESPONSIBILITIES

Project Manager - Responsible for ensuring that all field activities are conducted in accordance with approved project plan(s) requirements.

Field Operations Leader (FOL) - Responsible for the onsite verification that all field activities are performed in compliance with approved Standards Operating Procedures or as otherwise dictated by the approved project plan(s).

Site Health and Safety Officer (SHSO) - The SHSO exercises shared responsibility with the FOL concerning decontamination effectiveness. All equipment arriving on-site (as part of the equipment inspection), leaving the site, moving between locations are required to go through a decontamination evaluation. This is accomplished through visual examination and/or instrument screening to determine the effectiveness of the decontamination process. Failure to meet these objectives are sufficient to restrict equipment from entering the site/exiting the site/ or moving to a new location on the site until the objectives are successfully completed.

5.0 PROCEDURES

The process of decontamination is accomplished through the removal of contaminants, neutralization of contaminants, or the isolation of contaminants. In order to accomplish this activity a level of preparation is required. This includes site preparation, equipment selection, and evaluation of the process. Site contaminant types, concentrations, media types, are primary drivers in the selection of the types of decontamination as well as where it will be conducted. For purposes of this SOP discussion will be provided concerning general environmental investigation procedures.

The decontamination processes are typically employed at:

- Temporary Decontamination Pads/Facilities
- Sample Locations
- Centralized Decontamination Pad/Facilities
- Combination of some or all of the above

The following discussion represents recommended site preparation in support of the decontamination process.

5.1 Decontamination Design/Constructions Considerations

5.1.1 Temporary Decontamination Pads

Temporary decontamination pads are constructed at satellite locations in support of temporary work sites. These structures are generally constructed to support the decontamination of heavy equipment such as drill rigs and earth moving equipment but can be employed for smaller articles.

The purpose of the decontamination pad is to contain wash waters and potentially contaminated soils generated during decontamination procedures. Therefore, construction of these pads should take into account the following considerations

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	4 of 8
		Revision	3	Effective Date	09/03

- Site Location – The site selected should be within a reasonable distance from the work site but should avoid:
 - Pedestrian/Vehicle thoroughfares
 - Areas where control/custody cannot be maintained
 - Areas where a potential releases may be compounded through access to storm water transport systems, streams or other potentially sensitive areas.
 - Areas potentially contaminated.
- Pad – The pad should be constructed to provide the following characteristics
 - Size – The size of the pad should be sufficient to accept the equipment to be decontaminated as well as permitting free movement around the equipment by the personnel conducting the decontamination.
 - Slope – An adequate slope will be constructed to permit the collection of the water and potentially contaminated soils within a trough or sump constructed at one end. The collection point for wash waters should be of adequate distance that the decontamination workers do not have to walk through the wash waters while completing their tasks.
 - Sidewalls – The sidewalls should be a minimum of 6-inches in height to provide adequate containment for wash waters and soils. If splash represents a potential problem, splash guards should be constructed to control overspray. Sidewalls maybe constructed of wood, inflatables, sand bags, etc. to permit containment.
 - Liner – Depending on the types of equipment and the decontamination method the liner should be of sufficient thickness to provide a puncture resistant barrier between the decontamination operation and the unprotected environment. Care should be taken to examine the surface area prior to placing the liner to remove sharp articles (sticks, stones, debris) that could puncture the liner. Liners are intended to form an impermeable barrier. The thickness may vary from a minimum recommended thickness of 10 mil to 30 mil. Achieving the desired thickness maybe achieved through layering lighter constructed materials. It should be noted that various materials (rubber, polyethylene sheeting) become slippery when wet. To minimize this potential hazard associated with a sloped liner a light coating of sand maybe applied to provide traction as necessary.
 - Wash/drying Racks – Auger flights, drill/drive rods require racks positioned off of the ground to permit these articles to be washed, drained, and dried while secured from falling during this process. A minimum ground clearance of 2-feet is recommended.
 - Maintenance – The work area should be periodically cleared of standing water, soils, and debris. This action will aid in eliminating slip, trip, and fall hazards. In addition, these articles will reduce potential backsplash and cross contamination. Hoses should be gathered when not in use to eliminate potential tripping hazards.

5.1.2 Decontamination Activities at Drill Rigs/DPT Units

During subsurface sampling activities including drilling and direct push activities decontamination of drive rods, Macro Core Samplers, split spoons, etc. are typically conducted at an area adjacent to the operation. Decontamination is generally accomplished using a soap/water wash and rinse utilizing buckets and brushes. This area requires sufficient preparation to accomplish the decontamination objectives.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	5 of 8
		Revision	3	Effective Date	09/03

Buckets shall be placed within mortar tubs or similar secondary containment tubs to prevent splash and spills from reaching unprotected media. Drying racks will be employed as directed for temporary pads to permit parts to dry and be evaluated prior to use/re-use.

5.1.3 Decontamination Activities at Remote Sample Locations

When sampling at remote locations sampling devices such as trowels, pumps/tubing should be evacuated of potentially contaminated media to the extent possible. This equipment should be wrapped in plastic for transport to the temporary/centralized decontamination location for final cleaning and disposition.

5.2 Equipment Decontamination Procedures

The following represents procedures to be employed for the decontamination of equipment that may have contacted and/or accumulated contamination through site investigation activities.

5.2.1 Monitoring Well Sampling Equipment

5.2.1.1 Groundwater sampling pumps – This includes pumps inserted into the monitoring well such as Bladder pumps, Whale pumps, Redi-Flo, reusable bailers, etc.

- 1) Evacuate to the extent possible, any purge water within the pump.
- 2) Scrub using soap and water and/or steam clean the outside of the pump and tubing, where applicable.
- 3) Insert the pump and tubing into a clean container of soapy water. Pump a sufficient amount of soapy water through the pump to flush any residual purge water. Once flushed, circulate soapy water through the pump to ensure the internal components are thoroughly flushed.
- 4) Remove the pump and tubing from the container, rinse external components using tap water. Insert the pump and tubing into a clean container of tap water. Pump a sufficient amount of tap water through the pump to evacuate all of the soapy water (until clear).
- 5) Rinse equipment with pesticide grade isopropanol
- 6) Repeat item #4 using deionized water through the hose to flush out the tap water and solvent residue as applicable
- 7) Drain residual deionized water to the extent possible, allow components to air dry.
- 8) Wrap pump in aluminum foil or a clear clean plastic bag for storage.

5.2.1.2 Electronic Water Level Indicators/Sounders/Tapes

During water level measurements, rinsing with the extracted tape and probe with deionized water and wiping the surface of the extracted tape is acceptable. However, periodic full decontamination should be conducted as indicated below.

* - The solvent should be employed when samples contain oil, grease, PAHs, PCBs, and other hard to remove materials. If these are not of primary concern, the solvent step may be omitted. In addition, do not rinse PE, PVC, and associated tubing with solvents.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	6 of 8
		Revision	3	Effective Date	09/03

- 1) Wash with soap and water
- 2) Rinse with tap water
- 3) Rinse with deionized water

Note: In situations where oil, grease, free product, other hard to remove materials are encountered probes and exposed tapes should be washed in hot soapy water.

5.2.1.3 Miscellaneous Equipment

Miscellaneous equipment including analytical equipment (water quality testing equipment) should be cleaned per manufacturer's instructions. This generally includes wiping down the sensor housing and rinsing with tap and deionized water.

Coolers/Shipping Containers employed to ship samples are received from the lab in a variety of conditions from marginal to extremely poor. Coolers should be evaluated prior to use for

- Structural integrity – Coolers missing handles or having breaks within the outer housing should be removed and not used. Notify the laboratory that the risk of shipping samples will not be attempted and request a replacement unit.
- Cleanliness – As per protocol only volatile organic samples are accompanied by a trip blank. If a cooler's cleanliness is in question (visibly dirty/stained) or associated with noticeable odors it should be decontaminated prior to use.

- 1) Wash with soap and water
- 2) Rinse with tap water
- 3) Dry

If these measures fail to clean the cooler to an acceptable level, remove the unit from use as a shipping container and notify the laboratory to provide a replacement unit.

5.2.2 **Down-Hole Drilling Equipment**

This includes any portion of the drill rig that is over the borehole including auger flights, drill stems, rods, and associated tooling that would extend over the borehole. This procedure is to be employed prior to initiating the drilling/sampling activity, then between locations.

- 1) Remove all soils to the extent possible using shovels, scrapers, etc. to remove loose soils.
- 2) Through a combination of scrubbing using soap and water and/or steam cleaning remove visible dirt/soils.
- 3) Rinse with tap water.
- 4) Rinse equipment with pesticide grade isopropanol
- 5) To the extent possible allow components to air dry.
- 6) Wrap or cover equipment in clear plastic until it is time to be used.

5.2.3 **Soil/Sediment Sampling Equipment**

This consists of soil sampling equipment including but not limited to hand augers, stainless steel trowels/spoons, bowls, dredges, scoops, split spoons, Macro Core samplers, etc.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	7 of 8
		Revision	3	Effective Date	09/03

- 1) Remove all soils to the extent possible.
- 2) Through a combination of scrubbing using soap and water and/or steam cleaning remove visible dirt/soils.
- 3) Rinse with tap water.
- 4) Rinse equipment with pesticide grade isopropanol
- 5) Rinse with deionized water
- 6) To the extent possible allow components to air dry.
- 7) If the device is to be used immediately, screen with a PID/FID to insure all solvents (if they were used) and trace contaminants have been adequately removed.
- 8) Once these devices have been dried wrap in aluminum foil for storage until it is time to be used.

5.3 Contact Waste/Materials

During the course of field investigations disposable/single use equipment becomes contaminated. These items include tubing, trowels, PPE (gloves, overboots, splash suits, etc.) broken sample containers.

With the exception of the broken glass, single use articles should be cleaned (washed and rinsed) of visible materials and disposed of as normal refuse. The exception to this rule is that extremely soiled materials that cannot be cleaned should be containerized for disposal in accordance with applicable federal state and local regulations.

5.3.1 Decontamination Solutions

All waste decontamination solutions and rinses must be assumed to contain the hazardous chemicals associated with the site unless there are analytical or other data to the contrary. The waste solution volumes could vary from a few gallons to several hundred gallons in cases where large equipment required cleaning.

Containerized waste rinse solutions are best stored in 55-gallon drums (or equivalent containers) that can be sealed until ultimate disposal at an approved facility. These containers must be appropriately labeled.

5.4 Decontamination Evaluation

Determining the effectiveness of the decontamination process will be accomplished in the following manner

- Visual Evaluation – A visual evaluation will be conducted to insure the removal of particulate matter. This will be done to insure that the washing/rinsing process is working as intended.
- Instrument Screening – A PID and/or an FID should be used to evaluate the presence of the contaminants or solvents used in the cleaning process. The air intake of the instrument should be passed over the article to be evaluated. A positive detection requires a repeat the decontamination process. It should be noted that the instrument scan is only viable if the contaminants are detectable within the instruments capabilities.

Subject	DECONTAMINATION OF FIELD EQUIPMENT	Number	SA-7.1	Page	8 of 8
		Revision	3	Effective Date	09/03


- Rinsate Blanks – It is recommended that Rinsate samples be collected to
 - Evaluate the decontamination procedure representing different equipment applications (pumps versus drilling equipment) and different decontamination applications.
 - Single use disposable equipment – The number of samples should represent different types of equipment as well as different Lot Numbers of single use articles.

The collection and the frequency of collection of rinsate samples are as follows:

- Per decontamination method
- Per disposable article/Batch number of disposable articles

It is recommended that an initial rinsate sample be collected early in the project to ensure that the decontamination process is functioning properly and in an effort to avoid using a contaminated batch of single use articles. It is recommended that a follow up sample be collected during the execution of the project to insure those conditions do not change. Lastly, rinsate samples collection may be driven by types of and/or contaminant levels. Hard to remove contaminants, oils/greases, some PAHs/PCBs, etc. may also support the collection of additional rinsates due to the obvious challenges to the decontamination process. This is a field consideration to be determined by the FOL.

TtNUS SOP SA-6.1 – Non-Radiological Sample Handling



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number

SA-6.1

Page

1 of 11

Effective Date

02/04

Revision

3

Applicability

Tetra Tech NUS, Inc.

Prepared

Earth Sciences Department

Subject

NON-RADIOLOGICAL SAMPLE HANDLING

Approved

D. Senovich

TABLE OF CONTENTS

SECTION

PAGE

1.0	PURPOSE.....	2
2.0	SCOPE.....	2
3.0	GLOSSARY.....	2
4.0	RESPONSIBILITIES.....	3
5.0	PROCEDURES.....	3
5.1	SAMPLE CONTAINERS.....	3
5.2	SAMPLE PRESERVATION.....	3
5.2.1	Overview.....	4
5.2.2	Preparation and Addition of Reagents.....	4
5.3	FIELD FILTRATION.....	5
5.4	SAMPLE PACKAGING AND SHIPPING.....	6
5.4.1	Environmental Samples.....	6
6.0	REFERENCES.....	7

ATTACHMENTS

A	GENERAL SAMPLE CONTAINER AND PRESERVATION REQUIREMENTS.....	8
B	ADDITIONAL REQUIRED CONTAINERS, PRESERVATION TECHNIQUES, AND HOLDING TIMES.....	9

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 2 of 11
	Revision 3	Effective Date 02/04

1.0 PURPOSE

The purpose of this Standard Operating Procedure (SOP) is to provide information on sample preservation, packaging, and shipping procedures to be used in handling environmental samples submitted for chemical constituent, biological, or geotechnical analysis. Sample chain-of-custody procedures and other aspects of field documentation are addressed in SOP SA-6.3. Sample identification is addressed in SOP CT-04.

2.0 SCOPE

This procedure describes the appropriate containers to be used for samples depending on the analyses to be performed, and the steps necessary to preserve the samples when shipped off site for chemical analysis.

3.0 GLOSSARY

Hazardous Material - A substance or material which has been determined by the Secretary of Transportation to be capable of posing an unreasonable risk to health, safety, and property when transported in commerce, and which has been so designated. Under 49 CFR, the term includes hazardous substances, hazardous wastes, marine pollutants, and elevated temperature materials, as well as materials designated as hazardous under the provisions of §172.101 and §172.102 and materials that meet the defining criteria for hazard classes and divisions in Part 173. With slight modifications, IATA has adopted DOT "hazardous materials" as IATA "Dangerous Goods."

Hazardous Waste - Any substance listed in 40 CFR, Subpart D (y261.30 et seq.), or otherwise characterized as ignitable, corrosive, reactive, or toxic (as defined by Toxicity Characteristic Leaching Procedure, TCLP, analysis) as specified under 40 CFR, Subpart C (y261.20 et seq.), that would be subject to manifest requirements specified in 40 CFR 262. Such substances are defined and regulated by EPA.

Marking - A descriptive name, identification number, instructions, cautions, weight, specification or UN marks, or combination thereof required on outer packaging of hazardous materials.

n.o.i - Not otherwise indicated (may be used interchangeably with n.o.s.).

n.o.s. - Not otherwise specified.

Packaging - A receptacle and any other components or materials necessary for compliance with the minimum packaging requirements of 49 CFR 174, including containers (other than freight containers or overpacks), portable tanks, cargo tanks, tank cars, and multi-unit tank-car tanks to perform a containment function in conformance with the minimum packaging requirements of 49 CFR 173.24(a) & (b).

Placard - Color-coded, pictorial sign which depicts the hazard class symbol and name and which is placed on the side of a vehicle transporting certain hazardous materials.

Common Preservatives:

- Hydrochloric Acid - HCl
- Sulfuric Acid - H₂SO₄
- Nitric Acid - HNO₃
- Sodium Hydroxide - NaOH

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 3 of 11
	Revision 3	Effective Date 02/04

Other Preservatives

- Zinc Acetate
- Sodium Thiosulfate - $\text{Na}_2\text{S}_2\text{O}_3$

Normality (N) - Concentration of a solution expressed as equivalent per liter, an equivalent being the amount of a substance containing 1 gram-atom of replaceable hydrogen or its equivalent.

Reportable Quantity (RQ) - For the purposes of this SOP, means the quantity specified in column 3 of the Appendix to DOT 49 CFR §172.101 for any material identified in column 1 of the appendix. A spill greater than the amount specified must be reported to the National Response Center.

Sample - A sample is physical evidence collected from a facility or the environment, which is representative of conditions at the location and time of collection.

4.0 RESPONSIBILITIES

Field Operations Leader - Directly responsible for the bottling, preservation, labeling, packaging, shipping, and custody of samples up to and including release to the shipper.

Field Samplers - Responsible for initiating the Chain-of-Custody Record (per SOP SA-6.3), implementing the packaging and shipping requirements, and maintaining custody of samples until they are relinquished to another custodian or to the shipper.

5.0 PROCEDURES

Sample identification, labeling, documentation, and chain-of-custody are addressed by SOP SA-6.3.

5.1 Sample Containers

Different types of chemicals react differently with sample containers made of various materials. For example, trace metals adsorb more strongly to glass than to plastic, whereas many organic chemicals may dissolve various types of plastic containers. Attachments A and B show proper containers (as well as other information) per 40 CFR 136. In general, the sample container shall allow approximately 5-10 percent air space ("ullage") to allow for expansion/vaporization if the sample warms during transport. However, for collection of volatile organic compounds, head space shall be omitted. The analytical laboratory will generally provide certified-clean containers for samples to be analyzed for chemical constituents. Shelby tubes or other sample containers are generally provided by the driller for samples requiring geotechnical analysis. Sufficient lead time shall be allowed for a delivery of sample container orders. Therefore, it is critical to use the correct container to maintain the integrity of the sample prior to analysis.

Once opened, the container must be used at once for storage of a particular sample. Unused but opened containers are to be considered contaminated and must be discarded. Because of the potential for introduction of contamination, they cannot be reclosed and saved for later use. Likewise, any unused containers which appear contaminated upon receipt, or which are found to have loose caps or a missing Teflon liner (if required for the container), shall be discarded.

5.2 Sample Preservation

Many water and soil samples are unstable and therefore require preservation to prevent changes in either the concentration or the physical condition of the constituent(s) requiring analysis. Although complete and irreversible preservation of samples is not possible, preservation does retard the chemical and biological

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 4 of 11
	Revision 3	Effective Date 02/04

changes that inevitably take place after the sample is collected. Preservation techniques are usually limited to pH control, chemical addition(s), and refrigeration/ freezing (certain biological samples only).

5.2.1 Overview

The preservation techniques to be used for various analytes are listed in Attachments A and B. Reagents required for sample preservation will either be added to the sample containers by the laboratory prior to their shipment to the field or be added in the field (in a clean environment). Only high purity reagents shall be used for preservation. In general, aqueous samples of low-concentration organics (or soil samples of low- or medium-concentration organics) are cooled to 4°C. Medium-concentration aqueous samples, high-hazard organic samples, and some gas samples are typically not preserved. Low-concentration aqueous samples for metals are acidified with HNO₃, whereas medium-concentration and high-hazard aqueous metal samples are not preserved. Low- or medium-concentration soil samples for metals are cooled to 4°C, whereas high-hazard samples are not cooled.

The following subsections describe the procedures for preparing and adding chemical preservatives. Attachments A and B indicate the specific analytes which require these preservatives.

The FOL is responsible for ensuring that an accurate Chemical Inventory is created and maintained for all hazardous chemicals brought to the work site (see Section 5 of the TINUS Health and Safety Guidance Manual). Furthermore, the FOL must ensure that a corresponding Material Safety Data Sheet (MSDS) is collected for every substance entered on the site Chemical Inventory, and that all persons using/handling/ disposing of these substances review the appropriate MSDS for substances they will work with. The Chemical Inventory and the MSDSs must be maintained at each work site in a location and manner where they are readily-accessible to all personnel.

5.2.2 Preparation and Addition of Reagents

Addition of the following acids or bases may be specified for sample preservation; these reagents shall be analytical reagent (AR) grade or purer and shall be diluted to the required concentration with deionized water before field sampling commences. To avoid uncontrolled reactions, be sure to Add Acid to water (not vice versa). A dilutions guide is provided below.

Acid/Base	Dilution	Concentration	Estimated Amount Required for Preservation
Hydrochloric Acid (HCl)	1 part concentrated HCl: 1 part double-distilled, deionized water	6N	5-10 mL
Sulfuric Acid (H ₂ SO ₄)	1 part concentrated H ₂ SO ₄ : 1 part double-distilled, deionized water	18N	2 - 5 mL
Nitric Acid (HNO ₃)	Undiluted concentrated HNO ₃	16N	2 - 5 mL
Sodium Hydroxide (NaOH)	400 grams solid NaOH dissolved in 870 mL double-distilled, deionized water; yields 1 liter of solution	10N	2 mL

The amounts required for preservation shown in the above table assumes proper preparation of the preservative and addition of the preservative to one liter of aqueous sample. This assumes that the sample is initially at pH 7, is poorly buffered, and does not contain particulate matter; as these conditions vary, more preservative may be required. Consequently, the final sample pH must be checked using narrow-range pH paper, as described in the generalized procedure detailed below:

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 5 of 11
	Revision 3	Effective Date 02/04

- Pour off 5-10 mL of sample into a dedicated, clean container. Use some of this sample to check the initial sample pH using wide range (0-14) pH paper. Never dip the pH paper into the sample; always apply a drop of sample to the pH paper using a clean stirring rod or pipette.
- Add about one-half of the estimated preservative required to the original sample bottle. Cap and invert gently several times to mix. Check pH (as described above) using medium range pH paper (pH 0-6 or pH 7.5-14, as applicable).
- Cap sample bottle and seal securely.

Additional considerations are discussed below:

- To test if ascorbic acid must be used to remove oxidizing agents present in the sample before it can be properly preserved, place a drop of sample on KI-starch paper. A blue color indicates the need for ascorbic acid addition.

If required, add a few crystals of ascorbic acid to the sample and retest with the KI-starch paper. Repeat until a drop of sample produces no color on the KI-starch paper. Then add an additional 0.6 grams of ascorbic acid per each liter of sample volume.

Continue with proper base preservation of the sample as described above.

- Samples for sulfide analysis must be treated by the addition of 4 drops (0.2 mL) of 2N zinc acetate solution per 100 ml of sample.

The 2N zinc acetate solution is made by dissolving 220 grams of zinc acetate in 870 mL of double-distilled, deionized water to make 1 liter of solution.

The sample pH is then raised to 9 using the NaOH preservative.

- Sodium thiosulfate must be added to remove residual chlorine from a sample. To test the sample for residual chlorine use a field test kit specially made for this purpose.

If residual chlorine is present, add 0.08 grams of sodium thiosulfate per liter of sample to remove the residual chlorine.

Continue with proper acidification of the sample as described above.

For biological samples, 10% buffered formalin or isopropanol may also be required for preservation. Questions regarding preservation requirements should be resolved through communication with the laboratory before sampling begins.

5.3 Field Filtration

At times, field-filtration may be required to provide for the analysis of dissolved chemical constituents. Field-filtration must be performed prior to the preservation of samples as described above. General procedures for field filtration are described below:

- The sample shall be filtered through a non-metallic, 0.45-micron membrane filter, immediately after collection. The filtration system shall consist of dedicated filter canister, dedicated tubing, and a peristaltic pump with pressure or vacuum pumping squeeze action (since the sample is filtered by mechanical peristalsis, the sample travels only through the tubing).

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 6 of 11
	Revision 3	Effective Date 02/04

- To perform filtration, thread the tubing through the peristaltic pump head. Attach the filter canister to the discharge end of the silicon tubing (note flow direction arrow); attach the aqueous sample container to the intake end of the silicon tubing. Turn the peristaltic pump on and perform filtration. Run approximately 100 ml of sample through the filter and discard prior to sample collection.
- Continue by preserving the filtrate (contained in the filter canister), as applicable and generally described above.

5.4 Sample Packaging and Shipping

Only employees who have successfully completed the TiNUS "Shipping Hazardous Materials" training course are authorized to package and ship hazardous substances. These trained individuals are responsible for performing shipping duties in accordance with this training.

Samples collected for shipment from a site shall be classified as either environmental or hazardous material samples. Samples from drums containing materials other than Investigative Derived Waste (IDW) and samples obtained from waste piles or bulk storage tanks are generally shipped as hazardous materials. A distinction must be made between the two types of samples in order to:

- Determine appropriate procedures for transportation of samples (if there is any doubt, a sample shall be considered hazardous and shipped accordingly.)
- Protect the health and safety of transport and laboratory personnel receiving the samples (special precautions are used by the shipper and at laboratories when hazardous materials are received.)

Detailed procedures for packaging environmental samples are outlined in the remainder of this section.

5.4.1 Environmental Samples

Environmental samples are packaged as follows:

- Place properly identified sample container, with lid securely fastened, in a plastic bag (e.g. Ziploc baggie), and seal the bag.
- Place sample in a cooler constructed of sturdy material which has been lined with a large, plastic bag (e.g. "garbage" bag). Drain plugs on coolers must be taped shut.
- Pack with enough cushioning materials such as bubble wrap (shoulders of bottles must be iced if required) to minimize the possibility of the container breaking.
- If cooling is required (see Attachments A and B), place ice around sample container shoulders, and on top of packing material (minimum of 8 pounds of ice for a medium-size cooler).
- Seal (i.e., tape or tie top in knot) large liner bag.
- The original (top, signed copy) of the COC form shall be placed inside a large Ziploc-type bag and taped inside the lid of the shipping cooler. If multiple coolers are sent but are included on one COC form, the COC form should be sent with the cooler containing the vials for VOC analysis. The COC form should then state how many coolers are included with that shipment.
- Close and seal outside of cooler as described in SOP SA-6.3. Signed custody seals must be used.

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 7 of 11
	Revision 3	Effective Date 02/04

Coolers must be marked as containing "Environmental Samples." The appropriate side of the container must be marked "This End Up" and arrows placed appropriately. No DOT marking or labeling is required; there are no DOT restrictions on mode of transportation.

6.0 REFERENCES

American Public Health Association, 1981. Standard Methods for the Examination of Water and Wastewater, 15th Edition. APHA, Washington, D.C.

International Air Transport Association (latest issue). Dangerous Goods Regulations, Montreal, Quebec, Canada.

U.S. Department of Transportation (latest issue). Hazardous Materials Regulations, 49 CFR 171-177.

U.S. EPA, 1984. "Guidelines Establishing Test Procedures for the Analysis of Pollutants under Clean Water Act." Federal Register, Volume 49 (209), October 26, 1984, p. 43234.

U.S. EPA, 1979. Methods for Chemical Analysis of Water and Wastes. EPA-600/4-79-020, U.S. EPA-EMSL, Cincinnati, Ohio.

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 8 of 11
	Revision 3	Effective Date 02/04

ATTACHMENT A

GENERAL SAMPLE CONTAINER AND PRESERVATION REQUIREMENTS

Sample Type and Concentration	Container ⁽¹⁾	Sample Size	Preservation ⁽²⁾	Holding Time ⁽²⁾
-------------------------------	--------------------------	-------------	-----------------------------	-----------------------------

WATER

Organics (GC&GC/MS)	VOC	Low	Borosilicate glass	2 x 40 mL	Cool to 4°C HCl to ≤ 2	14 days ⁽²⁾
	Extractables SVOCs and pesticide/PCBs)	(Low)	Amber glass	2x2 L or 4x1 L	Cool to 4°C	7 days to extraction; 40 days after extraction
	Extractables SVOCs and pesticide/PCBs)	(Medium)	Amber glass	2x2 L or 4x1 L	None	7 days to extraction; 40 days after extraction
Inorganics	Metals	Low	High-density polyethylene	1 L	HNO ₃ to pH ≤ 2	6 months (Hg-28 days)
		Medium	Wide-mouth glass	16 oz.	None	6 months
	Cyanide	Low	High-density polyethylene	1 L	NaOH to pH > 12	14 days
	Cyanide	Medium	Wide-mouth glass	16 oz.	None	14 days
Organic/ Inorganic	High Hazard		Wide-mouth glass	8 oz.	None	14 days

SOIL

Organics (GC&GC/MS)	VOC		EnCore Sampler	(3) 5 g Samplers	Cool to 4°C	48 hours to lab preservation
	Extractables SVOCs and pesticides/PCBs)	(Low)	Wide-mouth glass	8 oz.	Cool to 4°C	14 days to extraction; 40 days after extraction
	Extractables SVOCs and pesticides/PCBs)	(Medium)	Wide-mouth glass	8 oz.	Cool to 4°C	14 days to extraction; 40 days after extraction
Inorganics	Low/Medium		Wide-mouth glass	8 oz.	Cool to 4°C	6 months (Hg - 28 days) Cyanide (14 days)
Organic/inorga nic	High Hazard		Wide-mouth glass	8 oz.	None	NA
Dioxin/Furan	All		Wide-mouth glass	4 oz.	None	35 days until extraction; 40 days after extraction
TCLP	All		Wide-mouth glass	8 oz.	None	7 days until preparation; analysis as per fraction

AIR

Volatile Organics	Low/Medium	Charcoal tube -- 7 cm long, 6 mm OD, 4 mm ID	100 L air	Cool to 4°C	5 days recommended
----------------------	------------	---	-----------	-------------	--------------------

1 All glass containers should have Teflon cap liners or septa.

2 See Attachment E. Preservation and maximum holding time allowances per 40 CFR 136.

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 9 of 11
	Revision 3	Effective Date 02/04

ATTACHMENT B

ADDITIONAL REQUIRED CONTAINERS, PRESERVATION TECHNIQUES, AND HOLDING TIMES

Parameter Number/Name	Container ⁽¹⁾	Preservation ⁽²⁾⁽³⁾	Maximum Holding Time ⁽⁴⁾
INORGANIC TESTS:			
Acidity	P, G	Cool, 4°C	14 days
Alkalinity	P, G	Cool, 4°C	14 days
Ammonia - Nitrogen	P, G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Biochemical Oxygen Demand (BOD)	P, G	Cool, 4°C	48 hours
Bromide	P, G	None required	28 days
Chemical Oxygen Demand (COD)	P, G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Chloride	P, G	None required	28 days
Chlorine, Total Residual	P, G	None required	Analyze immediately
Color	P, G	Cool, 4°C	48 hours
Cyanide, Total and Amenable to Chlorination	P, G	Cool, 4°C; NaOH to pH 12; 0.6 g ascorbic acid ⁽⁵⁾	14 days ⁽⁶⁾
Fluoride	P	None required	28 days
Hardness	P, G	HNO ₃ to pH 2; H ₂ SO ₄ to pH 2	6 months
Total Kjeldahl and Organic Nitrogen	P, G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Nitrate - Nitrogen	P, G	None required	48 hours
Nitrate-Nitrite - Nitrogen	P, G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Nitrite - Nitrogen	P, G	Cool, 4°C	48 hours
Oil & Grease	G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Total Organic Carbon (TOC)	P, G	Cool, 4°C; HCl or H ₂ SO ₄ to pH 2	28 days
Orthophosphate	P, G	Filter immediately; Cool, 4°C	48 hours
Oxygen, Dissolved-Probe	G Bottle & top	None required	Analyze immediately
Oxygen, Dissolved-Winkler	G Bottle & top	Fix on site and store in dark	8 hours
Phenols	G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Phosphorus, Total	P, G	Cool, 4°C; H ₂ SO ₄ to pH 2	28 days
Residue, Total	P, G	Cool, 4°C	7 days
Residue, Filterable (TDS)	P, G	Cool, 4°C	7 days
Residue, Nonfilterable (TSS)	P, G	Cool, 4°C	7 days
Residue, Settleable	P, G	Cool, 4°C	48 hours
Residue, Volatile (Ash Content)	P, G	Cool, 4°C	7 days
Silica	P	Cool, 4°C	28 days
Specific Conductance	P, G	Cool, 4°C	28 days
Sulfate	P, G	Cool, 4°C	28 days

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 10 of 11
	Revision 3	Effective Date 02/04

**ATTACHMENT B
ADDITIONAL REQUIRED CONTAINERS, PRESERVATION TECHNIQUES,
AND HOLDING TIMES
PAGE TWO**

Parameter Number/Name	Container ⁽¹⁾	Preservation ⁽²⁾⁽³⁾	Maximum Holding Time ⁽⁴⁾
-----------------------	--------------------------	--------------------------------	-------------------------------------

INORGANIC TESTS (Cont'd):

Sulfide	P, G	Cool, 4°C; add zinc acetate plus sodium hydroxide to pH 9	7 days
Sulfite	P, G	None required	Analyze immediately
Turbidity	P, G	Cool, 4°C	48 hours

METALS:⁽⁷⁾

Chromium VI (Hexachrome)	P, G	Cool, 4°C	24 hours
Mercury (Hg)	P, G	HNO ₃ to pH 2	28 days
Metals, except Chromium VI and Mercury	P, G	HNO ₃ to pH 2	6 months

ORGANIC TESTS:⁽⁸⁾


Purgeable Halocarbons	G, Teflon-lined septum	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	14 days
Purgeable Aromatic Hydrocarbons	G, Teflon-lined septum	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾ HCl to pH 2 ⁽⁹⁾	14 days
Acrolein and Acrylonitrile	G, Teflon-lined septum	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾ adjust pH to 4-5 ⁽¹⁰⁾	14 days
Phenols ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	7 days until extraction; 40 days after extraction
Benzidines ^{(11),(12)}	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	7 days until extraction ⁽¹³⁾
Phthalate esters ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C	7 days until extraction; 40 days after extraction
Nitrosamines ^{(11),(14)}	G, Teflon-lined cap	Cool, 4°C; store in dark; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	7 days until extraction; 40 days after extraction
PCBs ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C	7 days until extraction; 40 days after extraction
Nitroaromatics & Isophorone ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾ ; store in dark	7 days until extraction; 40 days after extraction
Polynuclear Aromatic Hydrocarbons (PAHs) ^{(11),(14)}	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾ ; store in dark	7 days until extraction; 40 days after extraction
Halocethers ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	7 days until extraction; 40 days after extraction
Dioxin/Furan (TCDD/TCDF) ⁽¹¹⁾	G, Teflon-lined cap	Cool, 4°C; 0.008% Na ₂ S ₂ O ₃ ⁽⁵⁾	7 days until extraction; 40 days after extraction

Subject NON-RADIOLOGICAL SAMPLE HANDLING	Number SA-6.1	Page 11 of 11
	Revision 3	Effective Date 02/04

**ATTACHMENT B
ADDITIONAL REQUIRED CONTAINERS, PRESERVATION TECHNIQUES,
AND HOLDING TIMES
PAGE THREE**

- (1) Polyethylene (P): generally 500 ml or Glass (G): generally 1L.
- (2) Sample preservation should be performed immediately upon sample collection. For composite chemical samples each aliquot should be preserved at the time of collection. When use of an automated sampler makes it impossible to preserve each aliquot, then chemical samples may be preserved by maintaining at 4°C until compositing and sample splitting is completed.
- (3) When any sample is to be shipped by common carrier or sent through the United States Mail, it must comply with the Department of Transportation Hazardous Materials Regulations (49 CFR Part 172).
- (4) Samples should be analyzed as soon as possible after collection. The times listed are the maximum times that samples may be held before analysis and still be considered valid. Samples may be held for longer periods only if the permittee, or monitoring laboratory, has data on file to show that the specific types of samples under study are stable for the longer periods, and has received a variance from the Regional Administrator.
- (5) Should only be used in the presence of residual chlorine.
- (6) Maximum holding time is 24 hours when sulfide is present. Optionally, all samples may be tested with lead acetate paper before pH adjustments are made to determine if sulfide is present. If sulfide is present, it can be removed by the addition of cadmium nitrate powder until a negative spot test is obtained. The sample is filtered and then NaOH is added to pH 12.
- (7) Samples should be filtered immediately on site before adding preservative for dissolved metals.
- (8) Guidance applies to samples to be analyzed by GC, LC, or GC/MS for specific compounds.
- (9) Sample receiving no pH adjustment must be analyzed within 7 days of sampling.
- (10) The pH adjustment is not required if acrolein will not be measured. Samples for acrolein receiving no pH adjustment must be analyzed within 3 days of sampling.
- (11) When the extractable analytes of concern fall within a single chemical category, the specified preservative and maximum holding times should be observed for optimum safeguard of sample integrity. When the analytes of concern fall within two or more chemical categories, the sample may be preserved by cooling to 4°C, reducing residual chlorine with 0.008% sodium thiosulfate, storing in the dark, and adjusting the pH to 6-9; samples preserved in this manner may be held for 7 days before extraction and for 40 days after extraction. Exceptions to this optional preservation and holding time procedure are noted in footnote 5 (re: the requirement for thiosulfate reduction of residual chlorine) and footnotes 12, 13 (re: the analysis of benzidine).
- (12) If 1,2-diphenylhydrazine is likely to be present, adjust the pH of the sample to 4.0±0.2 to prevent rearrangement to benzidine.
- (13) Extracts may be stored up to 7 days before analysis if storage is conducted under an inert (oxidant-free) atmosphere.
- (14) For the analysis of diphenylnitrosamine, add 0.008% Na₂S₂O₃ and adjust pH to 7-10 with NaOH within 24 hours of sampling.
- (15) The pH adjustment may be performed upon receipt at the laboratory and may be omitted if the samples are extracted within 72 hours of collection. For the analysis of aldrin, add 0.008% Na₂S₂O₃.

TtNUS SOP SA-6.3 – Field Documentation



TETRA TECH NUS, INC.

STANDARD OPERATING PROCEDURES

Number	SA-6.3	Page	1 of 12
Effective Date	09/03	Revision	2
Applicability	Tetra Tech NUS, Inc.		
Prepared	Earth Sciences Department		
Approved	D. Senovich <i>DS</i>		

Subject
FIELD DOCUMENTATION

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 PURPOSE.....	2
2.0 SCOPE.....	2
3.0 GLOSSARY.....	2
4.0 RESPONSIBILITIES.....	2
5.0 PROCEDURES.....	2
5.1 SITE LOGBOOK.....	2
5.1.1 General.....	2
5.1.2 Photographs.....	3
5.2 FIELD NOTEBOOKS.....	3
5.3 FIELD FORMS.....	4
5.3.1 Sample Collection, Labeling, Shipment, Request for Analysis, and Field Test Results..	4
5.3.2 Hydrogeological and Geotechnical Forms.....	5
5.3.3 Equipment Calibration and Maintenance Form.....	6
5.4 FIELD REPORTS.....	6
5.4.1 Daily Activities Report.....	6
5.4.2 Weekly Status Reports.....	7
6.0 LISTING OF TETRA TECH NUS FIELD FORMS FOUND ON THE TTNUS INTRANET SITE. HTTP://INTRANET.TTNUS.COM CLICK ON FIELD LOG SHEETS.....	7

ATTACHMENTS

A	TYPICAL SITE LOGBOOK ENTRY.....	9
B	SAMPLE LABEL.....	10
C	CHAIN-OF-CUSTODY RECORD FORM.....	11
D	CHAIN-OF-CUSTODY SEAL.....	12

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 3 of 12
	Revision 2	Effective Date 09/03

that onsite activities take place which involve Tetra Tech NUS or subcontractor personnel. Upon completion of the fieldwork, the site logbook must become part of the project's central file.

The following information must be recorded on the cover of each site logbook:

- Project name
- Tetra Tech NUS project number
- Sequential book number
- Start date
- End date

Information recorded daily in the site logbook need not be duplicated in other field notebooks (see Section 5.2), but must summarize the contents of these other notebooks and refer to specific page locations in these notebooks for detailed information (where applicable). An example of a typical site logbook entry is shown in Attachment A.

If measurements are made at any location, the measurements and equipment used must either be recorded in the site logbook or reference must be made to the field notebook in which the measurements are recorded (see Attachment A).

All logbook, notebook, and log sheet entries shall be made in indelible ink (black pen is preferred). No erasures are permitted. If an incorrect entry is made, the entry shall be crossed out with a single strike mark, and initialed and dated. At the completion of entries by any individual, the logbook pages used must be signed and dated. The site logbook must also be signed by the Field Operations Leader at the end of each day.

5.1.2 Photographs

When movies, slides, or photographs are taken of a site or any monitoring location, they must be numbered sequentially to correspond to logbook/notebook entries. The name of the photographer, date, time, site location, site description, and weather conditions must be entered in the logbook/notebook as the photographs are taken. A series entry may be used for rapid-sequence photographs. The photographer is not required to record the aperture settings and shutter speeds for photographs taken within the normal automatic exposure range. However, special lenses, films, filters, and other image-enhancement techniques must be noted in the logbook/notebook. If possible, such techniques shall be avoided, since they can adversely affect the accuracy of photographs. Chain-of-custody procedures depend upon the subject matter, type of camera (digital or film), and the processing it requires. Film used for aerial photography, confidential information, or criminal investigation require chain-of-custody procedures. Once processed, the slides or photographic prints shall be consecutively numbered and labeled according to the logbook/notebook descriptions. The site photographs and associated negatives and/or digitally saved images to compact disks must be docketed into the project's central file.

5.2 Field Notebooks

Key field team personnel may maintain a separate dedicated field notebook to document the pertinent field activities conducted directly under their supervision. For example, on large projects with multiple investigative sites and varying operating conditions, the Health and Safety Officer may elect to maintain a separate field notebook. Where several drill rigs are in operation simultaneously, each site geologist assigned to oversee a rig must maintain a field notebook.

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 4 of 12
	Revision 2	Effective Date 09/03

5.3 Field Forms

All Tetra Tech NUS field forms (see list in Section 6.0 of this SOP) can be found on the company's intranet site (<http://intranet.ttnus.com>) under Field Log Sheets. Forms may be altered or revised for project-specific needs contingent upon client approval. Care must be taken to ensure that all essential information can be documented. Guidelines for completing these forms can be found in the related sampling SOP.

5.3.1 **Sample Collection, Labeling, Shipment, Request for Analysis, and Field Test Results**

5.3.1.1 Sample Log Sheet

Sample Log Sheets are used to record specified types of data while sampling. The data recorded on these sheets are useful in describing the sample as well as pointing out any problems, difficulties, or irregularities encountered during sampling. A log sheet must be completed for each sample obtained, including field quality control (QC) samples.

5.3.1.2 Sample Label

A typical sample label is illustrated in Attachment B. Adhesive labels must be completed and applied to every sample container. Sample labels can usually be obtained from the appropriate Program source electronically generated in-house, or are supplied from the laboratory subcontractor.

5.3.1.3 Chain-of-Custody Record Form

The Chain-of-Custody (COC) Record is a multi-part form that is initiated as samples are acquired and accompanies a sample (or group of samples) as they are transferred from person to person. This form must be used for any samples collected for chemical or geotechnical analysis whether the analyses are performed on site or off site. One carbonless copy of the completed COC form is retained by the field crew, one copy is sent to the Project Manager (or designee), while the original is sent to the laboratory. The original (top, signed copy) of the COC form shall be placed inside a large Ziploc-type bag and taped inside the lid of the shipping cooler. If multiple coolers are sent but are included on one COC form, the COC form should be sent with the cooler containing vials for VOC analysis or the cooler with the air bill attached. The air bill should then state how many coolers are included with that shipment. An example of a Chain-of-Custody Record form is provided as Attachment C. Once the samples are received at the laboratory, the sample cooler and contents are checked and any problems are noted on the enclosed COC form (any discrepancies between the sample labels and COC form and any other problems that are noted are resolved through communication between the laboratory point-of-contact and the Tetra Tech NUS Project Manager). The COC form is signed and copied. The laboratory will retain the copy while the original becomes part of the samples' corresponding analytical data package.

5.3.1.4 Chain-of-Custody Seal

Attachment D is an example of a custody seal. The Custody seal is an adhesive-backed label. It is part of a chain-of-custody process and is used to prevent tampering with samples after they have been collected in the field and sealed in coolers for transport to the laboratory. The COC seals are signed and dated by the sampler(s) and affixed across the lid and body of each cooler (front and back) containing environmental samples (see SOP SA-6.1). COC seals may be available from the laboratory; these seals may also be purchased from a supplier.

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 5 of 12
	Revision 2	Effective Date 09/03

5.3.1.5 Geochemical Parameters Log Sheets

Field Analytical Log Sheets are used to record geochemical and/or natural attenuation field test results.

5.3.2 Hydrogeological and Geotechnical Forms

5.3.2.1 Groundwater Level Measurement Sheet

A Groundwater Level Measurement Sheet must be filled out for each round of water level measurements made at a site.

5.3.2.2 Data Sheet for Pumping Test

During the performance of a pumping test (or an in-situ hydraulic conductivity test), a large amount of data must be recorded, often within a short time period. The Pumping Test Data Sheet facilitates this task by standardizing the data collection format for the pumping well and observation wells, and allowing the time interval for collection to be laid out in advance.

5.3.2.3 Packer Test Report Form

A Packer Test Report Form must be completed for each well upon which a packer test is conducted.

5.3.2.4 Boring Log

During the progress of each boring, a log of the materials encountered, operation and driving of casing, and location of samples must be kept. The Summary Log of Boring, or Boring Log is used for this purpose and must be completed for each soil boring performed. In addition, if volatile organics are monitored on cores, samples, cuttings from the borehole, or breathing zone, (using a PID or FID), these readings must be entered on the boring log at the appropriate depth. The "Remarks" column can be used to subsequently enter the laboratory sample number, the concentration of key analytical results, or other pertinent information. This feature allows direct comparison of contaminant concentrations with soil characteristics.

5.3.2.5 Monitoring Well Construction Details Form

A Monitoring Well Construction Details Form must be completed for every monitoring well, piezometer, or temporary well point installed. This form contains specific information on length and type of well riser pipe and screen, backfill, filter pack, annular seal and grout characteristics, and surface seal characteristics. This information is important in evaluating the performance of the monitoring well, particularly in areas where water levels show temporal variation, or where there are multiple (immiscible) phases of contaminants. Depending on the type of monitoring well (in overburden or bedrock, stick-up or flush mount), different forms are used.

5.3.2.6 Test Pit Log

When a test pit or trench is constructed for investigative or sampling purposes, a Test Pit Log must be filled out by the responsible field geologist or sampling technician.

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 6 of 12
	Revision 2	Effective Date 09/03

5.3.2.7 Miscellaneous Monitoring Well Forms

Monitoring Well Materials Certificate of Conformance should be used as the project directs to document all materials utilized during each monitoring well installation.

The Monitoring Well Development Record should be used as the project directs to document all well development activities.

5.3.2.8 Miscellaneous Field Forms - QA and Checklists

Container Sample and Inspection Sheet should be used as the project directs each time a container (drum, tank, etc.) is sampled and/or inspected.

QA Sample Log Sheet should be used at the project directs each time a QA sample is collected, such as Rinsate Blank, Source Blank, etc.

Field Task Modification Request (FTMR) will be prepared for all deviations from the project planning documents. The FOL is responsible for initiating the FTMRs. Copies of all FTMRs will be maintained with the onsite planning documents and originals will be placed in the final evidence file.

The Field Project Daily Activities Check List and Field Project Pre-Mobilization Checklist should be used during both the planning and field effort to assure that all necessary tasks are planned for and completed. These two forms are not a requirement but a useful tool for most field work.

5.3.3 Equipment Calibration and Maintenance Form

The calibration or standardization of monitoring, measuring or test equipment is necessary to assure the proper operation and response of the equipment, to document the accuracy, precision or sensitivity of the measurement, and determine if correction should be applied to the readings. Some items of equipment require frequent calibration, others infrequent. Some are calibrated by the manufacturer, others by the user.

Each instrument requiring calibration has its own Equipment Calibration Log which documents that the manufacturer's instructions were followed for calibration of the equipment, including frequency and type of standard or calibration device. An Equipment Calibration Log must be maintained for each electronic measuring device used in the field; entries must be made for each day the equipment is used or in accordance with the manufacturer's recommendations.

5.4 Field Reports

The primary means of recording onsite activities is the site logbook. Other field notebooks may also be maintained. These logbooks and notebooks (and supporting forms) contain detailed information required for data interpretation or documentation, but are not easily useful for tracking and reporting of progress. Furthermore, the field logbook/notebooks remain onsite for extended periods of time and are thus not accessible for timely review by project management.

5.4.1 Daily Activities Report

To provide timely oversight of onsite contractors, Daily Activities Reports are completed and submitted as described below.

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 7 of 12
	Revision 2	Effective Date 09/03

5.4.1.1 Description

The Daily Activities Report (DAR) documents the activities and progress for each day's field work. This report must be filled out on a daily basis whenever there are drilling, test pitting, well construction, or other related activities occurring which involve subcontractor personnel. These sheets summarize the work performed and form the basis of payment to subcontractors. The DAR form can be found on the TtNUS intranet site.

5.4.1.2 Responsibilities

It is the responsibility of the rig geologist to complete the DAR and obtain the driller's signature acknowledging that the times and quantities of material entered are correct.

5.4.1.3 Submittal and Approval

At the end of the shift, the rig geologist must submit the Daily Activities Report to the Field Operations Leader (FOL) for review and filing. The Daily Activities Report is not a formal report and thus requires no further approval. The DAR reports are retained by the FOL for use in preparing the site logbook and in preparing weekly status reports for submission to the Project Manager.

5.4.2 Weekly Status Reports

To facilitate timely review by project management, photocopies of logbook/notebook entries may be made for internal use.

It should be noted that in addition to summaries described herein, other summary reports may also be contractually required.

All Tetra Tech NUS field forms can be found on the company's intranet site at <http://intranet.ttnus.com> under Field Log Sheets.

6.0 **LISTING OF TETRA TECH NUS FIELD FORMS FOUND ON THE TTNUS INTRANET SITE. [HTTP://INTRANET.TTNUS.COM](http://intranet.ttnus.com) CLICK ON FIELD LOG SHEETS**

Groundwater Sample Log Sheet
Surface Water Sample Log Sheet
Soil/Sediment Sample Log Sheet
Container Sample and Inspection Sheet
Geochemical Parameters (Natural Attenuation)
Groundwater Level Measurement Sheet
Pumping Test Data Sheet
Packer Test Report Form
Boring Log
Monitoring Well Construction Bedrock Flush Mount
Monitoring Well Construction Bedrock Open Hole
Monitoring Well Construction Bedrock Stick Up
Monitoring Well Construction Confining Layer
Monitoring Well Construction Overburden Flush Mount
Monitoring Well Construction Overburden Stick Up
Test Pit Log
Monitoring Well Materials Certificate of Conformance
Monitoring Well Development Record

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 8 of 12
	Revision 2	Effective Date 09/03

Daily Activities Record
Field Task Modification Request
Hydraulic Conductivity Test Data Sheet
Low Flow Purge Data Sheet
QA Sample Log Sheet
Equipment Calibration Log
Field Project Daily Activities Checklist
Field Project Pre-Mobilization Checklist

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 9 of 12
	Revision 2	Effective Date 09/03

**ATTACHMENT A
TYPICAL SITE LOGBOOK ENTRY**

START TIME: _____ DATE: _____

SITE LEADER: _____

PERSONNEL: _____

TINUS

DRILLER

SITE VISITORS

_____	_____	_____
_____	_____	_____
_____	_____	_____

WEATHER: Clear, 68°F, 2-5 mph wind from SE

ACTIVITIES:

1. Steam jenney and fire hoses were set up.
2. Drilling activities at well _____ resumes. Rig geologist was _____. See Geologist's Notebook, No. 1, page 29-30, for details of drilling activity. Sample No. 123-21-S4 collected; see sample logbook, page 42. Drilling activities completed at 11:50 and a 4-inch stainless steel well installed. See Geologist's Notebook, No. 1, page 31, and well construction details for well _____.
3. Drilling rig No. 2 steam-cleaned at decontamination pit. Then set up at location of well _____.
4. Well _____ drilled. Rig geologist was _____. See Geologist's Notebook, No. 2, page _____ for details of drilling activities. Sample numbers 123-22-S1, 123-22-S2, and 123-22-S3 collected; see sample logbook, pages 43, 44, and 45.
5. Well _____ was developed. Seven 55-gallon drums were filled in the flushing stage. The well was then pumped using the pitcher pump for 1 hour. At the end of the hour, water pumped from well was "sand free."
6. EPA remedial project manger arrives on site at 14:25 hours.
7. Large dump truck arrives at 14:45 and is steam-cleaned. Backhoe and dump truck set up over test pit _____.
8. Test pit _____ dug with cuttings placed in dump truck. Rig geologist was _____. See Geologist's Notebook, No. 1, page 32, for details of test pit activities. Test pit subsequently filled. No samples taken for chemical analysis. Due to shallow groundwater table, filling in of test pit _____ resulted in a very soft and wet area. A mound was developed and the area roped off.
9. Express carrier picked up samples (see Sample Logbook, pages 42 through 45) at 17:50 hours. Site activities terminated at 18:22 hours. All personnel off site, gate locked.

Field Operations Leader

Subject

FIELD DOCUMENTATION

Number

SA-6.3

Page

10 of 12

Revision

2

Effective Date

09/03

ATTACHMENT B



Tetra Tech NUS, Inc.
661 Andersen Drive
Pittsburgh, 15220
(412)921-7090

Project:

Site:

Location:

Sample No:

Matrix:

Date:

Time:

Preserve:

Analysis:

Sampled by:

Laboratory:

Subject	FIELD DOCUMENTATION	
	Number	Page
	SA-6.3	11 of 12
	Revision	Effective Date
	2	09/03

Subject FIELD DOCUMENTATION	Number SA-6.3	Page 12 of 12
	Revision 2	Effective Date 09/03


ATTACHMENT D

CHAIN-OF-CUSTODY SEAL

Signature _____		CUSTODY SEAL _____
Date _____		Date _____
CUSTODY SEAL _____		Signature _____

APPENDIX B

FIELD FORMS



EQUIPMENT CALIBRATION LOG

PROJECT NAME : _____

INSTRUMENT NAME/MODEL:

SITE NAME:

MANUFACTURER: _____

PROJECT No.:

SERIAL NUMBER:

[illegible]

BORING LOG

Page ____ of ____

PROJECT NAME: _____
PROJECT NUMBER: _____
DRILLING COMPANY: _____
DRILLING RIG: _____

BORING No.: _____
DATE: _____
GEOLOGIST: _____
DRILLER: _____

[illegible]

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks:

Drilling Area
Background (ppm):

Converted to Well: Yes _____ No _____ Well I.D. #: _____

Page 67

Project Site Name: _____

Project No.: _____

☐ Surface Soil
☐ Subsurface Soil
☐ Sediment
☐ Other: _____
☐ QA Sample Type: _____

Sample ID No.: _____

Sample Location: _____

Sampled By: _____

C.O.C. No.: _____

Type of Sample:

☐ Low Concentration
☐ High Concentration

GRAB SAMPLE DATA:			
Date:	Depth Interval	Color	Description (Sand, Silt, Clay, Moisture, etc.)
Time:			
Method:			
Monitor Reading (ppm):			

COMPOSITE SAMPLE DATA:				
Date:	Time	Depth Interval	Color	Description (Sand, Silt, Clay, Moisture, etc.)
Method:				
Monitor Readings (Range in ppm):				

SAMPLE COLLECTION INFORMATION:			
Analysis	Container Requirements	Collected	Other

OBSERVATIONS / NOTES:	MAP:

Circle if Applicable:	Signature(s):
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;">MS/MSD</div> <div style="width: 45%;">Duplicate ID No.:</div> </div>	

Page 01

Project Site Name: _____ Sample ID Number: _____
Project Number: _____ Sampled By: _____
Sample Location: _____ C.O.C. Number: _____
QA Sample Type:
☐ Trip Blank ☐ Rinsate Blank
☐ Source Water Blank ☐ Other Blank _____

SAMPLING DATA:

Date: _____
Time: _____
Method: _____

WATER SOURCE:

☐ Laboratory Prepared ☐ Tap
☐ Purchased ☐ Fire Hydrant
☐ Other _____

**PURCHASED WATER INFORMATION
(If Applicable as Source or Rinsate Water):**

Product Name: _____
Supplier: _____
Manufacturer: _____
Order Number: _____
Lot Number: _____
Expiration Date: _____

**RINSATE INFORMATION
(If Applicable):**

Media Type: _____
Equipment Used: _____
Equipment Type:
☐ Dedicated
☐ Reusable

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatiles	Cool 4°C & HCl		YES / NO
Semivolatiles	Cool 4°C		YES / NO
Pesticide / PCB	Cool 4°C		YES / NO
Metals	Cool 4°C & HNO ₃		YES / NO
Cyanide	Cool 4°C & NaOH		YES / NO

OBSERVATIONS / NOTES:

Signature(s):